# 4. EARTH MAT

A new separate earth mat will be installed at the building edge below natural ground level (1.5m). The earth mat will consist of 70mm² round solid copper bars and will cover and area of at least 4m x 4m. The copper earth bars will form a grid of 400mm x 400mm. All connections will be cad-welded. Two round solid copper bars of 70mm² (the tails) from the mat will be connected to the Main DB earth bars. The tails will be connected at separate positions on the mat with a distance more than 1m apart. The tails will be connected into a separate York box at the mat and connected to a 70mm² single core cable to the Main DB.

# 5. TRANSFORMERS

NA

# 6. STANDBY GENERATOR AND CONTROL PANEL

# 6.1 GENERAL

This Specification covers the supply, delivery, factory testing and complete installation and re-testing on site and handover in full working order of the equipment and all associated equipment.

Full particulars, performance curves and illustrations of the equipment offered must be submitted with the tender. Contractors may quote for their standard equipment, complying as closely as possible with this Specification, but any deviations from the Specification must be fully detailed.

The questionnaire following this Specification must be completed by contractors in all respects.

The Employer reserves the right not to bind itself to accept the lowest or any tender.

Each diesel alternator set called for in this Specification will be used as a Standby Unit for the continuity of electrical power supply to emergency services.

The standby generator will be equal or better to CATTERPILLAR standard.

The following are a summary of the requirements and are additional to the Department of Public Works' standards:

Standby Capacity : 250 kVA

Generator Type : Self excited, static regulated

Brushless

IP rating : Drip proof IP 22

Over speed capacity : 50%

Voltage regulation

11/2% Steady state

: 1% No Load to Full Load

Time

: Maximum time to "full on load" from time of mains failure: 15 Seconds (70% load) and 19 Seconds

(Full load).

Frequency

: 50Hz

Voltage MV

: 11kV, 3 Phase

Voltage LV

: 400V, 3 Phase

Fuel tank

: Install a new free standing fuel tank with a capacity to feed the standby generator for a period of 16 hours at full load. The contractor will be responsible to supply and install new fuel line between the tank and the Standby Generator. The fuel line will be of adequate approved material, diameter and be installed with brackets as required by the generator manufacturers. Automatic fuel cut-off must be installed during fault and emergency situations according to ISO3046/1, AS2789, DIN6271 and BS5514.

The contractor to supply enough fuel for commissioning tests (At least 3 hours running time) and the re-filling of the fuel tank to full capacity after commissioning.

Additional equipment

: Heavy duty air cleaner

: Air pre-cleaner

Battery chargers

Battery racks

: Charging alternators

: A single set of chop-over contactors (1 x N/O & 1 x N/C) and coupler contactor (1 x N/C) each rated at 800 Amps and installed in the newly supplied standby generator panel.

: The following Circuit Breakers feed the Low voltage.

Standby Panel

: Main feed to Standby Panel: 800A

# 6.2 REQUIREMENTS

The set shall be fully automatic, i.e. it shall start when any one phase of the main supply fails, and shall shut down when the normal supply is reestablished. The set shall be capable of delivering the specified output continuously under the site conditions mentioned below, without overheating. The engine shall be capable of delivering an output of 100% of the specified output for 2 hour in any period of 3 hours consecutive running.

# 6.3 BASE REQUIREMENTS

The engine and alternator of the set shall be built together on a common Simplex type frame, which will have anti-vibration mountings/pads between the frame and concrete floor. The set shall be placed direct on a concrete floor.

# 6.4 OUTPUT AND VOLTAGE

Output voltage

: 400/231V

Frequency

: 50 Hz

# 6.5 DERATING

The engine must be de-rated for the site conditions as set out.

The de-rating of the engine for site conditions shall be strictly in accordance with B.S.S. 5514 of 1977 as amended to date. Any other methods of de-rating must have the approval of the Engineer and must be motivated in detail. Such de-rating must be guaranteed in writing and proved by the successful contractor at the site test.

# 6.6 DELIVERY & REMOVAL OF EQUIPMENT

Deliver to site and install. The generators must be lifted with a crane over a 2.4m high wall into a space in front of the generator room of  $4.5 \times 4.0 \text{ m}$  approximate. It must be then moved into the generator room with dimensions of  $4.5 \text{ m} \times 6 \text{m}$  approximate. The existing door opening is  $1.5 \text{ m} \times 2.1 \text{ m}$  high approximate.

# 6.7 ENGINE

The engine shall be a four stroke, full compression ignition, direct injection and of the readily available type industrial rated type diesel engine.

The engine shall comply with the requirements laid down in B.S.S. 5514 and must be of the direct injection, compression ignition type, running at a speed not exceeding 1 500 r.p.m.

The engine shall be amply rated for the required electrical output of the set when running under the above mentioned site conditions. The starting period for either manual or automatic switching-on until the taking over by the generating set, in one step, on a load equal to the specified site electrical output, shall not exceed 15 seconds.

#### 6.8 STARTING AND STOPPING

The engine shall be easily started from cold, without the use of any special ignition devices, under summer as well as winter conditions, against full load.

Contractors must state what arrangements are provided to ensure easy starting in cold weather. Full details of this equipment must be submitted. In the case of water-cooled engines, any electric heaters shall be thermostatically controlled. The electrical circuit for such heaters shall be taken from the control panel, and must be protected by a suitable circuit breaker.

An electric starter motor must be fitted to the engine.

Besides the automatic starting and stopping, provision must be made on the control board for manual starting and stopping of the set.

## 7. CABLE SLEEVE PIPES

Where cables cross under roadways, other services and where cables enter buildings, the cables shall be installed in asbestos-cement pipes or earthenware pipes. When otherwise specified or agreed upon, PVC sleeves maybe approved.

The electrical contractor will be responsible for all excavations, installation of sleeves, backfill and making neat of all.

The ends of all sleeves shall be sealed with a non-hardening watertight compound after the installation of cables. All sleeves intended for future use shall likewise be sealed.

#### 8. NOTICES

The Contractor shall issue all notices and make the necessary arrangements with Supply Authorities, the Postmaster-General, S.A. Transport Services, Provincial of National Road authorities and other Authorities as may be required with respect to the installation. The Contractor will be held responsible for damage to any existing services brought to his attention by the relevant authorities and will be responsible for the cost of repairs.

# 9. ELECTRICAL EQUIPMENT

All equipment and fittings supplied must be in accordance with the approved quality specification, suitable for the relevant supply voltage and frequency and must be approved by the Consultant's representative.

#### 10. DRAWINGS

The drawings generally show the scope and extent of the proposed work and shall not be held as showing every minute detail of the work to be executed.

The position of power points, switches and light points that may be influenced by built-in furniture must be established on site, prior to these items being installed.

The contractor will supply a complete set of "As Built" drawings at completion of the contract. This will be handed in with the Operational and Maintenance manuals.

# 11. BALANCING OF LOAD

The Electrical Contractor is required to balance the load as equally as possible over the multiphase supply. When Balancing of lads are not required, the specific phase to which a load must be connected will be indicated on the drawings.

#### 12. WORK SEQUENCE

#### in

# 13. SUPERVISION

The work shall at all times, for the duration of the contract be carried out under the supervision of a skilled and competent representative of the contractor, who will be able and authorised to receive and carry out instructions on behalf of the contractor. A sufficient number of workmen shall be employed at all times to ensure satisfactory progress of the work.

# 14. SUPPLY OF MATERIAL

The contractor shall be responsible to supply all the required material for the complete installation.

# 15. SERVICE CONDITIONS

All plant shall be designed for the climatic conditions appertaining to the service.


# 16. SWITCHES AND SOCKET OUTLETS

All switches will be supplied with a metal cover plate with brush aluminium or stainless steel finishing unless other wise specified in the Bill of Materials.


The following descriptions are as supplied in the table below:

BR	100 x 50mm Galvanized steel box, flush for biometric reader, to be installed as per drawing.
ML	65mm diameter galvanized round box for magnetic lock, to be installed as per drawing.
ACC	100 x 100mm Galvanized steel box, flush for air conditioner control unit, to be installed as per drawing.
ROOF CON	Roof consul consisting of dedicated 15A power socket outlet, composite video outlet (RCA), video outlet (15pin) and Usb port and 2 x data outlets. Typical housing Oline Double FFD3 All switches and outlets to b ULTI as supplied by Schneider.
DESK CON	Desk consul consisting of dedicated 15A power outlet, composite video outlet (RCA), video outlet (15pin), Usb port and 2 x data outlets. Typical housing Oline Double FFD3 All switches and outlets to b ULTI as supplied by Schneider.
IB	Inspection box to be installed underneath desks at lecture halls to connect the desk and roof consuls. To be galvanized steel 210 x 285 x 80mm, with lid. Typical: O-Line Power box.
#	Double channel power skirting, 165 x 55mm. Metal with 2 covers, light hammer tone grey. Typical: O-Line MS2.
(F)	Fire detection sensor
BG	Break glass

Wiring will be done in trays and connections to socket outlets as in detail below. Provide the necessary glands for entry to trays.




The detail for the installation of the roof and desk consoles is given in the picture below.



# 17. LIGHT FITTINGS AND LAMPS

Light circuits will be wired in channels as per the following detail.



The minimum 80 lux for all levels of the car park, 300 lux for the store areas and an average of 500 lux for the office areas will be adhered to.

All fittings to be supplied by the electrical contractor shall have the approval of the Department. Incandescent lamps shall bear the approved mark of the S.A.B.S. and shall have the British light centre length.

The following fittings will be supplied and installed as per the Bills of Materials:

Fluorescent: 1.5m, double tube x 58W, open channel, electronic ballast, surface mounted with industrial wing (dimensions: 1531 x 73 x 87mm)	- <u>(</u> -
Fluorescent: 1.5m, double tube x 36W, vandal and tampered proof, electronic ballast, with a build in PL9 night lite, surface mounted, with 1 x 36W battery back-up (dimensions: 1531 x 73 x 87mm)	<b>=0=</b>
Fluorescent: 1.5m, double tube x 36W, vandal and tampered proof, electronic ballast, surface mounted, with 1 x 36W battery back-up dimensions: 1531 x 73 x 87mm)	
Fluorescent: 1.5m, double tube x 58W, waterproof IP65, electronic pallast, surface mounted (dimensions: 1570 x 160 x 110)	G
Bulkhead: rectangular 155mm (w) x 324mm (l) x 122mm (h), 2 x PL18 220V, matt white, electronic ballast, surface mounted	C
Floodlight: wide beam 400W mercury vapour, stirrup mounted, tandard aluminuim complete with hot dipped galvanished mounting ccessories for wall mounting and 5A circuit breaker (dimensions: 50 x 425 x 175mm)	<u> </u>
sulkhead: decorative round 280mm (d) x 104mm (h), 2 x PL9 20V, matt black, electronic ballast, surface mounted	<u>@</u> .,
ulkhead: decorative round bulkhead, 2 x PL9 220V, matt white, ectronic ballast, surface mounted - bathrooms	0.
luorescent: 1.2m, double tube x 36W, waterproof IP65, AMPERED proof electronic ballast, surface mounted (dimensions: 200 x 160 x 110)	
ulkhead: rectangular 440mm (w) x 320mm (l) x 217mm (h), 2 x L9, matt black , with wire guard, surface mounted	E
mergency exit lighting: single sided illuminated with battery back o ceiling mounted bracket. (down arrow with man running) imensions: 330 x 145 x 46 mm)	<b>(E)</b>

Emergency exit lighting: single sided illuminated with battery back up, surface mounted bracket. (horizontal arrow - right, man and stairs, green) (dimensions: 330 x 145 x 46mm)	<b>(A)</b>
Down lighter: cut-out = 170mm, 1 x 70W 220V, matt white, electronic ballast, flush mounted	A

•

# 17.1 TUBULAR FLUORESCENT LAMP LUMINARIES

#### 17.1.1 SCOPE

This specification covers the requirements for fluorescent luminaries using tubular fluorescent lamps for general indoor use. The type of luminaries covered is open-channel, industrial, decorative and recessed types and includes luminaries with one or more lamps with standard wattage ratings as specified in the Bills of Materials.

#### 17.1.2 **GENERAL**

Luminaries, associated equipment and control gear shall be new and unused and shall be supplied complete with lamps, control gear, diffusers, mounting brackets, etc. and shall be delivered to site in a protective cover. Lamps shall be delivered separately.

# 17.1.3 STANDARDS

The following standard specifications of SABS shall apply to the luminaries' specifications:

SANS 1119	Interior Luminaries for
	fluorescent lamps.
SANS 1250	Capacitors for use with
1	fluorescent and other
	discharge lamp ballast's
SANS 890	Ballast's for fluorescent lamps
SANS 1464	Safety of Luminaries
SANS 1479	Glow starters for fluorescent
	lamps
SANS IEC 400	Lamp holders for tubular
	fluorescent lamps
SANS 1041	Tubular fluorescent lamps for
	general service
SANS 1247	Coatings applied by the
	powder-coating process
SANS 783	Baked enamels
SANS 0142	Wiring of premises
SANS 1464	Safety
SANS 890	Noise levels
SANS 1222	Protection

#### 17.1.4 FIXING

The luminaries shall be suitable for mounting in or against ceilings as described below:

All holdings will be galvanized, cadmium plated or stainless steel and completely corrosion proof.

The holding screws will not be longer than 30mm and not shorter than 20mm.

At least four fixing screws per luminaries will be supplied and installed.

The position of any other equipment or material that could be damaged when fixing luminaries must be established prior to fixing any luminaries.

Luminaries will be installed completely parallel, straight or/and horizontal at all times.

# 17.1.5 ENVIRONMENTAL

The luminaries will be suitable to operate in ambient temperatures between -10°C and +40°C.

# 17.1.6 SAFETY

The luminaries will bear the SANS 1464 safety mark.

#### 17.1.7 NOISE

Noisy ballasts will not be accepted and shall be replaced at no cost. All ballasts shall comply with the requirements of the latest edition of SANS 890, Part 1.

# 17.1.8 GENERAL TECHNICAL REQUIREMENTS

#### **GENERAL**

Tubular fluorescent lamp luminaries shall comply fully with SANS 1119 and all amendments as well as the additional requirements of the specification. Luminaries shall bear the SABS mark.

The client reserves the right to have samples of luminaries offered tested by the SABS for compliance with SANS 1119. If sample luminaries are found not to comply with SANS 1119 the cost of such tests shall be borne by the tenderer.

#### CONSTRUCTION

Luminaries shall consist of a ventilated body manufactured of either cold rolled sheet steel not less than 0.8mm thick or injection moulded flame retardant GRP, suitably braced or stiffened to prevent distortion. The body shall be of sufficient strength for the mounting of the entire luminaries.

The luminaries shall be designed to accommodate the control gear, wiring, lamp holders and where applicable, the diffuser and reflectors. It shall be possible to reach the control gear without disconnecting wiring or removing the luminaries.

Except for mounting holes and/or slots and the required openings in air-return luminaries, the back of the body channel shall be closed over the full length of the luminaries.

Suitable knockouts shall be provided in the rear or both ends of the luminaries body for wire entry.

All components, including screws, bolts and nuts utilised in the construction of the luminaries or fixing of its components, shall be corrosion proof. Cadmium plated or stainless steel materials are preferred.

The lamp compartment and body will have a degree of IP 65 protection as per SANS 1222.

# **INTERNAL WIRING**

Luminaries shall be completely wired internally. Conductors shall be protected with grommets where they pass through holes in the body.

The wiring shall be totally enclosed to prevent any possible contact with live components while changing lamps.

The conductor insulation shall be rated to withstand the temperature inside the luminaries body without deterioration.

The wiring shall terminate on a suitable terminal block having screw down plates bearing on the wires.

Terminal where screws bear down directly on wires will not be acceptable.

An earth terminal, welded to the luminaries body, shall be provided where applicable. To ensure good earth continuity the earth terminal shall not by spray painted. The earth conductor shall be connected to this terminal by means of a crimped lug.

#### LAMP HOLDERS

Lamp holders shall preferably be of twist-lock type. The mounting of the holders shall be able to accommodate the tolerances experienced in the length of lamps and in the manufacture of luminaries.

#### **CONTROL GEAR**

The control fear, ballasts, capacitors and starters shall be designed and manufactured to suit the control circuitry adopted. All luminaries shall operate on a switch-start basis.

Ballasts shall comply with SANS 890 and SANS 891, suitable for operation on 220V to 250V 50Hz supplies.

Ballasts shall further be suitable for the particular luminaries to ensure that the thermal limits specified in paragraph 3.5 of SANS 1119 are not exceeded.

Starters shall comply with SANS 1479 or with BS 3772 if it is not covered by SANS 1479. Starters with metal cans shall contain integral earthing facilities to earth the can upon insertion.

Starters shall be accessible from the outside of the luminaries, and the replacement of the starter shall not necessitate the removal of lamps.

Capacitors shall comply with SANS 1250. The power factor of each complete fitting shall be corrected to at least 0,85.

# **LAMPS**

Fluorescent lamps shall be suitable for the control circuitry used. Lamps shall comply with SANS 1041.

Only Osram & Philips branded lamps will be accepted on this project.

If no colour is specified, the light colour shall correspond to colour 2 (4 300K) of SANS 1041.

Lamps of the same colour shall be provided for an entire installation unless specified to the contrary.

There shall be no visible flicker in the lamps and lamps shall readily strike when switched on. Faulty lamps or ballasts shall be replaced at no cost.

#### PHOTOMETRIC DATA

Photometric data sheets of the luminaries as prepared by a laboratory, that complies with SABS requirements, shall be submitted with the luminaries.

# TECHNICAL INFORMATION

The tenderer shall include full technical particulars regarding the luminaries offered with the tender.

#### **RECESSED LUMINARIES**

Recessed luminaries shall be suitable for mounting in the ceiling structure specified in the project specification.

The diffuser or reflector shall fit flush with the ceiling and the only visible portion shall be the reflector of diffuser.

Should the luminaries be so designed that a surrounding frame is visible, then this frame shall be manufactured of anodized aluminium. The frame shall form a neat trim with the ceiling. The corners of the surrounding frame shall be mitered and reinforced.

#### LOW-BRIGHTNESS LUMINARIES

The luminaries shall be provided with an aluminium louvre with V- shaped longitudinal vanes and extruded stepped cross-shielding plates.

Louvres shall be constructed from high purity aluminium (99,98%), chemically brightened and anodized.

The total Light Output Ratio (LOR) shall be 62% or better. In the plane between 60 and 90 from the vertical, the LOR shall be below 3%.

#### LOW GLARE LUMINARIES

The luminaries shall be provided with a die-formed, bright-anodized high-purity aluminium (99.98%) louver with parabolic reflecting surfaces in both directions.

The total LOR shall be 62% or better. In the plane between 60 and 90 from the vertical, the LOR shall be less than 1.3%.

# LUMINARIES FOR USE IN AREAS WITH VISUAL DISPLAY TERMINALS

The luminaries shall have anodized specular louvers to provide the brightness control required for this type of application.

At angles between 60 and 90 from the vertical the luminance shall not exceed 200cd/m2.

At above angles the LOR shall be less than 0.6%. At angle between the vertical and 60 the LOR shall be 61% or better.

# 17.2 BULKHEAD LIGHT FITTINGS

# 17.2.1 SCOPE

The specification is for all bulkhead fittings to be used on this project.

# 17.2.2 **GENERAL**

Luminaries, associated equipment and control gear shall be new and unused and shall be supplied complete with lamps, control gear, diffusers, mounting brackets, etc. and shall be delivered to site in a protective cover. Lamps shall be delivered separately.

# 17.2.3 STANDARDS

The following standard specifications of the South-Africa Bureau of Standards shall apply to this luminary's specification:

912	
SANS 1119	Interior Luminaries for
	fluorescent lamps.
SANS 1250	Capacitors for use with
1	fluorescent and other
	discharge lamp ballast's
SANS 890	Ballast's for fluorescent lamps
SANS 1464	Safety of Luminaries
SANS 1479	Glow starters for fluorescent
	lamps
SANS IEC 400	Lamp holders for tubular
	fluorescent lamps
SANS 1041	Tubular fluorescent lamps for
	general service
SANS 1247	Coatings applied by the
	powder-coating process
SANS 783	Baked enamels
SANS 0142	Wiring of premises
SANS 1464	Safety
SANS 890	Noise levels
SANS 1222	Protection

# 17.2.4 PHYSICAL AND ENVIRONMENTAL REQUIREMENTS

N/A

#### 17.2.5 AREAS OF APPLICATION

The luminaries are attended for outdoor as well as indoor use.

#### 17.2.6 FIXING

The luminaries shall be suitable for mounting in or against ceilings as described below:

All holding screws will be galvanised, cadmium plated or stainless steel and completely corrosion proof.

The holding screws will not be longer than 30mm and not shorter than 20mm.

At least four fixing points per luminaries must be established.

The position of any other equipment of material that could be damaged when fixing luminaries must be established prior to fixing any luminary.

# 17.2.7 ENVIROMENTAL

The luminaries shall be suitable for operation in ambient temperatures between -10 C and +45 C.

#### 17.2.8 SAFETY

The luminary shall bear the SANS 1464 safety mark.

#### 17.2.9 NOISE

Noisy ballasts will not be accepted and shall be replaced at no cost. All ballasts shall comply with the requirements of the latest edition of SANS 890, Part 1.

#### 17.2.10 GENERAL TECHNICAL REQUIREMENTS

#### **GENERAL**

The bulkhead luminaries shall be suitable for surface mounting on a ceiling or wall and shall allow for surface conduits to enter on all sides.

#### CONSTRUCTION

The luminaries shall consist of a high-pressure die cast aluminium base and a structured opaque high impact acrylic diffuser.

It shall be rectangular in shape and shall be designed to operate compact fluorescent lamps up to  $2 \times 26W$  (staircases) or shaped as per the attached pamphlets for outside and bathroom lighting.

The diffuser shall be fixed to the body by four stainless steel Allen head screws. A silicon sponge gasket shall be fitted into a groove on the diffuser.

Four mounting holes shall be provided in the base for securing the diffuser onto the base.

All internal wiring shall be Teflon coated with protective sleeving to prevent damage by possible abrasion.

Main connections shall be by means of a suitable screw terminal block with a wire clamping contact.

All screws, bolts and metals shall be stainless steel or of non-corrosive material.

A luminary shall consist of a ventilated body manufactured of either cold rolled sheet steel not less then 0.8mm thick or injection moulded flame retardant GRP, suitably braced or stiffened to prevent distortion. The body shall be of sufficient strength for the mounting of the entire luminary

#### LAMP HOLDERS

Lamp holders shall preferably be of twist-lock type. The mounting of the holders shall be able to accommodate the tolerances experienced in the length of lamps and in the manufacture of luminaries.

#### **CONTROL GEAR**

The control gear shall be incorporated inside the separate control gear compartment and be mounted on a removable gear tray.

It shall be suitable for operation with the specified rating of the lamp on a 230V + 3%-10% 50Hz single-phase system.

All control gear components shall be removable and bear the relevant SABS mark.

The luminaries shall be power factor corrected to a minimum of 0.85.

Ignitors, where applicable, shall be of the superposed pulse type.

The luminaries shall be able to withstand ambient temperatures of at least 45 C. without resulting in any electrical or mechanical component exceeding its maximum allowed operating temperature.

The lamp compartment and body will have a degree of IP 65 protection as per SANS 1222.

#### LAMPS

Only Osram & Philips branded lamps will be accepted on this project.

If no colour is specified, the light colour shall correspond to colour 2 (4 300K) of SANS 1041.

Lamps of the same colour shall be provided for an entire installation unless specified to the contrary.

There shall be no visible flicker in the lamps and lamps shall readily strike when switched on. Faulty lamps or ballasts shall be replaced at no cost.

#### **TECHNICAL INFORMATION**

The Tenderer shall include full technical particulars regarding the luminaries offered with the tender.

#### **EMERGENCY EXIT INDICATORS**

Except for the following changes, all emergency exits will be indicated with the same Bulkhead fitting as specified above:

The high impact acrylic diffuser will be white.

The word "EXIT" will be indicated on the front of the diffuser and will be at least 60mm in height.

The colour of the script will be signal red.

The quality of the script will be such that it is engraved and will not be of the sticker type.

#### **BATTERY BACK-UP UNITS**

Where indicated on the attached drawings, bulkhead fittings will be fitted with battery back-up units with the following specifications:

The units must have self-testing facilities on a weekly basis and full functional test on a monthly basis.

It must have a one-hour standby facility with at least 18% of the normal light output.

It will have an external lamp, indicating the following:

Mains on and system in working order.
Battery voltage low.
Battery voltage too high.
Low capacity battery.
Bad lamps.
No mains.

## 18. EARTHING AND BONDING

The Contractor will be responsible for all earthing and bonding of the building and installation; the earthing and bonding is to be carried out strictly to the specification and to the satisfaction of the Department's representative.

Connection from the main earth bar on the main board must be made to the cold water main, the incoming service earth conductor, if any and the earth mat or other local electrode by means of 12mm x 1,6mm solid copper strapping of 16mm<sup>2</sup> stranded (not solid) bare copper wire or such conductor as the Department's representative may direct. Main earth copper strapping where installed below 3m from ground level, must be run in 20mm diameter conduit securely fixed to the walls.

All other hot and cold water pipes shall be connected with 12mm x 0,8mm perforated for solid copper strapping (not conductors) to the nearest switchboard. The strapping shall be fixed to the pipe work with brass nuts and bolts and against walls with brass screws at 150mm centers. In <u>all cases</u> where metal water pipe, down pipes, flues, etc., is positioned within 1,6m of switchboards an earth connection consisting of copper strapping shall be installed between the pipe work and the board. In vertical building ducts accommodating both metal water pipes and electrical cables, all the pipes shall be earthed at each distribution board.

Where service connections consist of overhead conductors, all metal parts of roofs, gutters and down pipes shall be earthed. One bare 10 mm² copper conductor shall be installed over the full length of the ceiling void, fixed to the top purloin and connected to the main earth conductor and each switchboard. The roof and gutters shall be connected at 15 m intervals to this conductor by means of 12 mm x 0,8 mm copper strapping (not conductors) and galvanized bolts and nuts. Self-tapping screws are not acceptable. Where service connections consist of underground supplies, the above requirements are not applicable.

A separate earth connection shall be supplied between the earth bush-bar in each subdistribution board and the earth bush-bar in the Main Switchboard. These connections shall consist of bare or insulated stranded copper conductors installed along the same routes as the supply cables or in the same conduit as the supply conductors. Alternatively armored cables with earth continuity conductors included in the armoring may be utilized where specified or approved.

An earth conductor shall be installed in all non-metal flexible conduit. This earth conductor shall not be installed externally to the flexible conduit but within the conduit with the other conductors. The earth conductor shall be connected to the earth terminals at both ends of the circuit.

Where non-metallic conduit is specified or allowed, the installation shall comply with the Department's standard quality specification for "conduit and conduit accessories."

Standard copper earth conductors shall be installed in the conduits and fixed securely to all metal appliances and equipment, including metal switch boxes, socket-outlet boxes, draw-boxes, switchboards, luminaries, etc. The securing of earth conductors by means of self-threading screws will not be permitted.

# 19. INTERRUPTIONS OF ELECTRICAL SUPPLY

All interruptions of the electrical supply that may be necessary for the execution of the work will be subject to prior arrangement between the Contractor and the University.

# 20. REGULATIONS AND CODES

The complete electrical installation shall be carried out in full compliance with the Wiring Code and with any Regulations or Codes of Practice in force or adopted in the area in which the contract is to be carried out. Tenderers shall familiarize themselves with all such Regulations or Codes before finalizing their prices; no price variations to the contract based on lack of knowledge or such Regulations or Codes will be allowed.

# 21. CONDUIT AND WIRING

Conduit will be PVC 20mm or 25mm with SABS markings. Conduit will be fixed with raised saddles to ensure that the conduit is horizontal at the roof at all times and does not lift at entry level. Saddles will be installed at not more than 1000mm apart

# 22. CABLE TRAYS

Cable ladder" cable trays shall be used for all new cables in the ceiling void and service ducting. Typical OL55 and OL76 as per request

Refer to Bill of quantities for detail on withs.

# 22.1 SUSPENSION HANGERS SHALL BE AS FOLLOWS:

All cable trays shall be suspended at intervals of not more than 800mm apart, from the existing roof structure by means of a 300mm or 400mm long P1000 channel, complete with 2 x 1m x 6mm galvanised threaded rods and 2 x preformed hold down saddles, per suspension hanger.

# 22.2 EACH MACHINE SUPPLY POINT SHALL CONSIST OF THE FOLLOWING:

N/A

# 23. CABLES

Note: All LV regularly used cables will be XLPE Insulated PVC bedded SWA PVC sheathed 600/1000V manufactured to SANS 1507-4.

This contract will require the use of temporally cables from the main DB to the three level DB's that will be 4 Core Rubber insulated trailing cables.

The electrical contractor shall allow for the supply and complete installation of all distribution cables as indicated on the drawings, and listed in the Schedule of Cables.

Tenderers must base their tender on the amounts of cable, including earth conductors, as indicated in the Bill of Quantities. During the course of the work the actual lengths will be measured on site and adjustments will be made according to the price per metre length as inserted by the tenderer for the particular cable size concerned.

Tenderers must base their cost for trenching in earth; hard rock on the total quantities as indicated in the Bill of Quantities. The actual quantities, based on the dimensions as specified below for trenches for the applicable number of cables to be laid, will be measured on site during the course of the service and adjustments made according to the price per cubic meter as inserted by the tenderer. Payment for cable trenching having a greater volume than that specified for the purpose will not be considered except where extra excavations are necessary to by-pass obstacles such as water pipes, drains, large boulders etc. In all such instances the amount of the extra excavations must be agreed upon on site between the Engineer and the contractor.

Cables in soil will be buried 1,5m underground. Cables that are attached to roofs or walls will be tied with aluminum strapping (25mm) every 400mm to 100mm cable racks.

The storage, transportation, handling and laying of the cables shall be according to first class practice, and the contractor shall have adequate and suitable equipment and labour to ensure that no damage is done to cables during such operations.

The cable-trenches shall be excavated to a depth of 0,6m deep below ground level and shall be 450mm wide for one to three cables, and the width shall be increased where more than three cables are laid together so that the cables may be placed at least two cable diameters apart throughout the run. The bottom of the trench shall be level and clear and the bottom and sides free from rocks or stones liable to cause damage to the cable.

The contractor must take all necessary precautions to prevent the trenching work being in any way a hazard to the personnel and public and to safeguard all structures, roads, sewage works or other property on the site from any risk of subsidence and damage.

In the trenches made in soft and hard rock the cables shall be laid on a 75mm thick bed of earth and be covered with a 150mm layer of earth before the trench is filled in.

No joints will be allowed in cables.

The laying of cables shall not be commenced until the trenches have been inspected and approved. The cable shall be removed from the drum in such a way that no twisting, tension or mechanical damage is caused and must be adequately supported at intervals during the whole operation. Particular care must be exercised where it is necessary to draw cables through pipes and ducts to avoid abrasion, elongation or distortion of any kind. The ends of such pipes and ducts shall be sealed to approval after drawing in of the cables.

Backfilling (after bedding) of the trenches is to be carried out with a proper grading of the material to ensure settling without voids, and the material is to be tamped down after the addition of every 150mm. The surface is to be made good as required.

On each completed section of the laid and jointed cable, the insulation resistance shall be tested to approval with an approved "Megger" type instrument of not less than 500 V for low tension cables.

Earth continuity conductors are to be run with all underground cables constituting part of a low tension distribution system. Such continuity conductors are to be stranded bare copper of a cross-sectional area equal to at least half that of one live conductor of the cable, but shall not be less than 4mm² or more than 70mm². A single earth wire may be used as earth continuity conductor for two or more cables run together, branch earth wires being brazed on where required.

# 24. LAYING, JOINTING AND MAKING OFF OF ELECTRICAL CABLES

NB: The requirements specified hereafter, are aimed essentially at high tension cable but are also valid for low tension cable, where applicable.

- 24.1 The use of the term "Inspector", includes the engineer or inspector of the Department or an empowered person of the concerned supervising consulting engineer's firm.
- No cable is to be laid before the cable trench is approved and the soil qualification of the excavation is agreed upon by the contractor and inspector.
- 24.3 After the cable has been laid and before the cable trench is backfilled the inspector must ensure that the cable is properly bedded and that there is no undesirable material included in the bedding layer.
- 24.4 All cable jointing and the making off of the cables must only be carried out by qualified experienced cable jointers. Helpers of the jointers may not saw, strip, cut, solder, etc. The cable and other work undertaken by them must be carried out under the strict and constant supervision of the jointer.
- 24.5 Before the contractor allows the jointer to commence with the jointing work or making off of the cable (making off is recognized as half a joint) he must take care and ensure:

that he has adequate and suitable material available to complete the joint properly and efficiently. Special attention must be given to ensure the cable ferrules and cable lugs are of tinned copper and of sufficient size. The length of the jointing lugs must be at least six times the diameter of the conductor,

that the joint pit is dry and that all loose stones and material are removed,

that the walls and banks of the joint pit are reasonably firm and free from loose material which can fall into the pit, that the necessary coffer-dams or retaining walls are made to stop the flow of water into the joint pit,

that the joint pit is provided with suitable groundsheets so that the jointing work is carried out in clean conditions.

that the necessary tents or sails are installed over the joint pit to effectively avert unexpected rainfall and that sufficient light or lighting is provided,

that the necessary means are available to efficiently seal the jointing or cable end when an unexpected storm or cloudburst occurs, regardless of how far the work has progressed,

that the cables and other materials are dry, undamaged and in all respects are suitable for the joint work or making off,

that the heating of cable oil, cable compound, plumbers metal and solder is arranged that they are at the correct temperature when required so that the cable is not unnecessary exposed to the atmosphere and consequently the ingress of moisture ( care must be taken of overheating)

- 24.6 Before the paper insulated cables are joined, they must be tested for the presence of moisture by the cable jointers test. This consists of the insertion of a piece of unhandled insulated impregnated paper tape in warm cable oil heated to a temperature of 130 ± 5 □ C. Froth on the surface of the oil is an indication that moisture is present in the impregnated insulation and the amount of the froth gives an indication of the moisture present.
- 24.7 If the cable contains moisture or is found to be otherwise unsuitable for jointing or making off the inspector is to be notified immediately and he will issue the necessary instruction to cope with the situation.
- The joint or making off of paper insulated cables must not be commenced during rainy weather.
- Once a joint is in progress the jointer must proceed with the joint until it is complete and before he leaves the site.

- 24.10 After the individual cores have been insulated they must be well basted with hot cable oil and again after the applicable separator and/or belt insulation tape is applied before the lead joint sleeve is placed in position.
- 24.11 The lead joint sleeve must be thoroughly cleaned and prepared before it is placed on the cable and must be kept clean during the whole jointing process. Seal the filling apertures of the sleeve with tape until the sleeve is ready for compound filling.
- 24.12 The plumbing joints employed to solder the joint sleeve to the cable sheath, must be cooled off with tallow and the joint sleeve is to be filled with compound while it is still warm. Top up continuously until the joint is completely filled to compensate for the compound shrinkage.
- 24.13 The outer joint box must be clean and free from corrosion. After it has been placed in position it must be slightly heated before being filled with compound. Top up until completely full.
- 24.14 As far as cable end boxes are concerned the requirements as set out above are valid where applicable.

# 25. DISTRIBUTION BOARDS AND CIRCUIT BREAKERS

The electrical contractor shall supply and install the distribution boards as indicated on the drawings. All distribution boards shall comply with the quality specification, and be approved by the Engineer or by the Department's representative.

All DB's as well as both ends of cables will be marked with engraving on aluminum plate.

All distribution boards shall be manufactured according to the detail specifications and drawings, and shall be inspected and approved by the Engineer before installation.

The Engineer shall first approve any other type of distribution board, which may be submitted as an alternative.

All bus bars and lugs shall be insulated, and wiring shall enter the switch gear from the back of the distribution board.

All circuit breakers will be the quality of CBI or better.

#### Quality Specification and Manufacturers:

All switchgear and equipment shall comply with the specification in the document.

# Wiring:

The manufacturers shall internally wire all distribution boards. Wiring between switchgear and busbars shall be done by means of PVC insulated stranded copper conductors, fixed to the busbars with copper lugs, and brass bolts.

Only color coded wiring shall be accepted, e.g.: Red, yellow and blue for phases, and black for neutral.

Wiring colored by means of PVC insulated tape shall not be accepted.

Wiring shall be neatly strapped in a vertical and horizontal manner. All instrument and control wiring shall be 2,5mm<sup>2</sup> PVC insulated copper conductors, and shall be numbered for ease of tracing circuits.

# Color:

The color of all distribution boards shall be light stone and all painting shall be done in accordance with the standard paint specifications in part 3 of this specification.

#### Doors:

Where specified, doors shall be of the removable type.

# Separate Compartments:

Where distribution boards have separate compartments, they shall be separated by means of a metal dividing section, and be equipped with individual removable circuit breaker covers.

# Legend Cards:

Legend cards covered by removable glass or 1.6mm transparent acrylic plastic shall be fitted to the inside of the door of the distribution board and circuits shall be noted on this legend card. Legend cards shall be as follow, for example:

Main - Main Isolator Switch OR Local Isolator Switch (As case

may be ).

L1 - Lights ; Bedroom 1, Bedroom 2 &

Kitchen.

P1 - Plugs ; Bedroom 1, Bedroom 2 &

Kitchen.

ELU1 - Earth leakage unit for plug circuits 1, 2 & 3.

The AS-Build diagrams will be updated and laminated. The laminated prints will be attached at each DB for future use of the client.

# 26. BILLS OF MATERIALS

- This Bill of Quantities forms part of, and must be read in conjunction with the specification.
- No alteration, erasure or addition is to be made in the text of the Bill of Quantities. Should any alteration, erasure of addition be made it will not be recognized but the original wording of the Bill of Quantities will be adhered to.
- 26.3 The Client will check the completed Bill of Quantities and reserves the right to adjust any individual price and to rectify any discrepancy whilst the total tender price as quoted remains unaltered.
- The quantities given in the Bill for cable, cable markers, earth wire laid with cable, overhead conductors, overhead earth wire and excavations cannot be regarded as exact and are subject to measurement on site after completion of the service and adjustments will be made according to the unit rates given in the Bill.

All other quantities will <u>not</u> be measured on site.

In the event of discrepancies between the drawings, specifications and Bill of Quantities the Client shall decide whether the work as executed shall be remeasured on site or whether re-measurement shall be effected from the working drawings only.

#### NOTE:

#### Checking of Cable and Overhead Conductor Lengths

Notwithstanding the fact that the lengths of cables and overhead conductors as given in the Bills of Quantities have been measured from scaled drawings, the contractor shall check such lengths on site before ordering the cable as he will not be paid for excess cable after the completion of the service. Any allowance for off-cuts shall be made in the unit rates. The final measurements shall be based on the nett route length of the cables and overhead lines concerned.

- Where alternative prices for gear of different manufacture are quoted the <u>lowest</u> alternative price for gear to specification must be quoted against the relevant item in the Bill of quantities. The remaining alternative prices must be furnished separately.
- 26.6 The unit prices quoted in the Bill of Quantities must include for such small Installation materials as are required for the complete installation in accordance with the specification.

# 27. X-RAY EQUIPMENT

N/A

# 28. LIFT INSTALLATION

N/A

# 29 FIRE & SMOKE DETECTION

#### 1 Extent of Work

This specification includes the fire & smoke detection system for the complete building

The fire detection system shall be utilized for the control of the automatic gas extinguishing system installed in several areas and the detection of fire in non protected areas.

The Fire Detection system will comply with the SANS 10139-2005 and the BS6266 as amended.

Disaster Recovery Areas will have a stand alone detection panel that will be linked to the master or other detection panels in the building.

The information on the panels will be made available on the MTN corporate LAN.

# 2 Special Notes to Tenderers

1

The fire detection system specified below and shown on the drawings has been designed with the following assumptions:

All detection loops shall be capable of supporting ±100 addressable devices including detectors, sirens, break glass units, isolators, I/O units etc. The conduit layout shall be designed according to these criteria. Should the system offered by the tenderer support more or less devices per loop this should be indicated on the accompanying drawings and the effect thereof clearly stated and included in the tender price.

All sirens will be addressable and will be powered by the system. Thus no provision will be made for separate power supplies or address units to the sirens. Should the items offered require any additional equipment, it should be clearly stated and included in the tender price.

Tenderers shall submit with their tenders all the requirements regarding temperature and humidity control required for the master and remote fire panels, if special environmental conditions are required. Should no special conditions be required, the tenderer shall clearly state this in the covering letter.

Tenderers are allowed to propose alternative designs or technologies than what is described in this specification. These alternatives must however incorporate the design philosophy described in the specification and accompanying drawings.

Tenderers must provide full details, design calculations and the advantages and disadvantages of their alternative proposals with their tender. A detail bill of quantities must also accompany their proposal.

Alternatives will be evaluated at the discretion of the engineer and aspects such as price, technical capabilities etc. will be considered.

## 3 Detection System

## 3.1 General Description

The smoke detection system shall consist of a central control unit (main fire panel) connected to field devices such as control units, detectors, break glass units and fire sirens. All of the above shall be of the analogue addressable type. The high sensitivity aspirating smoke detection systems will be linked to the loop via Input/Output units to ensure that it is addressable. The I/O units for these shall not be measured separately and is seen as part of each HSSD system.

The panel shall be selected at 80% of its capacity in terms of devices for future expansion. The panel will be a 2, 4, 6 or 8 loop panel, depending on the amount of detectors needed.

The main fire panel shall continuously monitor the analogue state of the sensing devices and make all decisions regarding the state of the system. The system shall incorporate self-monitoring and sensor self-test facilities, which will report immediately if any part of the system does not respond correctly:

Alarm management of the system shall be field programmable to enable specific customer requirements to be met. This configuration shall be maintained under power failure conditions for at least 24 hrs.

The main fire panel shall have a front panel consisting of indication LED's, display unit and a control keyboard from which all alarms and programming can be viewed and controlled.

The system shall be of a modular design and shall be able to operate as a stand-alone unit or part of a network if required.

The system shall endeavor to prevent false alarms by using a floating background with automatic level compensation, day/night sensitivity setting and a coincidence mode within and between zones. A soak test facility shall also be available to follow up suspect devices.

#### 4 Standards

All materials, components and equipment used shall be new and of professional quality and shall comply with the requirements of the relevant SANS, BS, DIN or IES specifications.

The latest issues of the following standards form part of this specification:

□□SANS 10139: Code of practice for the prevention, automatic detection and
extinguishing of fires in buildings.  □□BS 5839: Code of practice for the installation and servicing of fire detection and alarm
systems in buildings.  □□BS 6266: Code of practice for fire protection for electronic data processing
installations. □□SANS 10142: Code of practice for the wiring of premises.

Any conflict between the requirements of this specification and any of the above standards shall be referred to the Engineer for a ruling.

Equipment shall be standardized throughout the installation and the number of different assemblies used shall be limited to a minimum. Replacement of assemblies and units on a plug-in basis is regarded as essential to facilitate maintenance and to enable staff to do repairs. It will thus be preferred if the address of all the devices are situated in the base and not the head of the detectors.

All materials and equipment shall be suitable for the conditions on site. These conditions shall include weather conditions as well as conditions under which the materials are installed and used. Should the materials or components not be suitable for use under temporary site conditions then the subcontractor shall, at his own expense, provide protection until these unfavorable site conditions cease to exist.

Samples of all equipment shall, upon request of the Engineer, be submitted for approval before installation is commenced with. All such samples may be retained until completion of the contract.

#### 5 System operation

The system shall be designed to operate with the minimum of operator training. Basic fire alarm functions shall be self-explanatory and the occurrence of a fire or fault alarm shall indicate all relevant information without operator intervention.

In the event of a fire being detected or a break glass unit being activated or upon any other alarm input, an alarm signal shall be raised at the main fire panel. This shall be accomplished by displaying 40 characters of user programmable text, the type of device, zone number, loop number, device number and time and date on the display unit. Audible alarms shall also be activated in the affected fire zones only, programmed relays shall be triggered to turn air conditioning unit off after the second knock, to activate evacuation notices and to release extinguishing gas as required. These controlled outputs shall originate from the main fire panel and shall activate automatically under emergency conditions.

The main fire panel shall be of the analogue addressable type and shall be fully microprocessor controlled. This panel shall be housed in a suitably ventilated, aesthetically pleasing enclosure complete with a key, lock and tamper monitor.

A faulty device, or a detector already in an alarm state, shall not inhibit other detectors in the same zone or line from reporting faults or alarms.

The alarm line shall be monitored for short-circuit, earth fault and open circuit conditions and all faults shall be reported. Alarm indications shall be differentiated from line fault conditions.

The following device states shall be recognized by the fire panel:

Normal conditions:

maintenance alarm caused by performance deterioration of the detector due to contamination;

fire state and fault state.

A fault alarm shall cause the master panel to identify the fault fully by displaying 40 characters of user programmable text, the type of device, zone number, loop number, device number and time and date on the display unit.

If a detector head is removed from the base it shall generate a fault alarm on the panel which can only be reset by replacing the missing device. Removal of a unit shall not restrict the normal operation of the rest of the panel.

Should a detector become contaminated, a maintenance alarm shall be indicated and logged as follows:

The maintenance alarm LED shall be illuminated;

the LCD display shall indicate at least the following information: Type of alarm, Zone number, Device number, Type of device, Time and date, 40 characters of user programmable text;

the panel buzzer shall be activated;

it shall be possible to isolate a zone or a device from the fire panel without affecting any of the other zones or devices of the system. Isolation of devices shall be under software control;

All loop lines shall be provided with suitable surge protection equipment;

the panel shall be equipped with a keypad to enable control and programming of the panel and

this keypad shall normally be disabled and access to this facility shall be protected by means of a software access code.

Indicators LED's to be provided on the faceplate shall, amongst others indicate the following:

Fire conditions; Maintenance alarms:

Faults on the normal power supply to the panel;

Power supply to the panel healthy;

Processor fault;

System fault:

An alarm has been silenced and

A device has been isolate.

It shall be possible to determine the state of each device from the main fire panel.

The main fire panel shall be equipped with backup batteries to maintain the smoke detection system in a fully operational state in the event of a power failure.

The backup batteries shall form an integral part of the main fire panel and it shall be rated to supply emergency power to the system for a continuous period of at least 24 hours.

The main fire panel shall also be equipped with a suitable battery charging circuit to continually maintain the batteries in a fully charged state.

## 6 Detectors, Manual Alarms and Audible & Visual Alarms

#### General

All detectors, break glass units and fire sirens required for this installation shall be of the analogue addressable type. Detectors used shall be approved by at least two of the following internationally recognized laboratories:

Underwriters Laboratories (UL) Verband der Schass Versekerer, Germany VDS British Standards, Great Britian (BS) Underwriters Laboratories, Canada (ULC) Factory Mutual (FM)

### 6 Multi-sensor detectors

All point type detectors shall be of the multi-sensor type incorporating at least two fire sensing elements (optical and heat). Inputs from both sensing elements shall be used and analyzed by the detector's microprocessor with respect to time. On board algorithms should compare historical time readings, time patterns and known fire characteristics to make an alarm decision.

The detector shall continually monitor any changes in sensitivity due to environmental affects of dirt, smoke, temperature, aging and humidity. It shall also be possible to adjust the sensitivity level of each individual detector to suit environmental needs.

The detector shall be equipped with indication LED's which will discriminate between when the detector is in monitoring state (LED flashing). Detectors shall be installed so that the LED is visible from the main entrance to the room or office.

All detectors shall be complete with the necessary communications circuitry required for communication with the master fire panel. The communications circuitry shall form an integral part of the detector and shall be factory fitted by the original manufacturer of the detector.

Each detector shall be supplied with a separate base, which will allow for the removal of the detectors head for maintenance purposes.

The unique address of each detector shall be set by means of a coded plastic card fitted to the detector base or DIP switches in the detector head. Preference shall however be given to detectors that are software programmable.

The detector shall be suitable for operation within the following minimum conditions:

Temperature : -10 to +60 □C Humidity : 0% to 95% RH

Wind resistance: Up to 10 meters per second

The detector and detector base shall be constructed from white, self extinguishing polycarbonate plastic and all smoke entry points must be protected against dust and insect ingress by means of corrosion resistant gauze.

#### 7 Break Glass Units

These units shall be manufactured from red self-extinguishing polycarbonate plastic and shall be suitable for surface mounting over flush mounted round conduit boxes.

These units shall be addressable and shall be complete with the necessary

communications module and an indication LED, which will illuminate when the unit is activated. Means shall be provided to test the individual units without removing the glass front cover of the unit.

The break glass units shall be equipped with a normal open soft contact with a mounting plate and a glass front. The words "IN CASE OF FIRE BREAK GLASS" or any other similar wording approved by the engineer must be clearly marked on front of the unit.

To avoid accidental operation the break glass unit must be fitted with a clear plastic cover. This cover shall be hinged at the top and has to be raised before operation is possible.

#### 8 Audible Alarms

Fire sirens shall comprise an audio frequency generator, an amplifier and a pressure chamber loudspeaker. The unit shall be suitable for surface mounting and shall comply with the following:

Operating voltage: To suit control panel output

Sound level at 1 meter: 100dBA

Duty cycle: 100%

Permissible temperature: -15□C to +50□C

Frequency: Auto switching between high and low tone in

frequencies of 2500 - 3000 Hz

Alarm bells shall be provided in the gas-protected areas as indicated on the tender drawings. Bell alarms shall be 150mm in diameter and shall be

installed on a height of 500mm below ceiling level.

#### 9 Visual alarms

Evacuation signs shall be provided and installed above, or if this is not possible, next to the doors leading out of the gas protected areas, as indicated on the drawing. These signs must not be legible under normal circumstances, but on receipt of the first fire detection signals the sign shall become legible illuminated by a flashing light. The light shall illuminate the sign permanently upon the receipt of the second fire detection signal.

The lettering of the sign shall be at least 40mm in height and the wording shall be as indicated on the drawing.

#### 10 Gas control units (status panels)

These addressable gas control units shall provide the interface between the smoke detection system and the gas extinguishing system.

Each self-contained unit shall have key switches for manual or automatic selection as well as an isolate switch for maintenance. Dual LED's shall indicate automatic or manual mode, gas discharge, isolate, reset and fault statuses.

The control unit shall provide the outputs for the gas release valves, audible and visible alarms.

The control units shall be screened sufficiently for external electrical and electromagnetic interference.

Gas control units shall be incorporated with break glass units in the same panel and will be installed outside the risk area next to the entrance/exit door.

The status of the gas control unit will be relayed to the main control panel.

#### Warning notices

Warning notices shall be provided on the doors leading into the respective gas protected areas, as indicated on the drawing. The notices shall have legible white lettering at least 40mm high, on a red background and the wording shall be as indicated on the drawing. The "Door Caution" Label will read: "THIS IS A FM200 PROTECTED AREA". The label will be on a vellow plastic panel or an anodized aluminum panel.

An Illuminated sign will be visible displayed inside the room. It will read: "FM200 EVACUATE".

#### **Fire Detection Zones**

4.4.1 The system shall be configured to allow separate fire zones with multi sensors for each of the areas as shown on the drawings:

#### 11 Interface to other Systems

The smoke detection system shall provide the control for the gas extinguishing system,

disabling of the air-conditioning system, opening and closing of pressure relief dampers and opening of fire dampers. This interfacing shall be done by means of analogue addressable relays. The system shall also provides 3 sets of dry contacts to the BMS system for a Fire Alarm, Fire Panel alarm and a FM200 discharge Alarm.

#### **12 Control Procedures**

#### Zones with FM200

With the Gas Control Unit in Automatic Mode the release of gas in these areas will work on a double knock basis. The VESDA detectors will not be used to trigger any knocks only as an early warning system to switch off the fresh air units and to trigger alarms. Knocks shall be triggered according to the following procedure:

First knock: First multi-sensor detector detects a fire.

Step 1: Activate alarm bells (inside and outside room) - alert tone.

Step 2: Activate the evacuation warning in a flashing mode inside the affected area.

Second knock: Second multi-sensor detector detects a fire.

Step 3: Activate alarm bells (inside and outside room) - evacuation tone.

Step 4: Activate evacuation signs - flashing mode.

Step 5: Close fire dampers (fresh air).

Step 6: Activate pre-release timer adjustable from 20 to 120 seconds, : After pre-release

Step 7: Switch the evacuation warning to steady mode.

Step 8: Open gas release valve.

Gas Control Unit Switched to Manual Mode:

First Knock: With one detector activated

Step 1: Sound the alarm bell inside the affected area.

Step 2: Activate the evacuation warning in a flashing mode inside the protected area.

Second Knock: With a second detector activated (second knock)

Step 1: Stop the alarm bell and activate the alarm sirens inside and outside the protected area switch the evacuation warning to steady mode. NO GAS RELEASE SHALL TAKE PLACE IN THIS MODE. Gas release in this mode shall only be activated by either switching to the automatic mode or by activating the break glass unit on the gas control unit.

Break Glass Unit Activated

Activation of the break glass unit located on the gas control unit (status panel) shall directly start the steps subsequent to the Second knock of the extinguishing cycle. Manual release of the extinguishing gas shall always be possible by operation of the break glass unit on the gas control unit, regardless of the mode selected (manual or automatic). All alarms shall be reported to the main fire panel.

Zones in areas without FM200 gas:

Should a fire be detected in any of these zones alarm sirens will be set off and the alarms reported at the main fire panel.

#### 12 Testing and training of the end-user

#### Training of end-user:

The contractor shall be responsible to train 3 operators per site. The operators shall be trained to operate the system, to configure the system, to program the fire panels and any other functions required to enable independent operation of the system in all respects.

Three sets of operating and instruction manuals shall be supplied as part of this contract. These manuals shall contain a complete set of as-built drawings shall contain scanned images of the system with detailed descriptions of the operating thereof.

### 13 Testing and Maintenance:

The installation shall be completely tested in accordance with the requirements of NFPA2001.

The engineer shall do spot checks on the performance of the system.

The assistance of the SANS will be obtained when any dispute arises as to the interpretation of results.

The successful tenderer shall be required to supply all equipment and material to test the smoke detection system in its entirety.

Smoke detection system shall be done with the gas control unit in manual mode.

All pages will be laminated and contained in a 4-lever file.

## 14 Cabling, Wiring and Conduit

Unless otherwise specified, wiring shall be carried in conduit throughout. All conduits for the fire detection system shall be provided and installed by the tenderer according to the attached drawings and bill of quantities.

The loop-in system shall be followed throughout and no joints of any description will be permitted.

All cabling between panels and devices will be fire retardant (FR 20) and will be of the multi strand type at least 0.8mm<sub>2</sub>. The cabling will be adequately sized to ensure the minimum power loss in the cable. Cabling between panels and network points will be Fire retardant CAT 5 cable.

# 15 SCHEDULE OF TECHNICAL INFORMATION

The tenderer is required to fill in the information as requested below. Incomplete schedules will render the tender non responsive.

	Yes/No
	163/140
1	O-4:I
Heat/Ionisation/Multi/	Optical
Class Avciass b	
Yes/No	
	Heat/lonisation/Multi/ Class A/Class B Yes/No

#### 30. DATA CABLING SPECIFICATION

#### 1 GENERAL


This specification covers the supply, delivery, installation, testing, commissioning and maintenance during the guarantee period of the Data Cabling Installation covered under the scope of works for the Proposed New Development for the above mentioned building

#### 2 SCOPE OF WORKS

#### **DATA**

This specification covers the supply, delivery, installation, testing, commissioning and maintenance during the guarantee period of the Data Installation, described below, for the Proposed New Development for the above mentioned building.

- Backbone infrastructure in the form of fibre optic cabling to be able to provide the bandwidth specified;
- 2. Backbone telecommunication infrastructure in the form of 100 pair telephone cable cabling to the main administration building;
- 3. Fiber Optic cabling in to the main administration building.
- 4. 42U racks as specified;
- 5. Cat 5e cabling between workstations and patch panels including terminations and plugs in power skirting.
- 6. Patch panels as specified;
- 7. Patch leads to switches
- 8. Labeling as specified.
- 9. Backbone cabling for the security system. (Camera's and readers)



#### 3 MEASUREMENT

The attached Bill of quantities will be a guideline based on this specification and the accompanying drawings. The tenderer is to measure off the drawings for tender purposes, however, on award of contract the contractor shall measure on site quantities needed for installation. The tenderer is to provide a breakdown of his tender on the tender schedule page. The quantities provided can be adjusted and are for information only.

#### 4 FORM OF CONTRACT

NA

#### 5 RELATED WORK BY OTHERS

N/A

#### 6 STRUCTURED CABLING REQUIREMENTS GUIDELINE

#### 6.1 COMPLIANCE

Compliance with the requirements of Molex 25 year System Performance Warranty as well as any additional requirements by Ingcali Consulting Engineers and the owners of the supplied Structured Cabling System, namely.

The acceptance requirements as outlined in this document are mandatory. No variation will be tolerated nor accepted.

The design of the Structured Cabling System shall comply with the requirements of ISO 11801: 2002, and TIA 568-B.

Copper transmission performance shall exceed the specification for a Category 5e link as defined by the above standards.

The Quality Assurance provisions applied to the installation shall be compliant with BS EN 50174-1 and the Molex Premise Networks Global Warranty requirements.

Installation practices shall be compliant with ANSI/NECA/BICSI-568-2006, Standard for Installing Commercial Building Telecommunications Cabling and shall be wholly compliant with the installation practices laid down by Molex Premise Networks.

Installation practices shall also meet all applicable local and national codes, standards and ordinances. Where a conflict exists between these standards, it is the responsibility of the contractor to detail these

conflicts to the client prior to installation commencing.

#### 6.2 DOCUMENT SCOPE

1

This document is intended as a guideline and therefore does not supersede the International Standards on which it is based. The purpose of the document is to provide the contractor with information specific to the implementation of Standards based generic structured cabling as per the requirements of the University Network environment and the support/maintenance thereof.

## 6.3 CONTRACTOR MINIMUM QUALIFICATIONS REQUIREMENTS

- The contractor shall be Molex certified and posses a valid, authenticated Molex Certified Installer or Molex Business Partner certificate in order that the final installation be certified in accordance with the Molex Global Warranty program requirements.
- 2. The contractor shall provide only skilled labour to complete work within the agreed upon time frame.
- The contractor is responsible for the provision of all tools required to full fill his
  installation obligations in accordance with task at hand at his cost. This includes
  specialist tools such as core drills etc.
- 4. By means of the submittal of a quotation and the acceptance of the relevant order number, the contractor is solely responsible for the successful delivery of all documentation pertaining to installed components. E.g. Floor plans, excel sheets and test results to Ingcali Consulting engineers
- 5. The contractor is solely responsible for the thorough pre-quotation inspection and installation evaluation of any given project for which a quotation is submitted. Any over-sites on the part of the contractor are for his account.

# 6.4 100 OHM UTP STRUCTURED CABLING SYSTEMS (SCS) GENERAL PRODUCT CONFORMANCE REQUIREMENTS

- The minimum acceptable cable performance category to be installed on University premises shall be ANSI/TIA/EIA-568-B Category 5e / ISO 11801 Class E (2002) compliant.
- Only cable and connecting hardware specified for the Molex Premise Networks Structured Cabling Solution shall be used.
- 3. All installed components shall be new, complete, in good condition and unused albeit for demonstration purposes.
- 4. All cable reels are to be visually inspected for damage incurred during shipping and transit prior to installation.

 Cable and connecting components found to be damaged or defective prior and during the installation process are to be removed immediately and returned to the supplier at no additional cost to the University.

## 6.5 GENERAL PRODUCT PERFORMANCE REQUIREMENTS

The supplied product shall, once installed, conform to ISO 11801 Class E -2002 electrical characteristics for the purposes of Vendor warranty.

It is expected that installed products be capable of supporting voice and data communications applications and protocols from baseline 56Kbps to ISDN PRI for Analogue and Digital Voice and 10Base T to 1000 Base T for data as per the supported applications of ISO 11801 Class E (2002).

The project will be completed and signed off in 7 different phases by the Contractor and Ingcali Project Manager:

## Phase 1: Category 5e Data cable Installation:

This comprises the horizontal cabling, extending from the patch panel in the rack or cabinet to the consolidation point if applicable and extending to the telecommunications outlet in the work area. This is the part of the horizontal cabling referred to by the standards as the Permanent Link. Both ends of the cable must be terminated to specification and labelled at both ends by means of a legible, permanent label. Where applicable, the portion of the horizontal cable

extending from the patch panel in the cabinet to a consolidation point, intended for future extension to the telecommunications outlet, will be accepted.

Installation	Color of Cat5e
Data	Grey
Telephone	Grey
Camera	Yellow
Biometric readers	Black

## Phase 2: Category 5e Patch leads:

Provide patch leads from the patch panels to the switches and panels

Installation	Color of Cat5e/6
Data	Green

Telephone	Blue
Camera	Yellow
Biometric readers	Black
Special	Red

## Phase 3: The Main Fibre optic Installation:

The installation of a 24 Fiber Single or Multi Mode Heavy Duty Duct Cable cabling, extending from the patch panel in the rack or cabinet to the patch panel in the cabinet in the main administration building.

The installation of a 12 Fiber Single Mode Heavy Duty Duct Cable cabling, extending from the patch panel in the rack in the main administration building to the patch panel in the cabinet in security building.

## Phase 4: The Main Telephone cable Installation:

VOIP system to be integrated with network

## Phase 5: Testing and Labelling:

All outlets will be tested using the appropriate Level 3 test equipment, set to the ISO 11801 Class E Permanent Link setting. All links shall be permanently labelled at both ends of the cable, on the telecommunications outlet fascia and directly above or under the patch panel port as per the labelling requirements set out as specifications in this tender document.

## Phase 6: Warranties:

All test results and floor plans will be submitted to Molex Premise Networks' INSIGHT on-line warranty registration program in electronic format for Warranty purposes. The contractor must furnish the INSIGHT reference number to the Ingcali Project Manager.

### Phase 7: Final Handover:

The contractor will hand over all documentation, including, updated floor plans (as installed), test results and authenticated 25 year Molex System Performance Warranty Certificate to the INGCALI Project Manager, who will then sign off the installation.

## 6.6 GENERAL INSTALLATION PRACTICE REQUIREMENTS

- 1. During the cable installation process, the manufacturer's maximum tensile load recommendations may not be exceeded. This is typically specified as 110N, but should be verified with the manufacturer.
- 2. Cable being pulled in should be handled by no less than two individuals at all times in order to avoid damage to the cable by means of kinks, twisting along its own axis, getting snagged etc. It is recommended that three installers co-operate in the pulling in of any given cable run, one on each end and another in the middle or positioned near any obstructions to feed slack and thus avoid undue stress on the cable.

- 3. Whenever possible cable should be placed into pathways rather than be pulled in under tension.
- 4. Care should be taken not to score conductors during the removal of the outer insulating sleeve of the cable when preparing to terminate pairs.
- 5. Cables should not be subjected to a bend radius of less than 50mm when under tension (during installation) and the bend radius should not be less than 25mm when once installed.
- 6. During the installation process, installers are required to visually inspect cable and connecting hardware components for damage. If such damage is found, e.g. tears in the outer jacket of the cable, severe kinks as identified by white/grey bands of discoloration on cable jacket, these components are to be replaced immediately.
- 7. The installer is to make use of best practices when handling unjacketed conductors. Care is to be taken as not to create pair spread, pair wrapping, pair separation and the re-twisting of pairs.
- 8. Pair twists must be maintained up to the point of termination. Under no circumstances may pair untwist of more that 6 mm be allowed. The sheath should be trimmed such that no more than 25mm of wire may be exposed after termination.
- All cabling shall be clearly labelled at both ends to the rear of the point of termination no more than 100mm from such a termination point.
- 10. All patch panel ports and workstation outlets shall be clearly labelled by means of appropriately secured printed labels (hand written labels are not acceptable).
- 11. All patch and workstation outlet cables shall be clearly labelled by means of an appropriately secured printed label.
- 12. All labeling schemes shall be confirmed with the appropriate representative of Ingcali/Project Manager before being applied.
- The maximum number of screws or bolts as provided for by the design of connecting hardware or SCS components and accessories are to be used without exception.

### 6.7 DUCTING AND SUPPORTING STRUCTURES

 Where support structures are used, such structures are to provide support at a maximum of 1.5 meters along the length of the run as to avoid cable tension as a result of the cumulative weight of such cable acting upon itself at the next point of support.

- The surface of such support structures e.g. Cable hangers will not pose a risk of damaging cable due to sharp edges or angular surfaces which would act against the symmetry of wire pairs within the cable or a risk to installers e.g. Cuts.
- Where cable ties are used, they are to be securely fastened but still permit for cable movement if tugged upon making use of reasonable force.
- 4. Cable ties are to be used at set intervals of 300mm for all cable bundles where exposed to present a uniform appearance. In concealed spaces, the bundles may be tied at nominal 1m intervals.
- 5. Under no circumstances shall any cable/s hang unsupported, vertical runs are to be supported are no greater than 300mm intervals.
- 6. When cable ties are cut; once appropriately fastened around cable bundles, in order to remove protrusions beyond the buckle, the installer will ensure that such a cut is clean and that no sharp edges are created which would damage other cable being pulled past it or injure installers and support staff.
- 7. Cable shall under no circumstances be strapped to PVC electrical conduit or any structures belonging to an unrelated functional unit such as an air conditioning drain pipe as future maintenance by associated maintenance staff may result in damage or removal in order to facilitate work.
- 8. Where purpose-installed conduits are to be used for structured cabling, such conduits may never be filled beyond 40% of capacity and should bend at a radius of no less than 6 times the outside diameter of such conduit, nor shall more than two 90 degree bends along the total span of such a conduit. No continuous conduit run may exceed 15 meters without an appropriate draw box.
- 9. Cable is at no point to be placed directly on top of suspended ceiling tiles.
- Contractors are to ensure that cable is not installed in areas such as roof spaces or in direct sunlight where temperature ranges might exceed the manufactures operating temperate specifications (typically not in spaces where temperatures exceed 60 degrees Celsius.)
- All metallic support structures, be it conduit, ducting or trays, shall be grounded in accordance with national electric regulations.
- 12. Ducting systems shall be securely fastened to walls by means of the appropriate fixing hardware so as to ensure a sound and durable installation.

13. Ducting system covers are to be fitted securely and any portion of the ducting system found to be cracked or damaged is to be immediately replaced.

#### 6.8 POWER AND EMI SOURCE SEPARATION

- 1. Cable may be laid adjacent to sources of interference such as 240V electrical branch circuits with a minimum separation 75mm where:
  - a. A continuous grounded metallic barrier exists between electric cable and structured cabling.
  - b. A durable non-metallic insulation exists, other than the insulation material of the cable.
- 2. At no point may data cabling cross the path of any power or broadband cable, fluorescent lighting unit (where suspension is used as a means of separation) at an angle less or greater than 90 degrees.
- 3. The installer is to ensure that electrostatic devices such as photocopiers and sources of radiation such as x-ray devices, radio transmitters, their antennae and associated broadband cables are to be avoided when routing cable.

## 6.9 POST-INSTALLATION TEST AND CERTIFICATION

General Requirements

- Every cabling link is to be tested and must meet with the requirements of ISO 11801 Class E (2002) Permanent Link model across the full length of the link.
- 2. Test requirements are as per Permanent Link certification requirement for which the appropriate test adapters are to be used.
- 3. The contractor will ensure that the full plot data is stored for each and every test.
- 4. The test results shall also be in in the test equipment native software format (eg. Fluke Networks Linkware format (.flw)).

- 5. Test results are to be stored and provided to Ingcali/Project Manager staff in electronic format in .csv and .flw . When submitting to Molex Premise Networks, the test results must be in the test equipment's native software format.
- Only Fluke DTX series testers will be used to certify University SCS's or their subcomponents running the current firmware.
- The test equipment is to be well maintained and in good working order. Ingcali/Project Manager staff reserves the right to insist on an annual factory calibration certificate for the instrument to be used for testing.
- Ingcali/Project Manager staff further reserves the right to insist on being present during the self-calibration of the test unit and the instruments initial configuration prior to test and during the test process itself.
- The contractor is to advise Ingcali/Project Manager staff within 3 working days of intent to commence testing in order that such a staff member may make himself available to attend testing procedures.
- 10. The contractor is required to make available the test equipment and necessary personnel at no extra cost should a member of Ingcali/Project Manager wish to perform random acceptance testing on approximately 10% of the installed cabling infrastructure.
- 11. Ingcali/Project Manager staff reserves the right to decline acceptance of marginal performing cables irrespective of their having passed testing based on risk of future degradation over the life span of the installed product.
- 12. Where it is found that the random tests do not match those presented, Ingcali/Project Manager staff reserves the right to insist on a supervised re-test of any or all installed cables prior to acceptance.
- 13. It is the sole responsibility of the contractor to ensure that the appropriate Vendor test and documentation requirements are met in order that Ingcali/Project Manager be provided with a warranty certificate issued by the SCS Vendor.
- 14. Any contention regarding Vendor warranty requirements is to be resolved between the Vendor and the contractor and has thus no bearing on Ingcali's requirements as outlined here.
- 15. Documentation is to conform to the guidelines of EIA/TIA 606-A and provided in 4 parts:
  - An excel sheet indicating cable label, location of work area and Telecommunications closet termination points etc in electronic format.

- Detailed test results in .flw (Fluke Networks Linkware) or similar native b. software format inclusive of all plot data.
- A floor plan or site diagram reflecting the routes taken to and location of all C. installed cables in electronic format.
- Laminated A3 sheets showing the floor plans for the area covered per rack d. and labeled voice & data points, to be placed inside each rack.

#### INTERCONNECTING BANDWIDTH 7

## Backbone connectivity

The minimum bandwidth specification will cope with an Ethernet backbone operating at 10 GB/s as per the IEEE 802.ae specification. OS1 Single mode Fibre of appropriate physical construction suitable for the intended environment may be used.

#### 8 INTERCONNECTIONS

#### Sites

All buildings will be provided with a 12 pair, 24 cores fiber optical cable from the Building to the main admin building

A dedicated fibre 6 pair, 12 cores link will be installed from the Main Admin Building to the security building.

#### Users


The maximum length from the patch panel in a distribution centre to the user wall socket will be 85 meters.

#### 9 GENERAL

3 X 42 U rack will be provided. This rack will contain two 5 kVA rack mount UPS modules as well as the switches and interconnection to cope with voice and telephony requirements for the users. Each rack will have two separate, i.e. fed from different phase, 5 kVA UPS backed power supplies that provides 220V, 50 Hz, sine wave power with a 5% tolerance on the stated measures.

Each rack will have the power connections from the top of the rack and the data connections will come from behind and the bottom. Cabinets will be fitted with a plinth of not less than 150mm in height to enable cable entry in the event that raised flooring is not available.

There will be walkway of 800 mm width in front and behind the cabinet(s) as depicted in figure 1 below.



#### 10 RACK SPECIFICATIONS

- 42u x 1000mm deep
- 1 x 4-Way extractor fan tray mounted to the top of the rack
- 2 x 5-way dedicated Power Distribution Units (PDUs) mounted inside the racks
- Solid lockable doors on the back and sides, and lockable glass door on the front
- Standard colour rack goose grey

#### 11 CABLE COLOURS

- The horizontal Data cables must be Standard RAL grey colour PVC
- The horizontal camera cables must be Standard RAL yellow colour PVC
- The horizontal Biometric cables must be Standard RAL Black colour PVC
- •
- Patch leads
  - Must be in standard length of 2.5 metres
  - o Blue for voice points
  - o Green for data points
  - o Yellow for camera
  - o Black for biometric readers
- Fly leads
  - o 3m standard length
  - o Grey for all data points

#### 12 FIBRE

- SC duplex connectors on all fibre trays
- 3m SC to LC fibre patch leads to be provided

#### 13 PATCH PANELS

- Only Molex 1U 24-port Harmonica patch panels to be used.
- All the cables will be patched in separate panel. Switches will be installed in separate panel and connected with patch leads

#### 14 LABELLING OF DATA, VOICE & FIBRE POINTS

- First patch panel begins with letter A, Points 1-24
- Second patch panel begins with letter B, Points 1-24
- Continues to Z, Points 1-24
- Then starts with AA, Points 1-24

Next panel is AB, Points 1-24

# 15 SCHEDULE OF DATA/TELEPHONE OUTLETS CAT 5e/6 CABLING

See Bill of Quantities

## 16 FIBRE OPTIC CABLING

 The different buildings to be connected by 24 core fibre link to the main building

## 31. SECURITY

## 31 ACCESS CONTROL SYSTEM

## 31.1 BIOMETRIC (FINGERPRINT) READER

Biometric Readers shall be used by authorized personnel for access control. Biometric matching shall have a verification (1:1) accuracy of 99% or higher. The biometric Equal Error Rate (EER) shall not be more than 1% for verification.

Fingerprint biometric technology shall be capable of template creation from a single image capture. Fingerprint reader image resolution shall be 500 dpi or higher. When a reference or operational biometric verification (1:1) is initiated, the correct result (accept or decline) shall be accomplished on the first attempt at least 90% of the time. Biometric devices shall offer liveness detection as a manufacturer's option.

The Reader must satisfy the following requirements:

- Capacity for at least 500 users.
- Must support Ethernet and serial communications to polling PC,
- Ethernet port must be at least 10 Base-T with RJ-45 terminal,
- Serial connection must be capable of supporting communications at a minimum of 40 meters,
- Reader should be capable of functioning independent of polling software,
- In the event of failure of communications between the readers and the polling software, the readers must continue to accept punches as before,
- Reader must be capable of retaining the information after repeated power cycles for up to 5 days minimum,
- The readers must support both AC and DC power source.

#### 31.2 Controllers

The Controllers shall provide a single board solution for interfacing 1 or 2 doors to the access control system. In addition, other I/O and reader interface modules can be added on the Intelligent Reader Controller's downstream port to expand its capabilities. The Controllers shall be scalable.

The Controllers shall provide power and functionality. In the event of loss of connectivity, the full controller functionality and database of the Controllers shall allow nearly all local functionality to continue unimpaired until the server connection is restored.

The Controllers shall store up to 350,000 cardholders in non-volatile flash memory, and support selective download for larger cardholder databases. The downstream RS-485 2-wire port shall be used to connect up to 31 devices.

The Controllers shall support up to eight different card formats. The Controllers shall include eight inputs that support normally open, normally closed, supervised, and non-supervised circuits. In addition, four output relays shall support fail-safe or fail-secure operation.

The Controllers shall have the following features:

- 8 MB of available on-board non-volatile Flash memory.
- 512 KB available RAM for event memory, Lithium battery backup.
- Firmware stored in Flash memory, background download of firmware updates supported.
- Support up to 16 different formats (8 card formats and 8 asset formats).
- Biometric template storage support.
- Enhanced anti-passback capabilities.
- Up to 32,000 access level permissions.
- 255 holidays with grouping, 255 timezones, each with 6 intervals.
- Elevator control support for up to 64 floors.
- Individual extended held open and strike times (ADA required).
- Up to 9-digit user pin codes.
- 20 Status LEDs.

#### Reader Interface Functionality:

- Shall support Data1/Data0, Clock/Data and compatible RS-485 readers and keypads.
- Four Form-C 5 A at 30 VDC relay outputs.
- Door contact supervision (open/closed) and push-button monitor for each door.
- Strike control and auxiliary output for each door.
- Bicolor reader status LED support plus beeper control, or 2wire LED support.
- Onboard regulator shall allow 12 VDC reader power from 24 VDC power source.

## Other Features & Functionality:

- Two dedicated inputs for tamper and power failure status.
- 12 VDC or 24 VDC input power.

# 5.3 ELECTRO - MAGNETIC LOCKING DEVICE (MAGLOCK)

Maglocks shall conform to the following specification:

- Locks shall be capable of holding a 600-kilogram pulling force per door leaf.
- The units shall operate on 12 VDC.
- The lock housing shall be constructed to allow connection of all power and control wiring within the removable housing cover.
- The unit shall be no larger than 2" by 1 13/16" by 23" overall.
- All units shall be supplied with a bi-colour LED to indicate lock status
- Furnish a factory installed door position switch concealed within the housing.
- Supply units with magnetic bond sensors for each door leaf to detect an insufficient holding force on the lock armature.
- "TJ" locks (top jamb mounted units) shall be supplied with "Z" brackets for in swinging doors where scheduled.
- Lock housings and mounting hardware (filler plates and angle adapters) shall be standard US28 clear satin anodized aluminium except where special finished hardware is required
- The maglock shall be remotely controlled from the control room.
- All EM locks must have their own PSU per lock. No other devices shall be powered from this power supply.
- All PSU units will be housed in the control room.
- PSU units must be sized by the contractor and must have at least 33% safety margin at all times. EM power supply unit must be connected to the UPS line.
- Cable used to EM lock must be at least 1.5 mm Sq multicore type (rip cord will not be allowed).

For additional security the electromagnetic locks shall be supplied with the options: (or as scheduled)

- Edit, or include schedule showing required locations.
- All above units shall be supplied with a cover tamper switch to detect unauthorized removal of the housing and tamper proof cover screws to deter tamper attempts.
- To alert persons when the door is unlocked for access, a

sounder shall be mounted in the lock housing. This audible alert shall activate on door unlock and cease upon door opening or re-locking of the door. Shall be externally powered.

- For aesthetic design consideration and additional security all above units shall be supplied with "guard housings" to conceal the normally exposed (bottom) edge of the door armature.
- Provide extra length lock housing covers to extend across the full width of opening, or where locks are scheduled to be mounted vertically, from finished floor to door stop or underside of header.

On doors where emergency exit is required, only power-locked devices will be installed and these will be wired in series with an emergency release mechanism such as a break-glass unit or a fire-panel relay.

#### 5.4 Client Workstation

Client Workstation should be a Windows based PC with 23" LCD monitor. All necessary software should be legally installed and paid for. The web cam is to be mounted for easy and effective enrolment of people.

#### 5.5 Commissioning

Access control system should fully functional and integrated with the LAN. Cat 5e/6 data point for each biometric reader forms part of data scope of work.

#### 31. CCTV

The CCTV should be fully functional with a 400 frames per second real display and 400 frames per second storage. The Equipment in the bill of quantities is the minimum requirements. Add the cost of the equipment and items needed to provide functional system.

#### 32. INTERCOM

The intercom system is to be installed in the guard room from where the different stations at the cells can communicate to. The guard can then open the certain doors through the access control system to allow the flow of wardens and prisoners in and out of the building.



# National Department of Public Works

(Principal Client)

# Health and Safety Site Specific Specification

Submitted to:

Contractor:	

**FOR** 

Site: MANKWENG POLICE STATION

Reference no: 6066/0006

OFFICE OF THE REGIONAL MANAGER

DEPARTMENT OF PUBLIC WORKS

Private Bag X9469

**POLOKWANE** 

0700

**Date: 17 JANUARY 2024** 

# Scope of work:

# The SANS 10400 –S:2011 must be used to construct the Disability Facility INDEX:

- 1. This specification document (Construction regulation 2014, (7)(c)(1))
- 2. The Safety File
- 3. The Safety File Index
- 4. Incident / Accident reports / Wcl 2
- 5. Safety Committee and Minutes
- 6. Monthly Safety Audit Reports (CR 2014 7(1)(c)(vii))
- 7. Letter of good standing (CR 2014 7(1)(c)(iv))
- 8. Health and Safety Organogram
- 9. contractor A's appointment letter as a Contractor
- 10. Legal Appointments
- 11. Operators Appointments (CR 2014 23(d)(i(ii))
- 12. List of Plant on Site
- 13. List of Contractors on Site
- 14 Mandatory Agreement with contractor
- 15. Contractors Mandatory Agreements
- 16. Contractors Specification Documents (CR 2014 7(c)(i)
- 17. Contractors Appointment Letters (CR 2014 7(c)(v)
- 18. Contractors Safety Plans (CR 2014 7(c)(vi)
- 19. Contractors "Letter of Good Standing." (CR 2014 7(c)(iv)
- 20. Plant Hire and Labour only Contractor's Mandatory Agreements
- 21. contractor A's Safety Plan (CR 2014 7(2)(a))
- 22. contractor A's Health & Safety Policy Document
- 23. Risk Assessments Plan/Policy/Procedure (CR 2014 (9))
- 24. Incident / Accident Reporting Policy / Procedure
- 25. Health and Safety Specification Document (This document)(CR 2014 ((7)(c)(i))
- 26. Fall Protection Plan (CR 2014 10(1))
- 27. Site Emergency Plan
- 28. Site Rules
- 29. Risk Assessments
- 30. Public Safety
- 31. Safety Awareness Program
- 32. Toolbox Talks
- 33. REGISTERS
- 34. Induction Training Register (CR 2014 (7)(5))

- 36. Safety Harness Register
- 37. Hazardous Chemical Substance Register (CR 2014 (25))
- 38. Ladder Register
- 39. First Aid Register
- 40. Lifting Equipment Register
- 41. Electrical Equipment Register
- 42. Fire Equipment Register
- 43. Scaffold Register
- 44. Form & Support Work Register (CR 2014 12)
- 45. Explosive Actuated Fastening Devices Register (CR 2014 (21)(2)(g)(i))
- 46. CHECKLISTS
- 48. Electrical safety (CR 2014 (24)
- 49. Competency certificates (CR 2014 (1)(a))
- 50. Medical Certificates(CR 2014 7(1)(g))
- 51. Regulations applicable (CR 2014 7(3))
- 52. Covid 19 specification

Before you will be allowed to perform work on site you must adhere to all of the following as contemplated in the Occupational Health and Safety Act, Act no 85 of 1993, the Construction Regulation 2014 and this document: (and must have an approved H&S plan in place)

# 1. This specification document (Construction regulation 2014, (7) (c) (1))

You are required to compile your safety file the way we require in this document. You will not be to allowed to start working on site unless your safety file has been approved. Submit the file well in advance to enable our safety Department to audit and approve it, and if there are any discrepancies you will have ample time to rectify and re-submit.

This document requirement is that of what is written in the OHS Act. It also contains guidelines from Departmental Enquiries, court cases and own Experience. The ultimate goal of this document is to direct you to be legal and thereby keep us, contractor, the Principle Contractor, and the Client, legal and free from prosecution.

This document serves as our minimum requirements. We don't go overboard with safety. Nevertheless, this document is the law on site. Don't do less than what is described in this document. Don't fall victim to the new

stupidity of propagating that, "if it is not specified in this document then we won't do it," or, "it is not explicitly mentioned in the OHS Act and therefore we will not do it."

## 2. The Safety File

- 1. Use a lever arch file to contain all the documents
- 2. Divide the documents with dividers of the plastic type, numbered 1 to 31. Use another set of dividers behind the first, if the one set is not sufficient.
- 3. Clearly identify the file with the words "Safety File" and the Company name printed on the side with letters big enough to read from a distance for anyone on site to recognise it as the safety file.
- 4. Always have the safety file available in the site office. It will be handed to the Client at site handover. It may never leave the site.
- 5. All forms must be completely filled in and fully signed by all parties.
- 6. It must be clearly understood that all documents in the safety files are legal documents and must be treated as such. If corrections are made on any of the documents it must be initialled by all parties involved.

  No tipex are allowed.
- 7. All documents that are copies of the originals must be certified as a true and correct copy of the original.

# 3 The Safety file index

- Laminate the file index to prevent it from tearing and it will last longer. Paste it in front of the file.
   The following is a sample of such an index. There may be items that you want to add or change to fit your style. You may do so.
- 2. Please note that we need you to keep all documents separate with dividers. It makes it easier to find during an audit and your day to day activities.
- 3. Also note that one person can be appointed for more than one designation. The site number, printed in red on the cover page, must be prominently printed on all your documents.

#### INDEX:

- Incident / Accident reports / Wcl 2 forms / Annexure ones
- Safety Committee Meeting Minutes (Supplied by contractor)
- 3. Monthly Safety Audit Reports (We will audit you monthly) (CR 2014 (7) (c) (vii))
- 4. Letter of Good Standing (CR 2014 (7) (c) (iv))
- Health and Safety Organogram
- 6. Contractor A's appointment letter as a Contractor (CR 2014 (7) (c) (v))
- 7. Legal Appointments With proof of Competency & Medicals
- 8. CEO Delegation of Duties (16.2)
- 9. Construction Manager (CR 2014 (8) (1))
- 10. Assistant Construction Manager (CR 2014 (8) (2))
- 11. Construction Safety Officer (CR 2014 (8) (5) (6))
- 12. Construction Supervisor (CR 2014 (8) (7))
- 13. Assistant Construction Supervisor (CR 2014 (8) (8))
- 14. Risk Assessors (CR 2014 (9) (1))
- 15. Temporary Works Designer & Inspector (CR 2014 (12) (1) & (3) (f))
- 16. Temporary Works Supervisor (CR 2014 (12) (2) & (3) (a))
- 1. Excavation Supervisor (CR 2014 (13) (1) (a))
- 18. Scaffold Supervisor (CR 2014 (16) (1))
- 19. Scaffold Inspector (SANS 10085-1:2004 Edition 1.1 (14.5)
- 20. Scaffold Team Leader (SANS 10085-1:2004 Edition 1.1 (14.4.1)
- 21. Scaffold Erectors (SANS 10085-1:2004 Edition 1.1 (14.4.1)
- 22. Fire Equipment Inspector (CR 2014 (29) (h))
- 23. Fall Protection Planner (CR 2014 (10) (1) (a))
- 24. Safety Representatives (OHS Act (17))

# Occupational Health and Safety Act, Act 85 of 1993 and Construction Regulation 2014

- 25. List of Plant on site
- 26. Blank Appointments
- 27. Accident Register
- 28. Principle Contractor Mandatory Agreement
- 29. Plant Hire & Labour Only Mandatory Agreements
- 30. Fall Protection Plan (CR 2014 (10) (1))
- 31. Principle Contractor Safety Specifications (CR 2014 (7) (c) (1))
- 32. Safety Plan (CR 2014 (7) (c) (x))
- 33. SHEQ Policy
- 34 Risk Assessment Plan
- 35. Contractor Accident Reporting Procedure
- 36. Contractor Incident Reporting & Investigation Policy

For your documents that you are using daily, we suggest you open a separate file. The following is a sample of such a file index. There may be items that you want to add or change to fit your style. You may do so. Please again note that we are keeping all documents separate with dividers.

#### INDEX:

#### 1 egisters:

- Toolbox Talks
- PPE Issue Register
- Hazardous Chemical Substance Register
- Safety Harness Register
- First Aid Register
- Incident/Accident Register
- Lifting Equipment Register

- · Earth Leakage Testing Register
- Electrical Equipment Register
- Fire Equipment Register
- Scaffold Register
- Form & Support Work Register
- · Explosive Powered Tool Register

#### 2. Checklists:

- Electrical Extension Cords Checklist
- Afety Harnesses Checklist
- First Aid Boxes Checklist
- · Lifting Equipment Checklists
- Fire Equipment Checklist
  - Formwork

#### 3. Temporary, Electrical, and DB Box Checklist:

- Electric Drills Checklist
- Angle Grinder Checklist
- Skill Saw Checklist
- Ladder Checklist
- Scaffold Checklist
- Link stick
- Jump suite
- Gloves
- Fire Extinguisher Checklist
- formwork

#### 4. Excavation Checklist:

- Form and Support Work Checklist
- Gas Welding & Cutting Checklist
- Hand tools Checklist

It must be clearly noted that we do not accept registers that are also a checklist. We herewith clearly state that the registers and checklists are separate forms and must be utilised as such.

## 4. Incident / Accident reports / Wcl 2

All incidents and accidents where someone was hurt, there was damage or illness, must be reported to our Safety officer

Do not hide any accidents from us. We need to know about any incidents in order for us to assist you in preventing a similar incident. We have no blame but retrain policy. You are to familiarise yourself with our incident/accident reporting procedures.

# 5. Safety Committee and Minutes

We have established a Health and Safety Committee. You must nominate one person from your management and one person from your Safety Reps to serve on our safety committee. Whether you qualify to have a Safety Rep or not. We will supply the appointment letters and appoint them on the safety committee. Every Contractor must be represented on our safety Committee and be involved in safety on site. The safety meeting will be held monthly. Minutes will be kept and distributed to you for filing in your safety file. The Client, NDPW representative will sit in on some of the meetings as an observer.

# 6. Monthly Safety Audit Reports (CR 2014 7(1) (c) (vii))

We will do a full health and safety audit on your safety file and your activities every month. The results and the report must be filed by you in the safety file. Discrepancies must be action Ed within a week and signed off on the audit report. You must also do monthly safety audits on yourself. The reports must be filed in your safety file.

# 7. Letter of good standing (CR 7(1) (c) (iv)) 2014

You are to ensure that a letter of good standing with the Workman's Compensation Commissioner is current and kept in your file as proof that you are registered and in good standing with the compensation fund, or with a licensed compensation insurer prior to work commencing on site. (At least two weeks before arriving on site). If your letter has expired, your workers on site are not insured and work will be stopped until such time as you are in good standing with the Workman's Compensation Commissioner again. Contractor will not take responsibility on our Workman's Compensation insurance for your workforce.

# 8. Health and Safety Organogram

You must have a health and safety organogram in your safety file. It must always be kept up to date and current.

# 9. Contractor A's appointment letter as a Contractor

It is your duty to ensure that your appointment letter as a Contractor is in the safety file.

## 10. Legal Appointments

All your appointment letters must be properly signed by all parties involved. It must also be completely filled in with no blank spaces. The name of the appointment must be clearly written on the appointment. Proof of competency (Construction Regulation 2014 (1) (a)) must be attached to the back of the appointment letter. Proof of competency may be proven with degrees, diploma's, certificates and/or a short abbreviated CV as per the following example. A medical certificate (Construction Regulation 2014 (7) (8)) must be attached behind the proof of competencies. We do not accept appointment letters that has two designations on it. Each designation must have its own appointment letter.

#### Sample abbreviated CV:

Project name	year	period	Contract amount	Your position

The following appointments must be made by you. Remember that in most cases one person can be appointed for more than one appointment:

- \* CEO Delegation of Duties (16.2)
- \* Construction Manager (CR 2014 (8) (1))
- \* Assistant Construction Manager (CR 2014 (8) (2))
- \* Construction Safety Officer (CR 2014 (8) (5) (6))
- \* Construction Supervisor (CR 2014 (8) (7))

- \* Assistant Construction Supervisor (CR 2014 (8) (8))
- \* Risk Assessors (CR 2014 (9) (1))
- \* Temporary Works Designer & Inspector (CR 2014 (12) (1) & (3) (f))
- \* Temporary Works Supervisor (CR 2014 (12) (2) & (3) (a))
- \* Scaffold Inspector (SANS 10085-1:2004 Edition 1.1 (14.5)

If you are going to erect your own scaffolding, you need to have a scaffold Inspector and the following three scaffold appointments.

- \* Scaffold Supervisor (CR 2014 (16) (1))
- \* Scaffold Team Leader (SANS 10085-1:2004 Edition 1.1 (14.4.1)
- \* Scaffold Erectors (SANS 10085-1:2004 Edition 1.1 (14.4.1)
- \* Temporary Electrical Installation Controller (CR 2014 (24) (c))
- \* Fire Equipment Inspector (CR 2014 (29) (h))
- \* Fall Protection Planner (CR 2014 (10) (1) (a))
- \* Safety Representatives (OHS Act (17))
- \* First Aiders

# 1 Operators Appointments (CR 2014 23(d) (i (ii))

All operators must be appointed with a letter of appointment. The letter of appointment is actually a letter to authorise that person to operate the plant, equipment or tool.

- \* The letter must be properly signed by all parties involved. The name of the appointment must be clearly noted on the appointment.
- \* The operator must have a competency certificate from, or sent for training at, an accredited training provider.
- \* The certificate of competency must be attached to the back of the appointment letter.
- \* The operator must be in possession of a valid medical certificate declaring the operator medically fit to operate the plant, equipment or electric tool, as per the Construction Regulations 2014 (7) (8) & Annexure 3.

- \* If an operator has no competency certificate, they won't be allowed to operate the plant. If an operator has no medical certificate, they won't be allowed to operate the plant.
- \* Copies of original documents must be certified as being a true and correct copy of the original document.

#### 12. List of Plant on Site

You must paste a list of all plant on site in the safety file. It must always be kept up to date and current.

#### 13. List of Contractors on Site

If you have contractors, you must paste a list of all Contractors on site in the safety file. It must always be kept up to date and current.

# 14 Mandatory Agreement with contractor

We will see to it that a mandatory agreement is signed and entered into with contractor and contractor A. This agreement must be properly signed and all pages must be initialled by all parties. It refers to Section 37 1 and 2

## 15. Contractors Mandatory Agreements

It is contractor A's duty to see to it that a mandatory agreement is signed and entered into between contractor A and all their contractors on site before they come onto site. These agreements must be properly signed and all pages must be initialled by all parties. These mandatory agreements must be done in duplicate. One properly signed copy must be filed in your safety file. The other copy must be filed in the Contractors safety file. You must come to an agreement regarding the Safety Rep and the first aid arrangements with the Contractors. These arrangements must be written in the mandatory agreement. These arrangements are as follow; they must have at least one trained Safety Rep and at least one trained First Aider, whether they qualify to have one or not.

# 16. Contractors Specification Documents (CR 2014 7(c) (i)

Each one of your Contractors must be issued with a health and safety specification document written by contractor A.

Remember you must issue a site specific, and a job specific health and safety specification document. We don't want to see generic specification documents. We also don't want to see this document passed onto your Contractors as your specification document to them. Write your own. Contractors must sign for their specification documents.

# 17. Contractors Appointment Letters (CR 2014 7(c) (v)

Each one of your Contractors must be appointed in writing as a Contractor. The original letter where contractor A informed the Contractor of the allocation of the tender to them would suffice. These documents must be filed in your safety file. Copies of these documents must also be filed in the Contractors safety files by the Contractors.

# 18. Contractors Safety Plans (CR 2014 7(c) (vi)

All your Contractor's safety plans must be scrutinised by you and if in line with this document, the OHS Act and the Construction Regulation 2014, it must be approved by you in writing. The approval letters must be filed in the Contractors safety file and copies thereof in yours.

# 19. Contractors "Letter of Good Standing." (CR 2014 7(c) (iv)

None of your Contractors may be allowed to perform any work unless they submit a valid "Letter of Good Standing" as proof that they are in good standing with the Workman's Compensation Commissioner. These letters must be filed in the Contractor's safety files and the validation dates closely monitored.

# 20. Plant Hire and Labour only Contractor's Mandatory Agreements

This is a very controversial subject. Are they contractors or not? This is how we want you to handle the situation. If you hire a TLB from a person or a few tippers from another, and you want to treat them as a plant hire company and not a Contractor, then we require you to enter into a mandatory agreement with them. In the agreement you must clearly state that the operators are under your full management and control. You must also clearly state that contractor A takes full responsibility for the operators of their Workman's Compensation insurance. Labour Only's must be treated in the same manner. It is clearly stated that all plant hire companies cannot be treated this way just to avoid them having a safety file. We're talking one or two plant being hired. All the pages of the mandatory agreements must be initialled by all parties. It must also be properly signed by all parties.

# 21. Contractor A's Safety Plan (CR 2014 7(2) (a))

In answer to this safety specification document, contractor A must submit a safety plan on exactly how you plan to implement and manage health and safety on the site. The safety plan must address and reference to all items mentioned in this safety specification document. The safety plan will be scrutinised by contractor and after we familiarised ourselves with the content,

and only after we are satisfied that will be compliant to the OHS Act, the Construction Regulation 2014 and this specification document, will we issue an approval letter for your submitted safety plan. The approval letter must be filed with your safety plan in your safety file. Please be advised that your safety plan must be signed by contractor A's Chief Executive Officer.

#### **WARNING:**

- 1 Do not submit a generic safety plan. It must be special ally design for your project
- 2 Do not submit a safety plan that says some items in your plan may not be applicable to the site. that makes it generic. Make it site and job specific. We don't want to pick which items are applicable.
- 3 If your safety plan is approved, you are obliged to implement everything mentioned in your safety plan.
- 4 Construction Regulation 2014 (7) (1) (c) (vi)) explicitly says that we must take steps to ensure that each contractor's health and safety plan is implemented and maintained on the construction site.

# 22. Contractor A's Health & Safety Policy Document

You must paste your health and safety policy document in the safety file.

# 23. Risk Assessments Plan/Policy/Procedure (CR 2014 (9))

You must file your signed site specific risk assessments plan/policy/procedure in the safety file. The plan/policy/procedure must be communicated to all persons on site and record there-of must be kept.

Your assessment must be more or less have the basic matrix as shown below see tables

BASELINE RISK I	MATRIX		HAZARD EFFECT	HAZARD EFFECT / CONSEQUENCE			
Loss type	1 Insignificant	2 minor	3 moderate	4 major	5 catastrophic		
Time line	No impact on overall project timeline	May result in overall project timeline overrun of less than 5%	May result in overall project timeline overrun of between 5% and less than 20%	may result in overall project timeline overrun of between 20% and less than 50%	May result in overall project timeline overrun of 50% or more		
Budget	No impact on the budget of the	May result in overall project budget	May result in overall project budget overrun	May result in overall project budget overrun	May result in overall project budget overrun of 50% or mo		

LIF	(ELIHOOD	74 40	11/4/11		RISK RAT	ING			,			12 Page 1
5 Almo Certa	ost	occ fred hig			11 Medium	16	Significant	20 Significant		23 High	25	High
4 Like	ly	The pro bet 90%	ebability of reoccurring e unwanted event has a bability of eween 60% and less that 6 of curring		7 Medium	1:	2 Medium	17 Significant		21 High	24	High
3 Poss	sible	The of betv	unwanted event has a probab veen 30% and less than 60% urring		4 Low	8	Medium	13 Significant	1	8 Significant	22	High
2 Unli	(#0	of betv	unwanted event has a probab veen 1% and less than 30% o urring		2 Low		5 Low	9 Medium	1	4 Significant	19/Sij	guificant
1 Rare		nev occ less	curred, has a probability sthan	of	1 Low		3 Low	6 Medium		10 Medium	15 Si	gnificant
10	incompetent persons - incorrect stacking - procedures during site establishment   Injuries during off loading Cuts and burns injuries activities Dr. Rushed activities Incorrect supervision Trip and fall Cuts Collapsing of stacks   Medical Caste Pool accided to the control of		CON	NCEQINCES RISK HOW IS HAZAF REVIEW		ZARD TO BE DEALT WITH	ARD TO BE DEALT WITH BY WHOM			BY WHEN?		
1. 1.1			opping of ipment ysical injuries st Time injuries dical treatment	6	The contractor must declare all employees competent in writing Contractor OHS file must be approved prior to site establishment begins Site specific safe work procedures must be followed Site –induction must be given to all employees to make them aware of the specific hazards Employees must be issued with correct PPE before work begin All workers on site must be declared medically fit by a medical practitioner		0	- CHSA (Construction Health & Safety Agent)		During site establishme nt		
1.2	OFFLOADING HE EQUIPMENT AND CONTAINERS P/C SITE ESTABLISHMENT	)	Defective mobile crane can cause accidents Adverse weather conditions Untrained personnel/ Operators Unsafe hooking methods unstable load	fata Dai prop equi Por foot	ious injury and lities mage to perty and ipment tential hand & cinjuries inding time	19	Material t level grour stacking i competent Adequate provided All unstat and stacke Load test submitted Rope cert submitted Safe load working of Over wind and in wor Daily chec operator. Checklist	to be stacked on firm and and and. to be supervised by a tax supervisor. It storage area to be stacks to be dismantled over certificate will be to the client. It indicator must be in good and and and and and and and and and an	e od	- Construction Supervisor - CHSO - Construction Manager		During site establishme nt

# LIST OF COMMEN RISKS ON THIS PROJECT SUBJECTED TO CHANGE: These risks must be tableted; see above tables for reference and then put the risk and then the remedial action for the following list of risks

#### You may add to the list of risks in your risks analyses

- Concrete works
- Formwork
- Reinforcement
- Dust and noise pollution
- Debris removal
- Handling of materials
- Temporary supports to openings through existing walls
- Electrical strip and making safe work and all other electrical works
- Demolitions
- Breaking up and removal mass concrete aprons and ramp Removal of floor and wall tiles, floor covering
- Ironmongery removal of locks handles
- Removal of glass and related glazing work including a safety glass installation
- Removal of all water pipes and reinstall copper pipes
- · Laying and backfilling of pipes and electrical supply cables
- Plumbing and drainage
- Paintwork including sanding and cleaning
- Tree removal
- Excavating
- Soil poisoning
- Form work ,scaffolding ,rigging
- Gas reticulation and appliance installations
- General

# 24. Incident/Accident Reporting Policy/Procedure

You must paste our incident/accident reporting policy/procedure document in your safety file.

# 25. Health and Safety Specification Document (This document) (CR 2014 ((7) (c) (i))

This specification document must be signed by your CEO and filed in your safety file.


# 26. Fall Protection Plan (CR 2014 10(1))

You must have a fall protection plan in your safety file. The plan must be developed by your appointed Fall Protection Planner.

Your fall protection plan must be site specific and practically viable and must cover this sites anticipated fall hazards for your

Work area. Do not submit a generic fall protection plan, we know them all. All persons in your employment on site must be trained in fall protection plan.

The attendance register for the training must be attached to the fall protection plan. The plan must also contain a rescue plan for workers hanging from a height in a harness. You only have five minutes to rescue the person hanging from a harness. Your plan should include a practical rescue plan and equipment. Persons executing the rescue plan must be Trained in the plan. Your site management must endorse (sign) the plan.



# 27. Site Emergency Plan

You must familiarise yourself with the site emergency plan developed by contractor. All your employees on site Must be trained on the site emergency plan. The attendance registers for the training in the site emergency plan Must be signed and filed in your safety file. The emergency plan is pasted on the notice board on site.

Emergency numbers is also prominently displayed on the notice board.

#### 28. Site Rules

Our site rules, applicable to this site, are pasted on the notice board for everyone to have access to it. All your Employees on site must be trained in our site rules. The attendance registers for the training in the site rules Must be signed and filed in your safety file.

#### 29. Risk Assessments

All your tasks performed on site must be backed by a risk assessment which determined the risks, the hazards And determines the best preventative measures to minimize the risks and hazards. All the risk assessments must have:

The site name on the risk assessment.

- 2 The date on the risk assessment.
- 3 The person/s name/s that did the risk assessment and their signatures.
- 4 Managements signature as proof of their endorsement and knowledge of the assessment.
- 5 An attendance register as proof that your employees were trained in the risk assessment.

## 30. Public Safety

The site is securely barricaded to keep members of the public from entering the site. The entrance to the site Has access control. Make sure your visitors to the site signs the visitor's book and follow signage directing all

Visitors to the site office.

#### 31. Safety Awareness Program

Poster is displayed in conspicuous places on site depicting various safety tips. Make your employees aware of Them

#### 32. Toolbox Talks

You will do a safety talk with your employees once per week and it must be recorded as proof that you have Done so. The Toolbox talk attendance register must be filed in the safety file. Each person on site must attend a follow talk at least once per week. You must force the contractors to also do toolbox talks once per week and they must also keep record thereof. Topics must be meaningful, not just, e.g. "PPE" or "Safety." It must be Specific and really meaningful. Toolbox talks must be signed by the facilitator and signed off by management.

#### 33. REGISTERS

Do not use checklists as registers. You must have a separate document that serves as a checklist and a separate Document as a register. A register is not a checklist and vice versa. A register is documents where you list all the items you have in stock.

#### 34. Induction Training Register (CR 2014 (7) (5))

Me, contractor, the Principal Contractor, will do the site specific induction training with everyone on site. All Induction training will be recorded by us in the induction training register. ID numbers will also be noted, so keep them close by. No person or employee will be allowed or permitted to work on the site, unless such an employee or person has undergone the site's health and safety induction training, pertaining to the hazards prevalent on the site at the time of entry. It is your responsibility to ensure that all your employees on site has indeed undergone the said induction training before they start working

# 35. PPE Issue Register

You must issue your employees with the prescribed PPE free of charge. Hard hats, Overall, Steel point safety

Shoes are compulsory on site. You will keep a PPE issue Register and record all PPE Issued thereon. ID numbers must also be noted. All persons must be trained in the care and correct use of their PPE. PPE issued must be backed by a risk assessment.

## 36. Safety Harness Register

All your harnesses must be numbered and recorded on register. You must have a separate document that serves as a checklist. A register is not a checklist and vice versa. If you issue safety harnesses you must make the employee sign for it and you must train them in the proper use thereof and keep record of the training.

# 37. Hazardous Chemical Substance Register (CR 2014 (25))

All hazardous chemical substances must be listed and controlled on a register. These chemicals must be stored in a well-ventilated secure storage facility on site. Most of these chemicals on site is flammable and must be stored in your flammable goods store. These are samples of storage facilities for hazardous chemical Substances.







# 38. Ladder Register

All your ladders must be numbered and listed on a "Ladder Register" and this register must be kept up to date.

No self-made ladders will be allowed on site. Study the seven rules of ladders and make sure your employees strictly adhere to it.







#### 39. First Aid Register

All your first aid incidents must be recorded in your first aid register. It must also be reported to our Safety Officer.

#### 40. Lifting Equipment Register

All your lifting equipment must be listed on a Lifting Equipment Register. All lifting equipment must be Inspected on a separate checklist. The checklist must be signed by the person doing the check and signed off by management. Any discrepancies noted must immediately be actioned and action taken must be noted on the checklist. No discrepancy may be carried over to another checklist.

## 41. Electrical Equipment Register


Your electrical equipment must be numbered and listed on an electrical equipment register. Each one of these items on the register must be inspected on their own checklist. The checklist must be signed by the person doing the check and signed off by management. Any discrepancies noted must immediately be actioned and action taken must be noted on the checklist. No discrepancy may be carried over to another checklist. Checklist must have all equipment e.g. safety harness, link stick, gloves, jump suite ect.


#### 42. Fire Equipment Register

All your fire equipment must be numbered and listed on a fire equipment register. All fire equipment on register must be inspected monthly on a separate checklist. The checklist must be signed by the person doing the check and signed off by management. Any discrepancies noted must immediately be actioned and action taken must be noted on the checklist. No discrepancy may be carried over to another checklist.

#### 43. Scaffold Register

All you're scaffolding on site, whether completed or not, certified safe or not, must be listed on a register. All Scaffolding on your register must be inspected daily, or if any changes on the structure was made. This must be






No person may use any scaffold if it isn't declared safe for use and tagged with a tag, simular to this tag, tied to the scaffold.








No person may use any scaffold if it is tagged with a tag, simular to this tag, tied to the scaffold.









- Make sure the scaffolding boards are in place and in good condition.
  - The scaffold must be strong enough for the usage purpose.
- Never overcrowd scaffold with people, supplies, or equipment.
- Erect scaffold with proper access and guard rails.
- Tied scaffold adequately where regulred.
- Place the guard rails and toe boards firmly.
- Use safety harness and lifeline.
- Do not climb or stretch out over the guard rails.
- Incomplete scaffold must be blocked off or must display a warning notice that it must not be used.

# 44. Form & Support Work Register (CR 2014 12)

All your form and support work must be listed on a form and support work register. All form and support work on register must be inspected and certified by a competent person before pouring of any concrete.

# 45. Explosive Actuated Fastening Devices Register (CR 2014 (21) (2) (g) (i))

Your explosive powered tool and the cartridges must be listed and controlled on an explosive powered tool register.

# 46. Gas registers


is must be registered to ensure there's not more gas on site as necessary this gas include AC refill gas and nitrogen

## 47. CHECKLISTS

Checklists must be done daily, weekly or monthly depending on the type of checklist. If an item on a checklist is "OK" or "correct," the block must not be ticked, it must be initialled. The person doing the checks must initial in the block. Any discrepancies must be marked with a cross and then action ed immediately by your Construction supervisor. All checklists must be dated. All checklists must be signed by the person doing the checklist. Your Construction Supervisor must sign off the checklist. The checklist must be kept in the file for record and auditing purposes. In this document we supply a long list of possible checklists that could be used on site. Our advice is for you to have as much checklists as possible, to cover yourself.

# 48. Electrical safety (CR 2014 (24)

We take electrical safety very seriously. The following are examples of common unsafe electrical practices we don't want to see on our site



No joints are allowed on electric extensions cords. DB boards must have a COC certificate. We don't want to see any exposed wires like we see in the photo.

## 49. Competency certificates (CR 2014 (1) (a))

Where-ever this specification document prescribes a "competent" person, we will need a competency certificate issued by an accredited training service provider. All competency certificates must have the required criteria lay down by SAQA and the National Qualifications Forum (NQF), for the issuing of certificates in South Africa. All certification documents, whether a certificate or a letter, must at least, have the following criteria: Issue d

- Expiry date
- At least two signatures
- One signature the Assessor who assessed the certificate holder
- Assessors registration number at the NQF
- Certificate number
- Contact telephone number where we can verify the authenticity of the certificate.
- Certificate holder's full names and surname
- ID Number of certificate holder

#### 50. Medical Certificates (CR 2014 7(1) (g))

All your employees must have a medical certificate of fitness specific to the construction work to be performed and issued by an occupational health practitioner in the form of the attached Annexure 3.

#### 51. Regulations applicable (CR 2014 7(3))

Where contractor appoints another contractor to perform construction work, the duties determined in the Construction Regulations 2014 that apply to the principal contractor apply to the contractor, as if he or she were the principal contractor. Your file must be submitted to us for approval, well in advance, prior to you coming on site. (At least two weeks) This will prevent delays. You will not be allowed to start working on site unless our safety department gave their approval on the successful implementation of the above.

This document serves as a guideline on how we want you to manage the safety program on site. It is common sense and common knowledge that the OHS Act and the Construction Regulation 2014, must be read, and implemented, in liaison with this document and all its requirements. These three are the standards we will use when we audit your safety system.

See table next page

	Annexure 3		
	OCCUPATIONAL HEALTH AND SAFETY ACT 85 OF 1993	Construction Regulation 2014	
	Medical Certificate of Fitness	ness	
Name of Employee:	oyee: ID Number:	Co Number:	er:
	* Possible Exposures e.g. noise. heat. Iali risk, dust. confined space, etc.	* Job Specific Requirements e.g. Operating Mobile Crane. Digging Trenthes. Crecing formwork & Supportwork, etc.	* Protective Equipment e.g. Dust Respirator (Light Day), Welding
* Occupation			100 A CANADA
* The Employer to	* The Employer to complete the information in the spaces marked with an * before sending the Employee for a medical examination.	nding the Employee for a medical examinat	ion,
Declaration by the Medical Examiner:	Medical Examiner:		
Certify that I have I	Certify that I have by, examination and testing, using the above criteria specified by the employer, satisfied myself that the abovementioned employee is fit to perform the duties as described by the employer in the matrix above.	nployer, salisfied myself that the abovementi	ioned employee is fit
Occupational Medic	Occupational Medicine Practitioner/Occupational Health Nursing Practitioner: (Please Frinchaire)	[a.	
Signature:	Practice Number:	Date:	
Address:			

# 52. Covid 19 specification:



#

#### Addendum to the health and safety specification document, it form a part of the Health and safety specification

COVID-19 pandemic prevention	on measures to be taken
Site Name:	
Principal Contractor Name:	
Contractor Name:	
Da***	
Was /tender number:	
Approval + official details that approved the document;	

#### Background:

You are going to start working on the site soon as it is allowed. That means you must have a Covid - 19 management plan that form part of your health and safety plan, as an addendum, in your safety file. The Covid - 19 management plan must be developed by a competent person.

You're Covid - 19 management plan must be site specific and practically viable and must cover this sites anticipated areas where infections are likely to occur on your site area. All persons in your employ on site must be trained in your Covid - 19 management plan. The attendance register for the training must be attached to the Covid - 19 management plan.

You're CEO and site management must endorse (sign) the Covid - 19 management plan.

#### Your Covid - 19 management plan must contain at least the following:

- a. A schematically drawing of the actual work area and where the actual work will be performed.
- b. Health Risk Assessment:
  - This risk assessment must form part of your management plan. We do not want it as a separate document. It must physically form part of the Covid 19 management plan. Bind it within the plan document.
  - ii Different areas in the workplace might require different methods of safeguarding the employees. In that case specify the area and determine the risks and mitigating measures of that specific area.
- c. What are the symptoms and how to identify them in the workplace?
- d. Screening of workers. How will it be done and when?
- e. If someone is suspected of having the Covid -19 virus, what will the procedure be?
- f. If an employee suspects that he/she has contracted the virus, what would the procedure be?
- g. What PPE will be issued and when?
- h. Quarantine:- self quarantine, forced quarantine, what will your procedure and policy be?
- i. Working from home guidelines. (When, who, etc.)

#### Occupational Health and Safety Act, Act 85 of 1993 and Construction Regulation 2014

- j. Safe travelling to and from work.
- k. How will you safeguard meetings? Precautions during meetings?
- I. Hygiene in the workplace:

#### This specs was developed for Construction sites.

Page 2

- i. Disinfecting workplace, tools, facilities, etc.
- ii. Disinfecting hands and body parts.
- iii Methods of disinfecting that will be used.
- iv. What type of disinfectant?
- m. Physical contact. (Control, who, when, etc.)
  - Training of employees
- o. Cross Provincial border travel of employees.
- p. Keeping record and communicating vital information of cases detected on site.
- q. Visitors to the site.

n.

- r. Social distancing on site.
- s. Employee awareness program.
- t. Regularly cleaning common contact surfaces on site?
- u. How will you treat drivers that deliver to site?
- v. Handwashing facilities. (Where, when, how many, type, etc.)
- w. Provision and disposal of hand towels.
- x. Cleaning regimes for toilet facilities particularly door handles, locks and the toilet flush.
- y. Portable toilet hygiene.
- z. Break times, how will you reduce congestion and contact?
- aa Hygiene at water drinking stations.
- ab Tracing of infected employees.
- ac Your weekly Covid 19 reports that must be submitted to the Client.
- ad Congestion at the workplaces.
- ae Consequence of not adhering to the Covid 19 management plan, the risk assessment and the policy.
- af You must develop a Covid 19 Policy.
- ag How will you manage your contractors on site regarding the Covid 19?

The required document must be submitted to DPW Consultants/Project managers/OHS Managers. We will issue a letter of approval if all the requirements in this addendum to the health and safety plan, have been met. Please note that these requirements are minimum requirements only and all of the items must be addressed in your Covid - 19 management plan, risk assessment and Covid - 19 policy document.

#### The index to your Covid - 19 File should contain at least the following:

- 1 Covid 19 Management plan
- 2 Covid 19 Risk Assessment
- 3 Covid 19 Policy
- 4 Employee Screening declarations
- 5 PPE Issue Register

- 7 Toolbox Talks
- 8 Safe Work Procedures
- 9 Checklists
- 10 Training Material
- 11 Posters

#### Occupational Health and Safety Act, Act 85 of 1993 and Construction Regulation 2014

6 Compliance Employees Appointments	12	Compliance Officer Appointments	
I herewith my signature confirm that I have received this Covi	1 - 19 specification document.		
Signature:			
Date:			
This	a dayala and for Constitution		R DINING TELEVISION

End of specification: 2022

Occupational Health and Safety Act, Act 85 of 1993 and Construction Regulation 2014
E. I. C. V
End of site specific OHS Specification was compiled by Willem Botha 0609976744 or 012 4921486 April 2021

# CLIENT Coherent Health & Safety Specifications




# public works & infrastructure

Department:

Public Works and Infrastructure REPUBLIC OF SOUTH AFRICA

# CONSTRUCTION: SAPS Mankweng



#### **CONTROL SHEET:**

#### **Declaration**

This original document has been prepared, reviewed by the undersigned:

Prepared by: Riscon Consultants

Name: J. Heyneke Date: 20 Feb 2024

#### Received by:

NAME AND SURNAME	DESIGNATION	DATE	SIGNATURE
Johan Heyneke	CLIENTS OHS AGENT	20 Feb 2024	John.
	DESIGNER		
	CLIENT		
	PRINCIPAL CONTRACTOR		

This control sheet must be signed and mailed back to <a href="riscon09@gmail.com">riscon09@gmail.com</a>. Each page shall be signed at the bottom right corner of each page.

#### COPYRIGHT

All rights reserved. No part or section of this document may be changed, used, reproduced, or distributed in any form or by any means, electronic, mechanical, photocopying or recording or otherwise, or stored in a data base or retrieval system, without the prior written permission of Riscon Consultants.

#### **Foreword**

These Coherent Health & Safety specifications for SAPS Mankweng has been compiled by using the Occupational Health & Safety Act. no 85 of 1993 and the Construction regulations as amended on 7 Feb 2014. This document has been drawn up to assist the Principal contractor and the contractors to comply with the Act and the applicable regulations.

Should there be any contradiction between this document and the Act, the Act must take preference except where explicitly stated. Similarly, where this document does not address a certain topic / task the act and applicable regulations must be used as the minimum requirement.

Should you be unclear about anything set out in this document, please contact this office.


These specifications are site specific and include all works to be done by the principal contractor. The principal contractor will be responsible for all the work on site.

Every endeavour has been made to address the most critical aspects relating to Health and Safety issues in order to assist contractors in adequately providing for Health and Safety of employees on site. However, the Principal Contractor is required to ensure they stay compliant with statutory requirements and construction programs and processes and include such aspects in their Health and Safety file.

These health and safety specifications was prepared by J.Heyneke registered at the South African Council for the Project and Construction Management Professions (SACPCMP) as an Candidate Construction Health and Safety Agent (CanCHSA/204/2022)

No part of this document may be reproduced, transmitted, transcribed, and stored in a retrieval system in any form or by any means without written permission. Any unauthorised reproduction of this work will constitute a copyright infringement and render the perpetrator liable under both civil and criminal law.

#### Communication channel



#### **Table of Contents**

FOREWORD	3
1. INTRODUCTION	6
1. BACKGROUND TO THE COHERENT HEALTH & SAFETY SPECIFICATIONS	6
2. RESPONSIBILITY & ACCOUNTABILITY	
3. Purpose of the Health and Safety Specifications	
4. IMPLEMENTATION OF THE HEALTH AND SAFETY SPECIFICATIONS	
5. ABBREVIATIONS	
2. OCCUPATIONAL HEALTH & SAFETY MANAGEMENT	
2. IMPLEMENTATION OF THE HEALTH AND SAFETY SPECIFICATIONS (DRAFTING OF THE COHERENT HEALTH & SAFETY PLAN)	· ·
3. OCCUPATIONAL HEALTH & SAFETY MANAGEMENT	12
1. Scope of the project	12
2. THE EXTENT OF THE WORKS	12
3. Interpretations	13
Application	13
Definitions	13
4. MINIMUM ADMINISTRATIVE REQUIREMENTS	13
Notification of construction	
Notification of construction	13
Notice Board	15
5. Principal Contractors, Contractors and Sub-Contractors	
Principal Contractor's and Contractors' Requirements	
Principal Contractor / Contractor Competency Assessment	
Pricing for Occupational Health & Safety Compliance	
Contractors' Coherent Health & Safety Plans [Construction Regulations 7]	
Communication and Management of the work	
6. CLIENT IDENTIFIED HAZARDS AND POTENTIALLY HAZARDOUS SITUATIONS	
OHS Agent risks identified	
Local weather	
Unforeseeable Hazards	
7. SITE OPERATIONAL REQUIREMENTS	
1. Health and Safety Representative	
2. Health and safety committees	
3. Health and safety training	
4. Health & safety audits, monitoring and reporting	
5. Emergency procedures	
6. Medicals certificate of fitness	
7. First aid boxes and first aid equipment	
8. Personal protective equipment (PPE) and Clothing (PPC)	
9. Occupational Health and Safety signages	
10. Site hording & Access control	
11. Night Work (After Hours)	
12. Transport of workers	
13. Wind	
15. Fatigue management	
8. Physical Requirements	
O. I BESTAL NEGOTIALISED J	

1.	Site establishment	5 26
2.	Principal Contractor Construction board	
2. 3.	Existing structures CR 11	
3. 4.	Underground and internal services	
5.	Demolition CR 14	
5. 6.	Earthworks (Civil works) CR 13	
7.	Excavations CR13	
8.	Heritage and Archaeological sites	
9.	Graves & Middens	
J. 10.		
11.		
12.		
13.		
14.	Edge protection, Barricading and Penetrations	36
15.	Roof work CR 10	
<i>16</i> .	Temporary works CR 12	
17.	Traffic and pedestrian accommodation	
18.	Confined Spaces	39
19.	Deliveries, Waste removal , Stacking/Storage of materials	40
20.	Fire extinguishers and firefighting equipment	40
21.	Designated smoking area	
22.	Thunder & Lighting	40
23.	Concrete work	
24.	Brickwork	
9. P	LANT, EQUIPMENT AND MACHINERY	42
1.	Construction Vehicles & Mobile plant CR 23	42
2.	Hired plant and machinery  Cranes and lifting equipment	43
<i>3</i> .	Cranes and lifting equipment	43
4.	Explosive actuated fastening devices	44
<i>5</i> .	Electrical Installation and portable electrical Tools	
6.	General Machinery	
10.	OCCUPATIONAL HEALTH	45
1.	Industrial Hygiene	
<i>2</i> .	Hazardous Chemical Substance (HCS)	
3.	Alcohol and other drugs	
4.	Medical certificate of fitness	
5.	Welfare Facilities	
6.	Ergonomics	
<i>7</i> .	COVID 19.	48

#### 1. Introduction

#### 1. Background to the coherent health & safety specifications

The Construction regulations (7 Feb 2014) places the Onus on the CLIENT to prepare coherent health & safety specification, highlighting risks not successfully eliminated during design. The client (Naam) also has the opportunity to set the tone and standard of occupational health & safety on the construction site.

#### 2. Responsibility & Accountability

It is imperative to understand the process of determining legal accountability, as the OHS Act is the only criminal Act still administered by the Department of Labour. It assumes that the CEO is overall accountable even though he may delegate some of his responsibilities. This principle is entrenched in Section 37(1) of the Act. This is generally referred to as the REASONABLE MAN TEST. SECTION 37: Acts or omissions by employees or Mandatories

#### 3. Purpose of the Health and Safety Specifications

The purpose of this specification document is to provide the relevant Principal Contractor) and contractor with any information other than the standard conditions about construction sites that might affect the health and safety of persons at work and of persons in connection with the use of plant and machinery during Construction work.

#### 4. Implementation of the Health and Safety Specifications \

To brief the Principal and Contractor on the project's significant health and safety requirements and aspects. This shall include the provision of the following information and requirements, namely:

- a) safety considerations affecting the site of the project and its environment.
- b) health and safety aspects of the associated structures and equipment.
- c) required submissions on health and safety matters from the Principal Contractor (and Sub Contractor).
- d) the Principal Contractor's (Sub Contractors) health and safety plan.

To serve to ensure that the Principal Contractor (Contractors) is fully aware of what is expected from them with regards to the Occupational Health and Safety Act, 85 of 1993 and the Regulations made there-under including the applicable safety standards, and in terms of Section 8 and 44 of the Act.

To inform the Principal Contractor that the Occupational Health and Safety Act, 85 of 1993 in its entirety shall apply to the contract to which this specification document applies. The Construction Regulations promulgated on 7 February 2014 and incorporated into the above Act by Government Notice R 84, published in Government Gazette 37305, shall specifically apply to all persons involved in the construction work about this project.

"Purpose of the Act" –To provide for the health and safety of persons at work and the health and safety of persons in connection with the use of plant and machinery; the protection of persons other than persons at work against hazards to health and safety arising out of or in connection with the activities of persons at work; to establish an advisory council for occupational health and safety; and to provide for matters connected in addition to that.

"Agent" -means a competent person who acts as a representative for a client.

"Client" -means any person for whom construction work is performed.

"Construction manager" means a competent person responsible for the management of the physical construction processes and the coordination, administration, and management of resources on a construction site.

"Construction site" means a workplace where construction work is being performed.

"Construction supervisor" means a competent person responsible for supervising construction activities on a construction site.

"Construction work" means any work in connection with -

- a) The construction, erection, alteration, renovation, repair, demolition, or dismantling of or addition to a building or any similar structure; or 6
- b) The construction, erection, maintenance, demolition, or dismantling of any bridge, dam, canal, road, railway, runway, sewer, or water reticulation system; or the moving of earth, clearing of land, the making of excavation, piling, or any similar civil engineering structure or type of work.

"Contractor" means an employer who performs construction work.

#### "Designer" means-

a) A competent person who-

Prepares a design;

Checks and approves a design;

Arranges for a person at work under his or her control to prepare a design, including an employee of that person where he or she is the employer; or Designs temporary work, including its components;

- b) An architect or engineer contributing to, or having overall responsibility for a design;
- c) A building services engineer designing details for a fixed plant;
- d) A surveyor specifying articles or drawing up specifications;
- e) A contractor carrying out design work as part of a design and building project; or an interior designer, shop-fitter, or landscape architect;

"Health and Safety File" -means a file, or other record containing the information by the Construction Regulations;

"Health and Safety Plan" -means a site, activity, or project-specific documented plan in accordance with Mercurius Motor's health and safety specification;

"Health and Safety Specification" –means a site, activity, or project-specific document prepared by the Department of Public works & infrastructure pertaining to all health and safety requirements related to construction work;

"Method Statement" –means a document detailing the key activities to be performed in order to reduce as reasonably as practicable the hazards identified in any risk assessment; "Principal contractor" means an employer appointed by the Department of Public works & infrastructure to perform construction work;

"Risk Assessment" –means a program to determine any risk associated with any hazard at a construction site, in order to identify the steps needed to be taken to remove, reduce or control such hazard.

#### 5. Abbreviations

GMR: General Machinery Regulations

OHS Act: Occupational Health & Safety Act. Act 85 of 1993

Constr Reg: Construction Regulation 2014

ORHVS: Operating Regulations for High Voltage Systems

PPE: Personal Protective Equipment
GAR: General Administrative regulations

DMA: Disaster Management Act

QS: Quantity Surveyor

GSR: General Safety regulations

EXP Reg: Explosive Regulation

ERW: Environmental regulations for workplaces

FR: Facilities Regulations

HCS: Hazardous Chemical Substance Regulations
NIHLR: Noise Induced Hearing Loss Regulation

DMR: Driven Machinery Regulation
EIR: Electrical Installations Regulation
EMR: Electrical Machinery Regulation

Coherent Health & Safety Specification for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants© RisCon Consultants (All copyrights reserved)

RN: Road Note 13

NT: National Road Traffic Act
AR: Asbestos Regulation

NEMA: National Environmental Management Act

SANS: South Africa National Standards MSDS: Material Safety Data Sheets

## 2. Occupational Health & safety management

#### 1. Roles

## Client/ Agent

a) Prepare a baseline risk assessment and issue a health and safety specification to the Principal Contractor. Designer and include the specification in tender documentation.

b) Department of Public works & infrastructure or the appointed Client Agent will appoint each Principal Contractor for this project or phase/section of the project in writing for assuming the role of Principal Contractor as intended by the Construction Regulations.

c) Department of Public works & infrastructure or the appointed Client Agent shall discuss, negotiate, and approve the contents of the specified project health and safety plan submitted by the Principal and Sub Contractor.

d) Department of Public works & infrastructure or his Agent will take reasonable steps to ensure that the health and safety plan of the Principle and Sub Contractor is correctly implemented and maintained. Monthly audits shall be conducted to monitor the compliance.

e) In the event of design changes Department of Public works & infrastructure or the appointed Agent on his behalf will ensure that enough resources will be provided to implement the work safely.

f) Department of Public works & infrastructure or his appointed Agent on his behalf, will prevent the Principal Contractor and/or the Contractor from commencing or continuing with construction work should the Principal Contractor and/or the Contractor at any stage in the execution of the works be found to:

have failed to have complied with any of the administrative measures required by the Construction Regulations in preparation for the construction project or any physical preparations necessary in terms of the Act;

have failed to implement or maintain their health and safety plan;

have executed construction work which is not in accordance with their health and safety plan;

have acted in any way which may pose a threat to the health and safety of any person(s) present on the site of the works or in its vicinity, irrespective of him/them being employed or legitimately on the site of the works or in its vicinity.

#### Designer

- Must take into account the health and safety specifications of Department of Public works & infrastructure.
- Before the tender process, the designer must make available a report to Department of Public works & infrastructure about :
  - All the relevant health and safety information about the design of the relevant structure that might affect the pricing of the construction work.
  - o The geotechnical -science aspects, where appropriate.
  - o The loading that the structure is design to withstand.
- Inform Department of Public works & infrastructure in writing of any known or anticipated dangers or hazards related to the project.

- Make available all relevant information required for the safe execution of the work upon being designed or when the design is subsequently altered.
- During the design take into account the hazards relating to any subsequent maintenance to be performed with the minimum risk.
- During the design stage cognizance of ergonomic design, principles must be applied in order to minimize ergonomic-related hazards in all phases of the life cycle of a structure.

#### **Quantity surveyor**

The Quantity surveyor shall ensure that the contractor has made sufficient provision for all health & safety costs. The quantity surveyor shall ensure that the contractor had in a bill of quantities for health & safety. The QS takes full responsibility if the contractor does not have a sufficient budget to cater to all Health & safety needs.

## **Construction Health & Safety Officer Duties**

A <u>full-time</u> construction health and safety Officer (in terms of Construction Regulation 8) will be required for this project. The Construction Health and Safety Officer must be registered with SACPCMP on at least a Construction Health and Safety Officer level and proof of the appointee letter of good standing is compulsory before any work can commence. The safety officer need to be fully registered and not a Candidate safety officer. Can.CHSO will not be accepted.

The construction safety officer will be required to carry out at least the following duties:

## Before commencement and during the construction phase of the project you shall:

- Assist with the preparation of a construction health and safety plan
- Confirm necessary documentation was submitted to the relevant authorities
- Attend project planning meetings
- Assist with the assessments and approval of subcontractor(s) health and safety plans
- Attend the site handover #
- Attend regular site, technical and progress meetings
- Facilitate health and safety site meetings
- Participate in the identification of the hazards and risks relevant to the construction project through regular coordinated site inspections
- Establish and maintain health and safety communication structures and systems, distribution of health and safety-specific documents to sub-contractors
- Compiling project-specific emergency response and preparedness plans
- Testing the effectiveness of the emergency response plans
- Conduct site safety inductions
- Monitor, measure, and report on health and safety system performance by performing monthly health and safety audits
- Evaluate the levels of compliance of subcontractors to the project-specific health and safety plan and client specifications
- Oversee the reporting and investigation of project-related incidents
- Manage to report of non-compliance issues and take appropriate corrective and preventative action
- Oversee the maintenance of all records
- Incorporation of changes into a health and safety management system
- Review and update the health and safety plan

#### At the close out of the project, you shall:

- Review, discuss and approve the health and safety file with the contractor(s) and manage site health and safety during the defects liability period
- Prepare the consolidated project health and safety file for the client
- After the project the Principal Contractor will hand over the file Riscon to cancel certain documents. The fille will then be scanned in by the Principal Contractor according to annexure I that is attached and will be handed over to the client on a USB

#### In addition to the above, it is also your duty to:

- · Enforce such measure as may be necessary in the interest of health and safety;
- That all employees are informed regarding the scope of their authority as contemplated in Section 37.1.b of the Act;
- That all necessary measures are taken to ensure that the requirements of the Act and its regulations are complied with by every person employed at Principal Contractor
- Ensure that the required training and knowledge is provided regarding the terms of the Act and regulations.
- Provide all employees and contractors with access to the Occupational Health and Safety Act as well as the organization's SHEQ program documentation and information as is necessary and where required.
- You are charged with reporting on the following issues, trends and other relevant information to myself:
- Deviations and areas of non-compliance (which you cannot rectify) -- Immediately.
- Submitting a monthly report

The monthly report shall consist of the following information and shall be submitted in the approved format of trends, graphs, completion and databases:

- · Site Inspections.
- Internal Inspections/Audits.
- Planned Task Observations.
- Task Analysis.
- Continuous Risk Assessments.
- · Performance Measurement of Employees.
- Incidents (Near misses, Accidents, Illnesses, First Aid Treatments)
- Investigations
- Tool box talks
- Medicals (New employees, Scheduled medicals)
- Competency information (Drivers, First Aiders, Fire Fighters, HS Representatives etc)

## **Construction Manager Duties**

In terms of this appointment, you are personally accountable and responsible for the overall management of the site. If the project is a construction work permit project, the Construction manager shall be registered with SACPCMP as a PR.CM category or must have a valid SAQA recognized formal qualification on NQF level 7.In addition thereto, you are also responsible for ensuring compliance with the requirements in terms of Health and Safety on these sites. To this end, you are to ensure that the following documented procedures are adhered to at all times:

- · The Health& Safety Specification for the project,
- The Approved Health & safety Plan for the project issued by our company,
- The Approved Health & safety Plan of each contractor appointed for the project.

You are required to appoint Assistant Construction Managers to assist you in performing your duties, but under no circumstances may you manage any other projects other than the one to which this appointment refers.

You are required to appoint Construction Supervisors for various sections of the Site to assist in the implementation and enforcement of the health & safety procedures detailed in the Health & Safety Plans.

You are required to report to me on the following issues every month:

## Examples:

- Health and Safety Representative Inspections.
- Internal Inspections/Audits.
- Planned Task Observations.
- Task Analysis.
- · Continuous Risk Assessments.
- · Performance Measurement of Employees.
- Incidents (Near misses, Accidents, Illnesses, First Aid Treatments)
- Investigations
- Medicals (New employees, Scheduled medicals)
- Competency information (Operators, Drivers, First Aiders, Fire Fighters, HS Representatives etc.)

# 2. Implementation of the Health and Safety Specifications (Drafting of the coherent Health & Safety Plan)


These health & safety specifications document forms an integral part of the contract, and the Principal Contractor is expected to use it when compiling its project-specific coherent health & safety plan. The Principal Contractor must forward a copy of these specifications to all Contractors at their bidding stage so that they can in turn prepare coherent health & safety plans relating to their operations. This Specification can be revised during the construction process as new risk and hazards arises or in the case of a scope change

## 3. Occupational Health & Safety Management

## 1. Scope of the project

These Specifications set out the requirements for eliminating or if this is not possible, for minimising as far as reasonably practicable, the risk of incidents and injuries occurring at Client. This document covers work to be undertaken of the project and sets out the rules and procedures for engagement on the project. The scope also addresses legal compliance, Client standards, hazard identification and risk assessment, risk control, and the promotion of a health and safety culture amongst those working on the project. The health & safety specifications also make provision for the protection of those persons other than employees

# The 6 Stages of Construction (SACPCMP)



## 2. The extent of the works

The Project Comprises the construction of the following:

- The living quarters are basically complete and only minor finishing required.
- The police station: The cell block kitchen and generator room to be completed including a concrete slab over certain areas. Block B (bottom left on site plan) must still be re-built after demolition of original building, including concrete slabs over certain areas. See item on page 5 of report and drawing.
- The balance of the works are just completion of items refer to outstanding work report attached.

## 3. Interpretations

## **Application**

This specification is compiled with reference of South African legal requirements. and the client's specifications. The PC is reminded that if any additional guidelines are required, the construction manager has to contact the client or representative directly to prepare and issue updated guidelines. The definitions as listed in the Occupational Health & Safety Act 85/1993 and Construction Regulations (February 2014) apply throughout this document.

#### **Definitions**

The definitions as listed in the OHS Act 85/1993 and Construction Regulations (2014)

- CHSA = Construction Health & Safety Agent
- - Contractor includes a Principal Contractor / Direct / Sub-contractors.
- Contractor's Construction Manager as defined in the Construction Regulations 2014 [CR 8(1)] as the Construction Manager. This is not the Client's Project Construction Manager / site representative.
- Directs Any Contractor appointed directly by the construction Client.
- Principal Agent = P/Agent = Client Representative.
- Principal Contractor will include any Contractor appointed directly by the Client on the project.
- - Where the term Principal Contractors (plural) is used this refers to all Directs appointed on the project, which Directs are all Principal Contractors in their own right.

## 4. Minimum Administrative Requirements

#### Notification of construction

Notification of construction. (CR 4) PC will submit the notification to the Provincial Director of the Department of Labour in writing of the intent of construction work 7 days before commencing the work. A copy of this notification and proof that it was faxed to the department must be available in the file on-site. (CR 4 Feb 2014). Owing to the construction permit issued, it is not necessary to notify the Provincial Director of the Department of Labour of the construction. (CR 4 Feb 2014)

#### Principal Contractor (CR 5)

The client selected and direct appointed contractor's will work directly under supervision of the appointed Principal Contractor. The PC will issue the specification or applicable section thereof to the contractor. The client appointed **Principal Contractor** with the responsibility to carryout and supervise the required construction, own selected and client direct appointed contractor's. The client and designers issued the principal contractor (PC) with the following documents:

- CR 5 Appointment
- Mandatory agreement
- Project baseline risk assessment
- Project site specification
- Project design and drawings
- Demolition permit

The PC shall comply with the clients specification and appoint a fulltime qualified, registered SACPCMP safety officer for the project to support the project construction manager, managing project safety Further:

The safety officer/manager will be responsible to carryout general safety officers duties, specifically

- Audit contractors SHE plan and project file 7 days before the start of the contract.
- Record all appointed contractors audit scores on the register attached. (Appendix A)
- Forward the reports required by this specification to the project safety agent on the 25 the day of the monthly.
- To keep an updated project risk register (PC and contractor task risk assessments)
- The PC will ensure that project H&S file and all contractor files will consist of the following:
- Updated index or content register
- Client mandatory agreement and CR5 appointment
- A company project HS&E policy
- A company project HS&E plan which shall display be written using the Coherent health & safety specification a standard
- A detailed organogram that display all the appointments that will be made for the project that includes contractors that will be appointed.
- All appointments accompanied by the members ID, competencies and medicals
- The risk assessment methodology, method statements or procedures and risk assessments for all tasks and activities.
- Specific tasks required detailed operational plans or method statements, This will be supported by task and PPE assessments.
- The PC's incident and accident plan and methodology of reporting incidents with supported registers and documentation e.g. Incident report, Annexure 1, WCL2 and investigation proforma.
- Fall protection plan specific developed for the task and hazards, identified.
- Copies of registers and inspection sheets.
- MSDS'e for all hazardous chemicals on site A

Before the PC appoints a contractor, the PC must ensure that the contractor is competent for the task, is in good standing with the compensation commissioner and has the resources to execute the task safely. Refer CR 7(1)(c). The PC to ensure that:

- The contractor is register and in good standing with the workman's compensation commissioner, if not, the PC must register the C, and pay the levies required. (COID Act 89)
- The PC will issue applicable sections of the project specification and sections of its own SHE plan as safety guidelines to each contractor to ensure work on-site is done according the required standard.
- The contractor appointed a qualified health & safety representative that will assist the supervisor in doing the applicable registers & checklists.
- The project PC will be responsible to approve the appointed contractor safety files
- The project PC will assess and audit the (sub) contractor file before allowing the contractor starting on the project.
- The project PC will do monthly audits on the (sub) contractors and send the audits on a monthly basis before 25th of each month
- The project PC safety officer will carry PTW (permit to work) to ensure the (sub) contractor conduct the task to meet the project standard.

The PC will keep an updated register with relevant data of all contractors appointed for the project. The register must contain the date of appointment, the status of the file audit, reference to legal documentation (mandatory agreement and appointment). This register must kept on-site for inspection. That the PC project file is developed, kept updated and available on-site for the duration of the project. That all employees registered to work on-site receive site safety induction, are medically fit and in procession of an updated medical fit certificate. Members scheduled to work at heights, medical certificates must indicate that the member was tested and fit to conduct work at heights. That own- (PC's) and contractor files will be audited on a monthly basis and that Noncompliance reports are forwarded to the clients agent. Prove that the Non-compliances are eliminated must be available in the file. When practical completion of the contract is obtained and issued to the client, the PC/safety officer will:

- cancel all appointed contractors, agreements and appointment
- ensure that new agreements are signed with the maintenance team, that the maintenance team SHE plan and file is assessed and that the team is controlled by a competent supervisor.
- ensure that the project SHE file will be updated for handover to the client

#### **Notice Board**

The PC is required to erect a noticeboard on-site to display the following :

- The PC company's Health and Safety Policy signed
- List of the emergency numbers
- The emergency and evacuation plan (map/diagram)
- The PC will display a safety organogram (in the safety file) indicating the health and safety
  appointments for the project. The structure will also be available on the noticeboard.
- A copy of the construction permit /Notification of construction
- COVID 19 Policy
- · Letter of good standing
- Public liability
- Site safety rules

#### **COVID 19 - Risk Assessment**

- Contractor need to review their existing Risk Assessment (existing vs additional controls for COVID-19). Clients Agent will provide revised Baseline R/A.
- Additional controls in R/A to cover e.g.: adequate supply of wash basins; cleaning materials; disinfecting work areas with hand sanitisers; access control; PPE requirements; meeting requirements; COVID-19 training; emergency planning; hygiene; meals; breaks etc.
- There should also be a separate Health Risk Assessment in place.
- The R/A should address specific HIGH RISK areas and describing the type of PPE to be worn, as required by task

#### General Record Keeping

The Principal Contractor and all Contractors must keep and maintain all the necessary Health and Safety records to demonstrate compliance with these Coherent Specifications, the OHS Act 85/1993, and the Construction Regulations (February 2014). The Principal Contractor must also ensure that all records of incidents/injuries, emergency procedures, training, planned maintenance inspections, monthly contractor audits, etc. are kept in the health & safety file(s) held in the site office. The Principal Contractor must ensure that every Contractor keeps its own health & safety file, maintains the file and makes it available on request (the file must include the Contractor's health & safety plan and all relevant records). Such 'Contractor safety files' must be audited by the Principal Contractor on a monthly basis with audit reports kept as proof.

## Offences and penalties

Fines may be imposed on the Principal Contractor and Contractors for ongoing non-compliance with the provisions of the Client's Coherent Health & Safety Specifications, the Principal Contractor's Coherent Health & Safety Plan. Non-compliances identified during safety agent audits and visits will be categorized into one of three levels based on severity. These will be as follows:

- Life threatening situation an explanation in an audit report. This activity must be seized immediately and corrective measures taken.
- Serious injury possible a non-compliance will be issued with a time frame for compliance stipulated.
- Minor or no injury may result an improvement notice will be issued.

## Safety Non-conformance penalty/fines description:

Category	Non- compliance	Penalty Amount
N S N N S S N	Unsafe working at heights	R 10 000
	Contractor not complying with the OHS spec as issued & signed	R 10 000
	Safety officer not on site as required (mentioned in Spec)	R 10 000
	Contractor performing construction without a file approval letter from Riscon Consultants	R 10 000
70	No fall arrest equipment being used	R 5 000
n Risk	Contractor preforming construction without a construction permit or construction notification stamped from department of employment and labour	R 10 000
<b>.</b>	Working at night without any notification to Riscon	R 10 000
High	No supervision available on site (according to appointments in file)	R 10 000
	Alcohol & Drug abuse	R 4 000
	Speeding on site (exceeding 40 km p/h)	R 4 000
	Working on heights without approved fall protection plan in place	R 4 000
	Unsafe scaffolding being used	R 5 000
	Working in Unsafe Excavations	R 4 000
	Workers not wearing Compulsory PPE for task preformed	R 2 500
Medium Risk	Contractor not reporting incident and accidents within 24 hours to Riscon Consultants	R 2 500
	Unsafe electrical work being preformed	R 2 500
0 0	Medicals not in place	R 3 500
5	No competent first aider & Fire fighter on site	R 3 500
	Operator of machinery operating without applicable competency	R 2 500
	Applicable signage is not displayed	R 1 500
Low Risk	Employees driving plant & Construction vehicles while talking on the cellphone	R 1 500
	Poor housekeeping	R 1 500
	Employees not making use of the ablution facilities available	R 1 500
2	Making use of unsafe ladders	R 1 500
Ľ	Environmental Spillages	R 1 500
	Employees using unsafe electrical equipment	R 1 500

The client's safety agent has the right to impose fines as described above for non-compliances as set out in the categories. The non-compliance will be issued in to the contractor and the client. The Fines will be imposed with the idea that when a contractor receives a fine they should prove to the clients OHS agent and to the client in 7 working days how they spend that fine amount towards that specific non-compliance if possible otherwise towards any safety on site. In the case of repeated contraventions, the clients OHS agent shall recommended to stop the work to the client or the clients agent. These fines will be imposed by the Clients OHS agent with the 3rd Non-compliance

## 5. Principal Contractors, Contractors and Sub-Contractors

## **Principal Contractor's and Contractors' Requirements**

The Principal Contractor must ensure that all Contractors appointed by them comply with these Specifications, the Principal coherent health & safety plan as well as the OHS Act, Construction Regulations (February 2014), and other relevant legislation that may relate to the activities directly or indirectly. A Contractor, when appointing other Contractors as 'Sub-contractors', shall mutatis mutandis ensure compliance as if it was the Principal Contractor.

The Principal Contractor may only allow a Contractor to begin work on site after receiving a coherent health & safety plan which must include a project specific hazard identification, risk assessments and safety measures. The Principal Contractor must test competency and finally approve his sub — contractor coherent site specific health and safety plan. The Principal Contractor must audit each of its contractors on a monthly basis, with audit reports kept in the health & safety file on site. The audit must include an administrative assessment as well as a physical inspection of the contractor's site activities. The Principal Contractor must stop any Contractor from carrying out construction work that is not in accordance with the Principal Contractor's and/or Contractor's health & safety plan or if there is an immediate threat to the health and safety of persons.

The Principal Contractor shall take all reasonable steps necessary to ensure co-operation between all contractors to enable each of those contractors to comply with the provisions of the Construction Regulations;

The Principal Contractor shall take all reasonable steps to ensure that each contractor's coherent health and safety plan is implemented and maintained on the construction site: Provided that the steps taken shall include periodic audits at intervals mutually agreed upon between the Principal Contractor and contractors, but at least once every month;

The Principal Contractor must ensure that where changes are brought about to the design and construction, that sufficient health and safety information and appropriate resources are made available to contractors so as to allow them to execute the work safely;

The Principal Contractor must ensure that every contractor is registered and in good standing with a recognised compensation fund or with a licensed compensation insurer prior to work commencing on site;

The Principal Contractor must ensure that potential contractors submitting tenders have made provision for the cost of health and safety measures during the construction process;

The Principal Contractor shall discuss and negotiate with the contractor the contents of the coherent health and safety plan and shall finally approve that plan for implementation;

The Principal Contractor shall hand over a consolidated health and safety file to Department of Public works & infrastructure upon completion of the construction work and shall include a record of all drawings, designs, materials used and other similar information concerning the completed structure;

The Principal Contractor may only appoint a contractor to perform construction work when such Principal Contractor is reasonably satisfied that the contractor he or she intends to appoint, has the necessary competencies and resources to perform the construction work safely and that the contractor is an approved Client contractor.

The Principal contractor will ensure that with all the necessary safety equipment that will be required that one of the Items will be a wind meter that will be on site at all times.

SITE INDUCTED

SITE

NO

The principal contractor must ensure that all employee shall have an induction sticker on their hard hat to show they have received induction with the date and site name, see example bellow:

The Principal contractor will ensure that every employee on site will have a valid ID copy available in the safety file.

After the project the Principal Contractor will hand over the file Riscon to cancel certain documents. The fille will then be scanned in by the Principal Contractor according to annexure I that is attached and will be handed over to the client on a USB

## **Principal Contractor / Contractor Competency Assessment**

The Principal Contractor must be reasonably satisfied that the contractors it intends to appoint have the necessary competencies and resources to safely conduct the work they will be appointed for. This should be established at tender stage and before appointments are made. One of the preferred ways of determining whether a contractor is competent is to make sure the contractor is an accredited contractor for Client. Once the contractor is appointed, but before it begins work on site a site- specific safety plan must be discussed and negotiated with the Principal Contractor. Such safety plan must be approved for implementation by the Principal Contractor.

The Principal Contractor and Contractors should submit the following documentation for perusal and verification by Department of Public works & infrastructure and Principal Contractor respectively:

- Coherent health & safety plan as compiled for this project; (including Risk assessments, safe work procedures, fall protection plan
- Management Structure as envisaged at tender (organogram);
- Letter of Good Standing with the Compensation Commissioner or FEM;
- Proof of health & safety training and other related training; (CV and certificates) Legislative appointment letters
- Medical certificates of employees that will be working on site on annexure 3 format stamped by occupation health practitioner.
- Notification of Construction work; (proof notification was done)

#### Pricing for Occupational Health & Safety Compliance

All parties bidding to do work on this construction project must ensure that they have made provision for the cost of complying with this Specifications document as well as with the OHS Act and incorporated Regulations as a minimum requirement in their tender documentation. It must also be taken into consideration that time is money, which implies that sufficient time must be allowed for the implementation of the minimum OHS standards. No additional claims will be entertained at a later stage should a compliance requirement be prescribed in the OHS Act, incorporated regulations or in this Specifications document due to design changes which would require additional resources. The professional quantity surveyors must develop a strategy in this regard to ensure that H&S costs have received sufficient consideration. Contractors must make use of Annexure 'H' herein below as a guide when pricing health & safety on this project. Health & safety costs must be clearly set out in the tender submission by each and every contractor. The contractors shall also make provision for COVID 19. This provision need to be approved by the client or clients agent. All items must be looked into depth to ensure every step and cost of the task is accounted for. Example temporary

works, Temp Designer, Temp supervisor, scaffolding hire, scaffold training, working at height training, fall protection plan developer & edge barricading needs to be covered in the cost for temporary works.

## Contractors' Coherent Health & Safety Plans [Construction Regulations 7]

#### Introduction:

The Construction Regulations (2014) aims to improve overall management and co-ordination of Health, Safety and Welfare throughout the Construction Phase and reduce the large number of serious and fatal injuries and cases of ill health, which occur every year in the Construction Industry.

In terms of the Construction Regulations (2014), the Principal Contractor is required to develop a Health and Safety Plan before work commences on site and review it throughout the Construction Phase. The degree of detail required in the Health and Safety Plan and the time and effort in preparing it should be in proportion to the nature, size and level of Health and Safety risks involved in the project. Projects involving minimal risks will call for simple, straightforward plans. Large projects or those involving significant risks such as this project will need much more detail.

What should the construction health & safety plan cover?

The Construction Health and Safety Plan should set out the arrangements for ensuring the Health and Safety of everyone carrying out the construction work as well as all other persons who may be affected by it. The index of this plan must be in line with Annexure A

#### Communication and Management of the work

The Principal Contractor must indicate in its health and safety management plan that it has made provision for the following:

- · Management structure and responsibilities
- Health and Safety goals for the project and arrangements for monitoring and review of Health and Safety performance i.e. safety meetings; contractor meetings; risk assessment review, etc.
- · Site specific rules and procedures.
- Arrangement for:
  - i. Regular liaison between parties on site i.e. meetings
  - ii. Consultation with the work force i.e. toolbox talks
  - iii. The exchange of design information between Department of Public works & infrastructure, designers, and Contractors on site
  - iv. Selection and control of Contractors i.e. selection criteria; inspections; audits, etc.
  - v. Site health & safety induction and onsite training i.e. toolbox talks
  - vi. Welfare facilities, first aid, emergency planning and fire prevention strategy
  - vii. The reporting and investigation of injuries and incidents including near misses what the intended system will be
  - viii. The production, approval and review of risk assessments, safe work procedures and method statements and how does the company's risk assessment system work.

## 6. Client identified hazards and potentially hazardous situations

## **OHS Agent risks identified**


- Existing services
- Interface with the public
- Hazardous chemical such as solvents, cleaning agents, cement, fuels, oils, epoxies, etc.
- Site security and access control issues
- Relocation and protection of existing services
- Finishing trades

## Local weather

The bellow graph shows the rainfall & wind for the last year. This gives the contractor an indication of a possible delay in time as well as hazards that could come into play


#### Rainfall

## Yearly Rainfall and Rain Days Averages



#### Wind

# Annual Wind Speed and Wind Gust Averages



#### **Unforeseeable Hazards**

The Principal Contractor must immediately notify Contractors as well as Department of Public works & infrastructure, in writing, of any hazardous or potentially hazardous situations that may arise during the performance of construction activities so that the necessary precautions may be taken before such work begins.

#### 7. Site operational Requirements

#### 1. Health and Safety Representative

The Principal Contractor and all Contractors must ensure that Health and Safety Representative(s) are appointed under consultation with the employees. The H&S representatives must be competent to carry out their functions. The appointments must be in writing. The Health and Safety Representatives should carry out monthly inspections, keep records of the inspections and report all findings to the Responsible Person or safety officer forthwith and at monthly health & safety committee meetings. At least one Health & safety representatives is required by all Employers on site.

The Principal contractor must ensure for every 1 – 20 employees at least one Health and safety representative is appointed. Every specific section must have a health and safety representative for example wet works, roof work, ceilings, electrical etc. The solution will be that every contractor appointed will have their own health and safety representative that has knowledge in that specific section.

#### 2. Health and safety committees

The Principal Contractor must ensure that project health and safety committee meetings are held monthly with minutes kept. Meetings must be chaired by the Principal Contractor's Responsible Person [CR 7(1) person]. All Contractors' Responsible Persons and Health & Safety Representatives must attend the Principal Contractor's monthly health & safety meetings. The Principal Contractor's appointed supervisors must also attend health & safety meetings. The following topics must be tabled at meetings: management appointments and risk management portfolios; sub-contractor legal compliance issues; injuries and incidents; hazards and risk assessments (present and foreseen); safety procedures; method statements for upcoming activities; planned inspections and registers/record keeping, etc. The committee chairperson must sign off and date the minutes.

## 3. Health and safety training

#### Induction

The principal contractor will ensure that all the employees, contractors, professional team members and visitors received site specific safety induction. Record of attendance will be kept in the health and safety file. (OHS Act sec 13). A record of attendance must be kept in the health & safety file. Workers must carry proof of inductions on their person while on site. Employees shall have induction stickers as displayed above in the spec that will be issued by the safety officer on site.

#### **Awareness**

The Principal Contractor will ensure that on-site toolbox talks/safety talks are scheduled for once a week. These talks will conducted by a senior member or the safety officer of the company and focusses on topics relevant the task, the hazards of the activities identified for the weeks programme. A documented record of attendance will be kept in the health and safety file. The toolbox talks will not replace any certified training or a DSTI. All contractors' employees must attend

safety awareness toolbox talks carried out by their supervisors, the attendance registers must be copied to the Principal Contractor together with information on the information discussed at the session.

#### Competence

Competency training is the training conducted where the course is developed to a SAQA standard or tertiary education/qualification. All competent persons must have the knowledge, experience, training, and qualifications specific to the work they have been appointed to supervise, control and/or carry out. This must be assessed on a regular basis e.g. training, evaluation, and periodic audits by Department of Public works & infrastructure, progress meetings, etc. The Principal Contractor is responsible to ensure that Competent Contractors are appointed to carry out construction work on site. If the unforeseen training has arisen then the matter can be resolved with the clients OHS agent appointed for the project. Act "General duties of employers to their employees". Sub- paragraph (e) of sub-section 2 requires inter alia the training of the employee to ensure as far as is reasonably practicable the health and safety at work of the employee. This means that internal training will be discussed in certain events but will also be approved in writing by the clients OHS agent before internal training can commence.

## 4. Health & safety audits, monitoring and reporting.

The Clients OHS Agent shall conduct at least one legal audit a month. This audit will be to audit the systems and processes put in place by the principal contractor. The Clients OHS Agent will also conduct at least once a site visit to inspect the physical aspects. The audit will be send to the client within 48 hours from the time of the audit. Note that this audit will happen at any time during working hours and that the OHS agent does not need to make and arrangement to conduct the audit. The principal contractor shall do an audit close-out within 3 days from receiving the audit.

The Principal contractor will be required to do a monthly audit on all contractors and send the audits to the OHS agent before the 25th of each month.

#### 5. Emergency procedures

The procedure must detail the response procedures including the following key elements:

- List of key competent personnel
- Details of emergency services
- Actions or steps to be taken in the event of the specific types of emergencies
- Evacuation procedures: including routes and exits to be available on a drawing.
- Emergency procedure(s) must include, but shall not be limited to: fire; spills; injury to employees; damage to material / equipment / plant; use of hazardous substances; bomb threats; major incidents/injuries; evacuation; etc.
- The Principal Contractor must advise Department of Public works & infrastructure in writing forthwith, of any emergency situations, together with a record of action taken/action to be taken.
- A contact list of all service providers (Fire Department, Ambulance, Police, Medical and Hospital, etc.) must be maintained and made available to site personnel.
- The emergency plan will need to be reviewed from time to time as conditions/environment changes i.e. as building work increases in extent.
- A emergency map layout that clearly shows where is the emergency assembly points is with all the fire fighting equipment
- Emergency plan shall include community unrest and what to do during this hazard An emergency drill shall be done in the first quarter of the construction phase. The principal contractor shall have footages available as well as attendance register to have proof of the drill.

#### 6. Medicals certificate of fitness

The Construction regulation 7.8 requires that all employees on site shall have a valid medical certificate of fitness. The medical shall be done by a registered occupational health & safety medical practitioner. The construction regulation of 2014 requires that every medical certificate shall be recorded on an annexure 3 format to ensure that the medical is done for the task specific. The nurse that does the testing bust be an occupational health nurse or must be busy with the course. The Dr or the institution must issue each worker with a medical fitness certificate that identifies how long the medical is valid for. Construction regulations definitions with comments explains the following: Medical fitness certificate: (b) Regulations 7(1)(g); 7(8); 17(12)(a); 10(2)(b); 22(1)(f) and 23 (1)(d)(ii) – A risk based approach should be applied when considering the method and frequency of periodic medical surveillance.

#### 7. First aid boxes and first aid equipment

The Principal Contractor and all Contractors must appoint First Aider(s) in writing. The Principal Contractor must appoint at least one First Aider to start with, which first aider must be certificated. Copies of valid certificates are to be kept on site. The Principal Contractor must provide at least 1 (one) first aid box, adequately stocked at all times. Due to the nature of this project i.e. satellite work stations/areas, further first aid boxes must be provided close to the various work stations to allow for quick, effective treatment of injured persons. As the work progresses and the structure increases in height, extra first aid.

## 8. Personal protective equipment (PPE) and Clothing (PPC)

The Contractor must ensure that all site workers are issued with and wear the appropriate PPE as indicated in their risk assessments. The Contractors must make provision and keep adequate quantities of SANS approved PPE on site at all times according to their risk assessments. Safety harnesses are mandatory wherever work takes place in an elevated area where safe working platforms or ladders are not possible. Overalls clearly indicating the Contractor's logo must be worn and all sub-contractors must conform to this requirement. Eye protection must be worn by those working grinders, skill saws, and high pressure water cleaners. Even those workers in close proximity to these operations will also be required to wear such eye protection. The COVID 19 regulations requires that the principal contractor shall issue each employee with at least 2 overalls. Each employees shall receive 2 cloth masks free of charge. Employees must wash the cloth mask after each day of work and use the clean one the next day. No bump caps will be allowed on site. According to DEL directive 3 no General Fabric Masks with breathing valves and Fabric Neck Buffs will be allowed on site. The principal contractor shall have visitors PPE available at the site office should site visitors not have the compulsory PPE to access the site. No bump cap shall be allowed on site.

#### 9. Occupational Health and Safety signages


The Principal Contractor must provide adequate on-site OHS signage. Including but not limited to: 'construction work - no unauthorised entry', 'beware of overhead work', 'hard hat area', first aid – to be posted up at all work areas/zones.

Signage must also be posted up at strategic locations to warn the public of diversions, alternative through ways and other irregularities caused by construction work (pedestrians and motorists)Signs are also required as per law e.g. scaffolding and other potential risk areas/operations such as exposed edges and openings and trenches / excavations where persons are at work. Safety signs and awareness posters will also be required in strategic locations on site such as frequently used access routes, stairways and entrances to structures and buildings where the workers will continuously be made aware of health & safety. Health & safety signage must be well maintained including weekly inspections, cleaning, replacement and repair. COVID 19 awareness posters shall be posted all over site by the principal contractor to ensure that the employees stay aware and stay safe.

## 10. Site hording & Access control

All construction work must be fenced off with controlled access points provided (this means locked access gates and access control personnel to be located at entrances to the construction work areas), preventing access to unauthorised persons. Where fencing is necessary, such fencing must be at least 1.8m high, erected and adequately secured from displacement. It is further required that the fencing is fitted with shade cloth to assist with dust containment.

Contractor access to the construction work areas will be limited to the specified access routes as agreed with the Client and must be strictly enforced by the Principal Contractor. Contractor employees will be required to carry ID tags and hard hat stickers (must display name of person, company name, ID number, and photo) indicating their authority to enter the construction zone. Such access tags/stickers must also serve as proof of H&S induction attendance — no tag/sticker, no entry. All visitor shall report to site office first for site visitors induction.



All access points to site must carry the necessary signage and site manager's (and safety officer) contact numbers.

COVID 19 procedure need to be followed with each person entering the site: Scan, Sanitize, Access control personnel complete sign in register, Access control personnel complete COVID 19 medical questionnaire. NO MASK NO ENTERY

## 11. Night Work (After Hours)

No night work will be allowed within the hazardous zone on this project without prior approval from Client / Client's Agent and the Construction Health and Safety Agent. If the Night work has been approved by the client and the client's agent additional documents will need to be in place for example: Employees medicals on annexure 3 must specify that they are fit for night work, sufficient illumination etc. Principal contractor must ask permission 5 working days in advance when they are planning to working at night. Principal contractor & Contractor will only be allowed to commence with night work once the documents has been approved by the clients OHS agent.

#### 12. Transport of workers

The principal contractor will shall not be allowed to transport any workers with tools or material in the same compartment. Separated compartment for tools must be available to prevent that no tools & material fall on employees in case of an accident. No employee will be allowed to be transported if he/she is not seated in a proper seat with a seatbelt approved & tested by the road department.

Persons together with goods or tools unless there is an appropriate area or section to store the tools or equipment; Contractors must adhere to the National Road Traffic Act.

#### 13. Wind

All roof work and Crane work & working at heights will be reconsidered when wind becomes a factor. The principal contractor will ensure that at all times there will be a wind meter on site.

- No roof sheeting will take place if the wind is above 20 KM per/hour.
- No crane work will take place if the wind is above 30 KM per/hour on at the area where the
  material, load must be placed with the crane

If Crane work is being done on site a wind meter shall be available on site at all times. If wind becomes a concern then the Safety officer or construction manager shall take the meter readings on an hourly basis to ensure that the tasks is being performed in safe conditions. See attached annexure **G** for record keeping purposes.

## 14. Drones

Riscon Consultants will make use of a drone to take progress pictures as well as to assist with hard to reach areas during construction

All employees on site must be aware that the operator of the drone will fly with caution and stay a safe distance away from any employee

If the construction site is within a restricted flight zone the operator of the employee will make use of the self-unlocking fly zone on the DJI website in order for him/her to have permission to fly in that specific area.

#### 15. Fatigue management

The first step in risk management process is to identify all reasonably foreseeable factors which could contribute to and increase the risk of fatigue. The principal contractor shall have a site specific fatigue management plan available on file. Fatigue is often caused by a number of inter-related factors which can be cumulative. Common factors that may contribute to fatigue are:

- Work schedules which limit the time workers can physically and mentally recover from work
- This may include workers who undertake shift work, night work, work extended hours or are not able to take regular breaks
- Sleep, including the length of sleep time, the quality of sleep and the time since sleep
- Environmental conditions, such as exposure to heat, cold, vibration or noise, can make workers tire quicker and may impair performance
- No-work related factors, such as a worker's lifestyle, family responsibilities or health may all increase the risk of fatigue

Methods that managers may utilize to identify whether there are any of the above risk factors affecting the workers include:

- Consulting with workers
- Examining work practices and systems of work
- Incident data and the findings of incident investigations
- Seeking advice and information from the Team or other relevant experts

#### 16. Illumination

Illumination on a construction is critical. The principal contractor shall ensure that the employees have a safe workplace to work to with sufficient illumination. No employee will be allowed to work in a part of a building if sufficient lighting is not available. Poor lighting is not just only a hazard but the quality of work can also be influenced.

The contractor shall at all times comply with the environmental regulation for workplaces. The regulation states exactly what the sufficient lux is for the specific workplace.

## 8. Physical Requirements

#### 1. Site establishment


Access control to the site, including notices of "construction-site" or "be aware of constructions activities" and "visitors to report to the site office" to be installed. COVID-19 access to be implemented, no screening, recording - no access

Identify a safe laydown area and layout of the contractor's containers/sheds to ensure the safety of tools, material and equipment. Display of evacuation signage to point out the route to the assembly. Effective barricading of engulfment areas, and installation of the appropriate signage. Also ensure that laydown areas:

- Are equipped with correct serviceable fire extinguishers and signage.
- The safety and safe keeping of contractor's equipment, tools and materials remain the responsibility of the contractor.
- The PC and contractors to apply sound and good housekeeping principles for the duration of the project.

Physical site security, security lighting and guards to be considered and applied or implemented.

Laydown plan need to be submitted to the clients agent and to the clients OHS agent for approval 5 working days before site establishment. See example of the plan below:



#### 2. Principal Contractor Construction board

The Principal contractor shall place a construction notice board at the site access road. If the site is not camped off then the board will be placed at the site office or the most used road on the construction site. The contractor shall display the major hazards on the board as well as the construction manager, construction supervisor and the safety officer cell numbers. This will assist the public that if an emergency happens that they will be able to make contact with site management. The construction board shall be at 1,2m by 1,2 m on cromadec or ABS sheet. Below is an example of a contractor board that is explained above:



#### 3. Existing structures CR 11

The PC will ensure that the provisions of the regulation CR 11:2014 are met and record is kept of inspections carried out by a competent person of the integrity of the structure and the following: The drawings pertaining to the design of the structure are kept on-site and are available on request of an inspector, client or representative and employees. That project drawing issued comply with the requirements as displayed in SANS 10400 Part A e.g. displaying the required signage, notes, dated and signed by the draftsman and responsible person and stamped "issued for construction. That the structure is inspected and any signs of damaged reported to the structural engineer. The construction manager must ensure that no structure or part of a structure is loaded in a manner which would pose a risk of collapse. Records of all inspections must be kept in a register onsite. Before demolishing of a structure, that the structural engineers method statement is received and studied to ensure the support. Structures supervisor shall be appointed in writing with CV and proof of qualifications attached.

#### 4. Underground and internal services

The P/Contractor must ensure that all existing internal and underground services are known before starting any demolitions work on site. Where Way Leaves are required, they must be applied for by the P/Contractor and will serve as indications of the relevant services. Should the location of services (electrical, water, gas, sewer, etc.) not be known, are deemed to be inaccurate, or if it is suspected that services might be present, the Client must mandate the Contractor to make use of the necessary detection equipment in order to accurately. When possible drawings of services shall be obtained by the principal contractor from the local municipality.

#### 5. Demolition CR 14

Any Contractor carrying out demolition work must ensure that prior to any such work being carried out, and in order also to ascertain the method of demolition to be used, a structural engineering survey of the structure to be demolished must be carried out by a competent person and that a method statement on the procedure to be followed in demolishing the structure is developed. It is required that a detailed demolitions method statement be included as a tender returnable document for assessment by the consulting structural engineer and clients OHS agent appointed to the project.

In addition to CR14 the following measures must also be adhered to:

- The Contractor must appoint a competent person in writing to supervise and control all demolition work on site;
- No demolition work may be carried out until the risk of injury and property damage has been identified, assessed for risk, and such risk of injuries and property damage has been eliminated, and proven to the consulting structural engineer and/or similar engineer i.e. appointed by the demolitions contractor;
- The Contractor must ensure that any partly demolished structure does not pose a safety risk to workers or members of the public;
- Should the Contractor be in doubt about the safety of a partly standing structure, the structure
  must be demarcated at a reasonable distance and sign posted, warning persons of the risk until
  such structure is made safe:
- The Contractor must ensure that no persons work, move or stand under any partly demolished overhanging material, which has not been adequately shored, braced or supported;
- Any support work must be designed to withstand the load being imposed on it, the design must be held on site;
- Where the stability of an adjoining structure, building or road may be negatively impacted, the Contractor must take all necessary steps to ensure the stability thereof;
- The Contractor must ascertain the location and nature of electricity, water, gas or other similar services, which may be affected by the work being performed. A safe method of removal or work around these services must be drawn up;
- Safe and convenient access must be provided to all work areas scaffolding, ladders, etc.;
- While demolition is taking place, all unauthorised persons must be kept well away from the operations;
- The Demolition Contractor's safety plan must include what applicable personal protective
  equipment and clothing is required. The minimum being leather gloves; steel toecap boots; eye
  protection where the risk of eye injury exists i.e. cutting, grinding, hot work, impact work;
  hearing protection for operators and other workers exposed to noise over 85dB(A); and fall
  prevention and/or arrest equipment when the risk of falling exists.
- The suppression of noise and dust is important due to worker exposure as well as sensitivity to neighbouring premises.

Demolition must take place in Chronological sequence:

- Planning and hording of demolition site
- Demolishing and striping by hand example: removing all no structural items (soft stripping)
- Demolition of brick walls and structures
- Remove rebar from building rubble before removing to a registered dumping site

## 6. Earthworks (Civil works) CR 13

The PC will ensure that the provisions of the regulation CR 13 are met and ensure that earthworks and are carried out as per the design . Further that:


- Before conducting any earthworks ensure that wayleaves is obtained and taken into consideration for the protections of services, further that:
- The project area is secured, fenced and warning signs of construction activities, installed.
   Other access routes to be clearly marked with signage indicating "Construction No Access"
- That the construction board is installed at the entrance displaying the PPE requirements with clear route to the site office.
- That land clearance and ripping is done following the design drawing and rubble kept in a area assessed as laydown area.
- That surveyor pegs and benchmarks are clearly marked and protected to prevent the accidental removing and clearing of land between incorrect coordinates.
- That when squatters or CLO are met site, to report the situation directly to the client.
- That the PC assess wild animals and take the necessary precautions to ensure the safety of the employees.
- That the PC ensure the appoint a security company to react on civil unrest or criminal activity onsite.
- That the PC will assess and take preventative action to protect water environment, wetland, rivers or stormwater inlets.
- That the PC will remove trees as per agreements and with the authorization of the client.

## Retaining walls

- Retaining wall shored/braced and secured as per assessment of dangerous works Retaining walls and brick work secured on firm foundation
- · Retaining walls and soil to meet the required compaction requirements
- · Retaining walls to be secured with solid barricading to prevent accidents

#### 7. Excavations CR13

Once the Principal contractors starts with excavations & trenches and these is deeper than 500 the excavation shall be barricaded with barrier netting example is visible below. If the excavation is deeper that 1,2 M every 6 M from the employees there shall be means of access & egress. No Danger tape will be allowed on site.



The Principal Contractor and relevant Contractors must make provision in their tender for the shoring of excavations where the soil conditions warrant it or if this is not possible batter back such excavations to a safe angle, termed the safe angle of repose.

The Principal Contractor has the following options: shore or brace the excavation, should this not be practical then such excavation must be battered back to the safe angle of repose from the engineers recommendation, should the first two options not be deemed necessary by the contractor, then permission must be given in writing by the appointed competent excavation supervisor. Where uncertainty pertaining to the stability of the soil exists, the decision of a professional engineer or professional technologist competent in excavations shall be decisive. Such permission must be in writing.

The following requirements must be adhered to:

- Excavations/trenches are inspected before every shift and a record of these inspections is kept;
- · Safe work procedures have been communicated to the workers;
- The safe work procedures are enforced and maintained by the Principal Contractor's and Contractors' responsible persons at all times;
- Excavations next to permanent or temporary roadways ensure that no load, material, plant or
  equipment is placed or moved near the edge of any excavation where it is likely to cause its
  collapse and thereby endangering the safety of any person, unless precautions such as the
  provision of sufficient and suitable shoring or bracing are taken to prevent the sides from
  collapsing;
- Ensure that where the stability of an adjoining building, structure or road is likely to be affected by the making of an excavation, steps are taken that may be necessary to ensure the stability of such building, structure or road as well as the safety of persons;
- Cause convenient and safe means of access to be provided into every excavation in which persons are required to work and such access shall not be further than 6m from the point where any worker within the excavation is working;
- Ascertain the location and nature of electricity, water, or other services which may in any way be affected by the work to be performed. The necessary steps must then be taken to render the circumstances safe for all persons involved. Should you as the contractor not be sure of the exact location of electrical services, detection equipment must be used as well as a system of hand excavation as per a written risk assessment and method statement;
- Cause every excavation which is accessible to the public or which is adjacent to public roads or thoroughfares, or where the safety of persons may be endangered, to be-
- (i) adequately protected by a barrier or fence of at least one meter in height and as close to the excavation as is practicable; and
- (ii) provided with warning illuminates or any other clearly visible boundary indicators at night or when visibility is poor;
- Cause warning signs to be positioned next to an excavation within which persons are working or carrying out inspections or tests



## 8. Heritage and Archaeological sites

If an artefact on site is uncovered, work in the immediate vicinity shall be stopped immediately. The contractor shall take reasonable precautions to prevent any person from removing or damaging any such article and shall immediately upon discovery thereof inform the Employer Agent of such discovery. The South African Heritage Research Agency (SAHRA) is to be contacted who will appoint an archaeological consultant. Work may only resume once clearance is given in writing by the archaeologist. (Read with COLTO General Condition of Contract Sub clause 4.24 as amended by Particular Condition).

The demolition of heritage structures (buildings 650 year old or of specific historical value) requires specific authority before it may be demolished. The following procedure to be followed:

- The appointed contractor for the demolition will apply for the permit.
- Where the portion of historical value is required to be protected, the structural engineer will be informed to conduct an survey and prepare and issue a structural report to protect the specific area of the building.
- The contractor will implement the structural engineers report for approval before demolishing the building connected to the historical part or section.

#### 9. Graves & Middens

If a grave or midden is uncovered on site, or discovered before the commencement of work, then all work in the immediate vicinity of the graves/middens shall be stopped and the Employer Agent informed of the discovery. SAHRA should be contacted and in the case of graves, arrangements made for an undertaker to carry out exhumation and reburial. The Employer will be responsible for attempts to contact family of the deceased and for the site where the exhumed remains can be reinterred. (Read with COLTO General Conditions of Contract Sub clause 4.24 as amended by Particular Condition).

## 10. Ladders GSR 13

All ladders shall be inspected on a monthly basis and shall be recorded on a ladder register. Ladder inspector shall be appointed in writing to carry out these inspection.

## Extension ladders

- Extension or single ladders should be used only as a means of access or egress from a working area.
- · They should not be used as working platforms,
- Any portable ladder used at the workplace should be set up on a solid surface that is stable and set up to prevent the ladder from slipping.
- Extension ladders must exceed the platform with 900mm
- All ladders must be numbered and recorded on a register
- Placing a ladder at 75 degrees angle securing single and extension ladders at both the top and bottom.

#### A frame ladders

- Timber portable ladders should not be painted (this can hide cracks and other defects in the timber)
- Metal portable ladders should not be used when carrying out work on electrical equipment.
- They should also not be painted as this can hide defects in the welds.
- Stepladders should be used only in their fully open position, and a person should not carry out work from a stepladder if they are standing higher than the 3rd rung from the top.

Ladder Duty Ratings					
Grade	Туре	Duty Rating			
Household	III	90 Kg			
Commercial	II	100 Kg			
Industrial Heavy Duty	I	115 Kg			
Industrial Extra Heavy Duty	IA	136 Kg			
Duty Rating represents ma	ximum weight of fully clothed use				

#### 11. Scaffolding CR 16

All scaffolding will comply to the SANS 10085-1:2004 standard as well as with the section 16 in the construction regulation of 2014.

The following appointments shall be done if scaffolding is being done on site:

- Scaffolding erectors
- · Scaffolding inspectors
- Scaffolding supervisor

All scaffolding will have a safe to use or not safe to use sign visible on the scaffolding to ensure compliance. Example of signs below:



Scaffolding will at all times have double side rails on platform area. Platform shall be fully boarded with scaffolding hook on boards & not with wooden planks. All scaffolding will have safe access the employees can use to get to desired platform. Access on scaffolding can be with scaffolding stairs or with scaffolding access ladders

According to SANS 10085-1:2004 section 3.21 No work will be allowed on scaffolding if the wind is greater than 40 km per/hour

Each scaffolding shall be on a register and on a weekly basis and immediately after inclement weather or alterations has been made.

The Principal contractor's safety officer and construction manager will ensure that the base jacks of the scaffolding shall not be jacked more than 2/3 of the full length.

All employees working on scaffolding without double hand rail and toe boards shall wear a double lanyard safety harness with scaffolding hooks. All erectors & dismantlers shall wear double lanyard safety harness with scaffolding hooks that will be hooked on all the time to prevent falling while erecting or dismantling the scaffolding.

Mobile scaffolding will be allowed on site if it complies to the SANS 10085. All mobile scaffolding shall have a break on each wheel that will be used while working on the scaffolding. No mobile scaffolding will be allowed to be moved while employees is on top of the scaffolding.

#### 12. Trestles SANS 10085

Trestles Shall not be allowed on site of the clients OHS agent did not approve it in writing. No timber trestles will be allowed on site

When approved then the following will be the requirements to make use of the trestles:

#### SANS 10085 10.16:

- The minimum width of the trestle legs when opened and locked in position shall be 780 mm.
- Trestles shall not be used on slopes exceeding 1:12.
- The platform supported by the trestles shall be level within 1:50 in all directions.

All trestles shall have a double hand rail to prevent the employee from falling off the elevated platform. Safe access shall be provided for employees working on the trestles. Trestles will be inspected before each shift/day with a specific trestle checklist and after inclement weather or alterations. The platform will be packed fully with steel scaffolding platform boards and will hook onto the trestle steel frame and not exceed the length.



#### 13. Fall protection - Fall Risk positions CR 10

## A Contractor must-

 Designate a competent person to be responsible for the preparation of a fall protection plan; ensure that the fall protection plan contemplated in paragraph (a) is implemented, amended where and when necessary and maintained as required; and take steps to ensure continued adherence to the fall protection plan.

- A fall protection plan contemplated in sub regulation (1), must include—
- A Risk Assessment of all work carried out from a fall risk position and the procedures and methods used to address all the risks identified per location;
- The processes for the evaluation of the employees' medical fitness necessary to work at a fall risk position and the records thereof;
- A program for the training of employees working from a fall risk position and the records thereof;
- The procedure addressing the inspection, testing and maintenance of all fall protection equipment; and
- A rescue plan detailing the necessary procedure, personnel and suitable equipment required to affect a rescue of a person in the event of a fall incident to ensure that the rescue procedure is implemented immediately following the incident.

A Contractor must ensure that a construction manager appointed under regulation 10(1) is in possession of the most recently updated version of the Fall and Rescue Protection Plan. Fall prevention and fall arrest equipment are —

- Approved as suitable and of sufficient strength for the purpose for which they are being used, having regard to the work being carried out and the load, including any person, they are intended to bear; and
- Securely attached to a structure or plant, and the structure or plant and the means of attachment thereto is suitable and of sufficient strength and stability for the purpose of safely supporting the equipment and any person who could fall; and
- Fall arrest equipment is used only where it is not reasonably practicable to use fall prevention equipment.

#### Fall Elimination -

The first step in work at height control is to assess the workplace and the work itself in the earliest design/ engineering stages of the project/ site and during the planned stages of all work so that potential fall hazards can be eliminated at an early stage. By doing so employees are not exposed to these potential fall hazards at any stage and work can be conducted with little exposure to fall risks and hazards.

The benefit of identifying these hazards allows for them to be included in the building phase of the job so that prevention measures are included during the construction and maintenance processes involved in the project.

#### Fall Prevention -


The second outlook is to assess the scope of work and potential conditions using collective protective measures. If fall hazards cannot be completely eliminated during the first step, management must take a proactive approach to the prevention of falls by improving the workplace and its conditions. In this step any hazards that arise outside of the design phase of a project are identified. This is achieved by assessing the work place and its conditions using a work at height risk assessment with the idea of implementing fall prevention measures such as guardrails, edge protection, hand rails and so forth. In this way all hazards that were not dealt with in the design phase can be addressed and a safe working environment will be achieved through the implementation of these systems.

#### Fall Arrest -

This is the last resort in preventing falls and individual prevention measures are assessed and implemented. In this step the condition or type of work conducted at height cannot be addressed at a design level or prevention level. In this step preventing the employee from hitting the ground is the aim, whereby systems and fall arrest equipment are used to prevent this from occurring. Equipment such as harnesses, lanyards, shock absorbers, fall arresters, lifelines, anchorage points, and safety nets can reduce the risk of injury if a fall occurs.

#### Life lines -

- The lifeline shall be of no less than 12.5 millimetres steel cable, able to withstand a 2.250 kg drop
  maintains tensile strength integrity of the material. Where steel cable cannot be used adequate
  lifelines in the form of ropes are to be used in accordance with manufacturing specifications able
  to support the above mentioned force. If a fall is expected while attached to lifeline, that line shall
  be replaced.
- The lifeline shall be installed in a length not to exceed 60 meters. The lifeline ends should be attached in such a manner that the ends are wrapped around a fixture so that it is facing the work area. As it is wrapped, a softener shall be installed to keep the cable from being marred or kinked.
- The cable shall be wrapped no less than one complete wrap around a beam or fixture and secured with no less than three (3) cable clamps of suitable strength. It shall be pulled to at least 45 torque kilograms.
- During installation, and as the cable is passed through each bay, it shall be attached/ supported in increments of no more than 15 meter runs. To maintain the intended height and elevate sag, the supporting material must be affixed in such a manner to be immobile.
- The supporting material must be of at least 75 x 75 mm angle iron/ steel. Holes may be tapped through the material as long as it is evenly centred, and the inside diameter edges are smooth and rounded.
- When working on elevation where there is no means for overhead attachment, supporting material shall be attached from the same elevation in an upright manner and attached.



#### Safety Harnesses

- > Engineering contractor and all contractors/ subcontractors will provide full body harnesses meeting SABS standards. Safety belts are not allowed for fall protection.
- Standard full body harnesses are not designed for a combined personnel and tool weight in excess of 137 kg. Personnel weight more than 137 kg, with tools, must consult project/ site SHE coordinator prior to using fall arresting equipment
- All Safety harnesses are to be stored in cool dry areas and inspected on a monthly basis. Any cuts, snags abrasions are to be reported to the site supervisor and the harness discarded immediately
- > Harnesses and lanyards must be checked for the following, but this the check points are not limited to this list:
- Beginning at one end, 15 cm to 20 cm of the harness/ lanyard must be bent into a U shape. This helps reveal worn, cut, frayed, burned, or damaged fibres. Both splices and all straps along the entire length must be checked.
- > Webbing must be carefully checked at attachment points to buckles and "D" rings.
- > The shock-absorbing section of the lanvard must be checked for ripped stitches.
- > The harness/ lanyard must be checked for broken/ frayed strands.
- Checks for rough, sharp edges; corrosion; dents or distortion; freely moving parts.

## Lifeline Hooks

# **Scaffolding Hooks**







## 14. Edge protection, Barricading and Penetrations

A Contractor must ensure that-

- All unprotected openings in floors, edges, slabs, hatchways and stairways are adequately guarded, fenced or barricaded or that similar means are used to safeguard any person from falling through such openings;
- No person is required to work in a fall risk position, unless such work is performed safely as contemplated in sub-regulation (2);
- A detailed Fall Arrest and Rescue Plan will be drafted and implemented on site.
- The above mentioned plan will be demonstrated on instruction of Department of Public works & infrastructure 's Agent.
- Rebar that is exposed will be made safe by placing a rebar cap on, to prevent the rebar from penetrating an employee or damaging equipment







## 15. Roof work CR 10

A Fall protection plan must be compiled by the roof work contractors (roof structure contractor and roof covering contractor) prior to such work being undertaken. This plan must be forwarded to the H&S Agent at least two weeks before the roof supporting structural steel work is programmed to begin. External scaffolding needs to be erected and remain in position to above roof height until completion of the roof work and associated activities so as to ensure elimination of fall risks (objects and equipment falling onto members of the public).

Life line systems during roof work must be designed and fitted.

A part-time safety officer must be designated by the roof work contractor

The Fall protection plan must include the following:

- How the roof work is planned to be erected or worked on:
- What hazards (tasks and tools) are associated with the work;
- That the roof workers are competent (trained, experienced, knowledgeable);
- \* That no work is carried during inclement weather or where conditions are hazardous to workers;
- That fragile material/areas are demarcated and sign posted;

- ♣ That suitable platforms are provided where fragile materials exist;
- Safe access systems/procedures;
- Public protection safety measures and fall prevention (objects and equipment):
- ♣ The safety and health measures that will be implemented to ensure the safety and health of roof workers as well as persons working below the roof work i.e. fall prevention systems.

A fall prevention strategy must be implemented and enforced which must include a combination of safety harnesses, life lines, specified attachment points, safe access, competent personnel, supervision, tool/equipment drop prevention.

#### 16. Temporary works CR 12

The PC will ensure that the provisions of the regulation CR 12:2014 are taken into consideration and appoint a temporary works designer to design to design and inspect form- and support work:

The temporary works drawing must display the design, braces, edge barricading and special safety arrangements to prevent that any part of the staging, shutter boards accidently can be dislodge and blown over the edge in gale force winds. That the temporary works designer or formwork contractor appoints a competent temporary works supervisor that will supervise the erection of support work and covering of the deck e.g. staging or Perri system The supervisor will be in possession of a printed, approved design drawing at the point where the deck is erected. The supervisor will be in possession of an inspection document to be completed and signed by the PC supervisor accepting the deck before loading it with rebar.

- The temporary work supervisor will ensure that support work is erected in accordance with the design, that bracing and intermediate props are installed.
- That the deck is fully boarded, that boards are secured to prevent accidental dislodge incidents and all lose material is removed from the deck.
- That safe access and edge barricading are installed.
- That all safety measures to ensure shutter board (when used) are secured to prevent dislodge in gale forces wind.

## Steel fixing and shuttering activities:

- Steel fixing are done under supervision of a competent supervisor following the approved bending schedule.
- Employees fixing steel close to unprotected edges must wear a safety harness connected to a safe anchor point.
- The installation of shutter boards or panels must be secured to prevent concrete spill or be accidental dislodged in gale force winds.
- Installation of rebar structures for columns and shutter panels by mobile crane must be done in conjunction of a competent banksman.
- Installation of rebar structures for columns and shutter panels by mobile crane must be done in conjunction of a competent banksman.
- Where scaffold is used for the installation of column rebar and shutter panels, the scaffold must be erected in accordance of SANS 10085

The area where the concrete pump will be positioned with outriggers extended, must be demarcated and barricaded:

- The safety of public to be considered and where applicable, flagman posted The pump and delivery pipes to be connected and secured correctly
- Sufficient space to allow delivery trucks to stop and que for delivery of premix
- Preventative measures taken to prevent concrete spill on the road service or into the stormwater system

## Casting concrete with concrete bucket

- The area where the concrete bucket is filled directly from delivery truck, must be barricaded.
- All the principles applicable to crane operations e.g. safe connections, lifting and banksman duties are valid and needed to be applied during this operation.
- A concrete bag to be installed around bucket outlet to prevent dripping spillage during transit
  of the concrete.
- All safety whistles and signs applied, the bucket may not be moved over a public road of walkway.
- The supervisor for the concrete pour must ensure that the bucket is empty and the safety cover is inserted over the opening before returning it for refilling.
- The PC must ensure that the concrete bucket is cleaned daily after concrete pour to prevent concrete to set in or on the bucket to prevent it from falling when accidently dislodged.
- · may be installed directly over a public road

#### 17. Traffic and pedestrian accommodation

The Principal Contractor must ensure that all the necessary traffic/vehicle and pedestrian accommodation safety measures are taken into account to ensure the safety of personnel and members of the public (including site visitors) both on site and adjacent to site. Such measures must be in accordance with recognised practises and to the approval of the Client and the local municipality and traffic authority. The Principal Contractor must place the necessary emphasis on safe pedestrian walkways and routings throughout the construction stage. Traffic and pedestrian accommodation drawings must be available on site as a source of reference and to assist with daily inspections and enforcement and inclusive of vehicle and pedestrian movement/management.

The principal contractor shall compile a traffic management plan to the client OHS agent & clients Agent for approval before the start of traffic accommodation. The traffic accommodation should include a sketch or a picture t explain where what signs would be displayed and to indicated detours should it be applicable. All signs need to comply to the National Road Safety Act.

## 18. Confined Spaces

Confined space is a space of any volume which, a person may at any time enter or be allowed to enter and which:

The atmosphere is liable to be contaminated at any time by dust, fumes, mist, vapor, flammable or toxic gases or other harmful substances

- The atmosphere is liable at any time to be oxygen deficient or excess
- The area is not intended to be regular workplace
- The area has restricted means of entry and exit
- The area may be subjected to engulfment
- The area is an atmospheric pressure during occupancy

Areas not normally regarded as confined spaces can become one depending on the conditions or presence of hazards.

Entry into a confined space shall not be permitted until the atmosphere has been tested to ensure safety of all personnel.

Retesting or continuous monitoring may be required because of the potential for the release of hazardous material during welding or other processes. The release of hazardous substances depends on the type of work currently being carried out, type of previous contaminant and the presence of residual chemicals. Provision should be made to continuously monitor or regularly retest the atmosphere within a confined space.

#### If entry is required then:

- Notify all personnel of how the task will be performed
- > Ensure that lockout, tag and isolation procedures are in place
- > Hazards which are involved in working in a confined space should be minimised at the design stage and during the initial installation of equipment
- An employer must ensure that before carrying out work involving entry into a confined space that a written assessment (confined space permit is carried out by a responsible person and determines the following
  - · The work to be carried out
  - Is necessary to enter the confined space
  - The method by which the work can be carried out
  - The hazards involved
  - The actual method and plant proposed
  - · Safety equipment required
  - Emergency and rescue procedure
  - Gas monitoring and detection necessary
  - PPE
  - Number of personnel to carry out the task
  - Number of standby personnel required

## 19. Deliveries, Waste removal, Stacking/Storage of materials

The Principal Contractor and other relevant contractors must ensure that there is an appointed stacking supervisor and all materials, formwork and all equipment is stacked and stored safely, on level, compact ground, out of access ways and no more than three times the minimum base width in height. Pallets of bricks may not be stacked more than two above each other and must be on timber pallets. No construction materials or equipment may be stacked or stored in public areas unless authorised by Department of Public works & infrastructure and fenced off as per Department of Public works & infrastructure 's requirements. Waste materials must be kept within designated construction zones. The Principal Contractor will be responsible for co-ordinating and managing this function.

## 20. Fire extinguishers and firefighting equipment

The Principal Contractor and relevant Contractors shall provide adequate, regularly serviced firefighting equipment located at strategic points on site, specific to the classes of fire likely to occur. The appropriate notices and signs must be posted up as required. A minimum of four 9 kg dry chemical powder fire extinguishers must be available in and around the site office establishment and stores. Fire extinguishers must also be placed at all work zones/areas, in strategic locations. Wherever \*'hot work' is taking place, additional fire extinguishers must be on hand. Contractors are responsible for ensuring compliance with hot work procedures and must be in possession of method statements detailing the safe working procedures. \*'Hot work' includes all work that generates a spark or flame and may therefore result in a fire.

Further, during the finishing stages of the construction phase when the finishing trades are on site, fire extinguishers will be required at strategic locations within the work areas – to be supplied and managed by the Principal Contractor.

## 21. Designated smoking area

The principal contractor will ensure that a designated smoking area will be established on site at a safe location away of chemicals or any other fire hazard, at least one fire extinguisher will be close (not further than 10 M) to the designated smoking area.

## 22. Thunder & Lighting

The management and safety personnel of the Principal Contractor shall download the lightning Alarm app from Istore or google play store. The site location must be set on the app to inform the management and the safety personnel when lightning is 30 km away from the site. When the notification is received on their phones all employees (PC, Contractors & sub-contractors) working at heights must get down as fast possible. The employees are only allowed back on heights when the app has not notifies the team about lightning for at least 15 Min from the last notification.



#### 23. Concrete work

As with many other materials, there are potential risks involved in handling or working with cement or mixes made using cement.

The composition of cement is such that when dry cement is exposed to water a chemical reaction called hydration takes place, releasing a very strongly alkaline (and caustic) fluid. This can cause alkali burns and safety measures should be observed. Appropriate precautions are advised to prevent tissue damage when handling fresh mixes containing water and cement.

Cement dust, dusts from handling aggregates and from cutting concrete are easily inhaled.

Prolonged or regular exposure to these dusts should be avoided.

Cement is a complex combination of compounds that includes minute quantities of trace elements. Although South African cements typically contain less than two parts per million of Hexavalent Chrome (widely regarded as a safe level), it may serve as an aggravating factor in cases of exposure to alkaline fluids. There have been some reports of allergic dermatitis after exposure to these fluids.

When fresh concrete or its bleed water comes into contact with human skin, the alkalis react with the oils and fats in the skin as well as the proteins in the skin itself causing tissue damage. Other organic tissue (e.g. mucous membrane) can also be attacked by strong alkalies leading to burns that can sometimes be severe, and users should try to avoid all unnecessary contact with these fluids. Where such contact is unavoidable, suitable precautions should be taken.

Roughness and dryness of the hands after working with concrete is a typical consequence of loss of these oils and fats. More prolonged exposure could result in irritant dermatitis. It is possible that the effects of trace elements may aggravate the condition and lead to an allergic dermatitis. To safeguard against accidental exposure, appropriate protective equipment is strongly recommended.

Impermeable gauntlet type rubber gloves and high length rubber boots should be worn to prevent direct contact with skin. Trousers should overlap the boots rather than be tucked into them. Hydrophobic alkali-resistant barrier creams should be applied to hands and any areas of skin likely to be in contact with fresh concrete. Ordinary barrier creams are likely to be inadequate.

These precautions may be ineffective if the skin itself is not clean and free of concrete residue. Even a tiny trace of cement dust remaining in contact with wet skin will raise the pH significantly.

Regularly wash (at least daily) protective clothing and keep it clean and free of concrete and wash any areas that have been accidentally splashed with wet concrete as soon as possible with large quantities of clean water. Ensure that normal and protective clothing does not become soaked with wet concrete or concrete fluids as this could result in exposure over an extended period, resulting in tissue damage.

Cement is an abrasive fine powder, and when handled, some dust may become suspended in the air in the working area. Users should avoid inhaling cement dust as this may cause irritation of the nose and throat. Cement dust may also cause irritation of the eyes. This will occur because of the chemical reaction of the suspended dust with the moist mucous membranes. Airborne cement dust should be kept to a minimum to avoid these problems. Should this be impractical, then the use of goggles and dust masks is strongly recommended.

Many of the aggregates used in concrete have high silica contents. The fine silica dusts created when crushing or handling these aggregates could cause lung problems, and precautions should be observed to avoid breathing in such dusts.

Dust from demolishing or cutting hardened concrete may contain un hydrated cement and could cause respiratory problems as outlined above. In addition, if the coarse or fine aggregate used in making the concrete contains crystalline silica, then inhalation of these fine silica particles could expose workers to the risk of developing silicosis. A concerted effort should be made to avoid generating such dusts. If this is not possible, the use of suitable respiratory protective equipment is recommended.

Site workers should also not kneel on fresh concrete during placing, compacting and finishing operations. If kneeling is unavoidable, thick waterproof kneepads should be worn with a kneeling board to prevent the pads sinking into the fresh concrete. In severe cases of alkali burns, a medical practitioner should be consulted as soon as possible

#### 24. Brickwork

Brick work goes hand in hand with other section discussed in this coherent specification for example: Scaffolding, Concrete work, Hand tools, stacking and storage & barricading.

The bricks shall be stacked on pallets in a dedicated area. The bricks shall not be double stacked. The double stacking poses a risk for falling over on employees, plant or cause damage to the property.

Brick work on scaffolding is a high risk and the necessary precautions need to be taken to ensure that scaffolding platform is not overloaded. The scaffolding that will be used shall comply to the relevant regulations and act as well as the scaffolding section in this coherent OHS specification.

All employees shall wear the compulsory PPE (overall, safety boots, gloves, hard hat). It will not be allowed to throw bricks from on level to another. Bricks that needs to be cut must be done with a brick cutter or with a grinder. If employee uses these methods then the process shall be discussed in a risk assessment to ensure safe work and proper PPE is being worn.

## 9. Plant, equipment and machinery

## 1. Construction Vehicles & Mobile plant CR 23

Construction Plant" includes all types of plant including but not limited to, cranes, piling rigs, excavators, construction vehicles, compaction plant and lifting equipment.

The Principal Contractor must ensure that such plant complies with the requirements of the OHS Act, Construction Regulations (Feb 2014) and any manufacturers specifications. The Principal Contractor and all relevant contractors must inspect and keep records of inspections on construction vehicles and mobile plant used on site. Only authorised/competent persons in the possession of the necessary training certificates and in possession of a certificate of medical fitness may operate construction vehicles and mobile plant. Should any operator be caught making use of a cell phone while driving he will be given a written warning as well as when the operator do not wear the safety belt. All construction vehicles & mobile plant shall be fitted with rotating light (visitors included). Lockout procedure shall be written and implemented to ensure that no plant will be left unattended while idling and to ensure that plant will be locked out at the end of shift.

## 2. Hired plant and machinery

The Principal Contractor must ensure that any hired plant and machinery used on site is safe for use and complies with the minimum legislated requirements. The necessary requirements as stipulated by the OHS Act and Construction Regulations shall apply. The Principal Contractor shall ensure that operators hired with machinery are competent and that competency and medical certificates are kept on site in the health & safety file. Any load test requirements and inspections in terms of legislation must be complied with and copies of load test certificates and inspections must be kept in the health & safety file. All relevant contractors

## 3. Cranes and lifting equipment

Cranes and Lifting Equipment must be designed and constructed in accordance with generally accepted technical standards and operated, used, inspected and maintained in accordance with the requirements of Driven Machinery Regulation 8 of the OHSAct:

- To be clearly and conspicuously marked with the maximum mass load (MML) that it is designed
  to carry safely. When the MML varies with the conditions of use, the table should be used by
  the driver/operator
- Each winch on a lifting machine must at all-time have, at least, three full turns of rope on the drum when the winch has been run to its lowest limit
- Fitted with a brake or other device capable of holding the MML. This brake or device to automatically prevent the downward movement of the load when the lifting power is interrupted
- Fitted with a load limiting device that automatically arrest the lift when
- The load reaches its highest safe position or
- When the mass of the load is greater that the MML
- Every chain or rope on a lifting machine that forms an integral part of the machine must have a factor of safety as prescribed by the manufacturer of the machine and where no standard is available the factor of safety must be:

0	Chains	4 (four)
0	Steel wire ropes	5 (five)
0	Fibre ropes	10 (ten)

- Every hook or load attaching device must be designed such or fitted with a device that will
  prevent the load form slipping off or disconnecting
- In addition all ropes, chains, hooks or other attaching devices, sheaves, brakes and safety devices forming an integral part of a lifting machine must be inspected every 6 months by a competent person
- All maintenance, repairs, alterations and inspection results must be recorded in a log book and each lifting machine must have its own log book.
- No person may be lifted by a lifting machine not designed for lifting persons unless in a cradle approved by the inspector or the Department of Labour.
- A clearly marked drop zone of 5 M around the crane will be identified with cones and barrier netting to keep people away from under the load

#### Lifting tackle:

- To be manufactured of sound material, well-constructed and free form patent defects
- To be clearly and conspicuously marked with id and MML
- Factor of safety:

0	Natural fibre ropes	-	10 (ten)
0	Man-made fibre ropes & woven webbing	-	06 (six)
0	Steel wire ropes – single rope	-	06 (six)
0	Steel wire ropes – combination slings	_	08 (eight)

Mild steel chains

05 (five)

- o High tensile/alloy steel chains
- 04 (four)
- Steel wire roes must be discarded (not used any further or lifting purposes) when excessive wear and corrosion is evident and must be examined by a competent person every three months for this purpose and the results recorded.

### **Lifting Machine Operators**

• Every lifting machine operator must be trained specifically for the type of lifting machine that he/she is operating

### 4. Explosive actuated fastening devices

The PC will ensure that the provisions of the regulation CR 21:2014 are met and ensures that explosive actuated fastening device operations including devices operated with compressed air, gas cartridge, pneumatic tools, complies to the following:

- That a competent person is appointed in writing to:
- Issue explosive actuated fastening device
- Issue explosive actuated fastening cartridges and nails (shots & pins)
- Inspect the explosive actuated fastening device before issue and on return
- · Clean and maintain the explosive power actuated fastening device
- Explosive actuated device to be inspected daily before use and records to be kept
- Explosive cartridges and nails to be recorded when issued and when returned
- Explosive actuated device, cartridges and nails to be locked securely
- Explosive actuated device to be fitted with a muzzle on the end to control debris
- Only a competent appointed user my operate the explosive power actuated device

### 5. Electrical Installation and portable electrical Tools

The consulting engineers will ensure as far as possible that the principal contractor is made aware of the positions of all electrical installations and other services. The Principal Contractor must notify the engineer concerned should it not be sure of the location of any particular service. This is especially pertinent to the Demolitions Contractor who will need to ensure that all electrical installations are 'made safe' before demolition work begins. An installation electrician will need to prove this by means of the necessary documentation and written lock-out procedures, tags, and the like.

The Principal Contractor and contractors must comply with the Electrical Installation Regulations, the Electrical Machinery Regulations and the Construction Regulations.

The Principal Contractor must keep a copy of the Certificate of Compliance (CoC) for its temporary electrical power supply and installation. A revised CoC is required whenever the installation is altered or changed in any way. All temporary electrical installations must be inspected at least weekly by a competent person appointed in writing with records kept.

The testing and commissioning of the permanent electrical installation must be done under the management of a written method statement and detailed set of safety requirements and must only be put into use after a CoC has been issued to the principal contractor for that section/area.

Portable electrical tools and equipment must be visually inspected daily by a competent person (trained by an electrician or suitable person to carry out visual inspections on electrical tools and extension leads) before use, with records kept as proof.

Coherent Health & Safety Specification for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants© RisCon Consultants (All copyrights reserved)

### 6. General Machinery

The Principal Contractor and relevant contractors must ensure compliance with the Driven Machinery Regulations, which includes carrying out risk assessments on the machines, inspecting machinery regularly, appointing a competent person to inspect and ensure maintenance, issuing PPE and relevant clothing, and training those who use machinery.

### 10. Occupational Health

### 1. Industrial Hygiene

Exposure of workers to occupational health hazards and risks is very common in any work environment, especially in construction. Occupational exposure is a major problem and all Contractors must ensure that proper health and hygiene measures are put in place to prevent exposure to these hazards. Prevent inhalation, ingestion, and adsorption through the skin of hazardous chemical substances.

- Noise induced hearing loss is a highly underrated occupational condition. Occupational
  noise emitted by construction machinery and power tools must be controlled as far as
  possible by implementing engineering solutions such as noise dampening, regular
  maintenance, servicing and inspection, screening off the noise, and reducing the
  number of persons exposed. Personal protective equipment such as earmuffs and
  earplugs must also be used in conjunction with engineering controls so as to reduce
  noise exposure to below the acceptable levels.
- Heat stress is a major hazard in South Africa. The principal contractor must ensure that
  there is clean drink water available on site at all times and in extremes heat conditions
  must ensure that employees consume 600ml water an hour to prevent dehydration.

### 2. Hazardous Chemical Substance (HCS)

The Principal Contractor and other relevant contractors must provide the necessary training and information as far as the use, transport, and storage of HCS. The Principal Contractor must ensure that the use, transport, and storage of HCS are carried out as prescribed in the HCS Regulations. The Principal Contractor and contractors must ensure that all hazardous chemicals on site have Material Safety Data Sheets (MSDS) on site and the users are made aware of the hazards and precautions that need to be taken when using the chemicals. The First Aiders must be made aware of the MSDS's and how to treat HCS incidents appropriately. Copies of the MSDS's must be kept in the first aid box and in the store. All containers must be clearly labelled. Flammable substances must be stored separately, away from other materials, and in a well-ventilated area (appropriate cross ventilation). A competent person should be appointed to be in control of this portfolio. Stores must be well ventilated, preventing the build-up of flammable and toxic gases/vapours. Should fuel storage containers be used, they must conform to the general environmental legislation and Environmental Management Plan (if a requirement on this site). The necessary safety signage must to be posted up - 'no naked flames', 'no smoking'. Two 9 kg DCP fire extinguishers must be placed near to the fuel containers, but not within 5 m of the containers. These extinguishers are over and above the minimum four required for the offices and stores.

### 3. Alcohol and other drugs

No alcohol and/or other drugs will be allowed on site. No person may be under the influence of alcohol or any other drugs while on the construction site. Any person on prescription medication must inform his/her superior, who shall in turn report this to the Principal Contractor forthwith. Any person suffering from any illness/condition that may have a negative effect on his/her /anyone else's health or safety performance must report this to his/her superior, who shall in turn report this to the

Coherent Health & Safety Specification for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants© RisCon Consultants (All copyrights reserved)

Principal Contractor forthwith. Any person suspected of being under the influence of alcohol or other drugs must be sent home immediately, to report back the next day for a preliminary inquiry. The Contractor concerned must follow a full disciplinary procedure and a copy of the disciplinary action must be forwarded to the Principal Contractor for its records.

### 4. Medical certificate of fitness


A contractor must ensure that all his or her employees have a valid medical certificate of fitness specific to the construction work to be performed and issued by an Occupational Health Practitioner in the form of **Annexure 3** of the construction regulations. IN this section of the safety file the principal contractor shall ensure that in front of the medicals of all the employees there will be a medicals register. All employees' medicals must be listed on this form, see attached annexure H. This annexure shall only be TYPED.

### 5. Welfare Facilities

The Principal Contractor will be using chemical toilets that will be strategically placed on site. The ratio is for every 30 workers on site there will be 1 chemical toilet, When females is working on site there will be 2 toilets for every 30 workers (one for each gender). Waste bins must be strategically placed around site and emptied regularly. Shaded eating area shall be available for employees with seating and tables. The eating area shall have sufficient waste bins.

### 6. Ergonomics


Ergonomics is the study of how workers relate to their workstations. We advise the Principal Contractor and Contractors to take this into consideration when conducting risk assessments, thereby improving the worker-task relationship, which will in turn improve productivity and reduce chronic conditions such as back strains, joint problems and mental fatigue, amongst others. Ergonomic risk assessor shall be appointed in appointed writing and shall have the competency to perform this task.



### 7. COVID 19

The COVID 19 is an international disaster. This is a pandemic that needs to be managed and to ensure that all our employees and visitors is safe. All precaution measures must be in place to ensure that the spread of the virus does not happen during construction. The following will shall be in place to prevent the COVID 19 virus from spreading:

- · Each employee and visitor hands will be sanitised when entering the site and exiting the
- Lunch breaks will be rotated to ensure that at all times a social distance of 1 M shall be possible between employees
- COVID 19 site rules shall be displayed at every notice board
- Notice boards shall be available at the following places: Site entrance, toilets, site offices, storerooms, eating areas, hand washing stations
- PPE issue register will be available to ensure that all employees have been issued with masks or face shields and gloves where applicable
- All hand sanitizer that is being used on site must have at least 70% alcohol and a certificate needs to be available on site
- A COVID 19 Guideline / procedure and Baseline risk assessment shall be in file and discussed with employees
- Emergency plan shall be changed to cover COVID 19 and to ensure that assembly points is big enough to ensure a 1 M social distancing at all times



### Omissions from the Site-Specific Health and Safety Specifications

Every endeavor has been made to address the most critical aspects relating to Health and Safety issues in order to assist the contractor in adequately providing for the Health and Safety of employees on site. However, the Principal Contractor is required to ensure they stay compliant with statutory requirements and construction programs and processes and include such aspects in their Health and Safety File.

### PRIMARY HEALTH AND SAFETY COMPLIANCE

D	roi	i	d	
Г	IUI	C	U	

### ANNEXURE A

The Principal Contractor and Contractors must submit compliance with Annexure 'A' before commencing on work on site. Compliance with Annexure 'A' must be maintained and proven to the Safety Agent at audits.

NO	Document Document	YES	NO	N/A	COMMENTS
1.	Appointment Letter from Client				d_straw
2.	Notification of Construction				
3.	Letter of good standing				
4.	Copy of public liability				A NA
5.	Scope of work		0		est:
6.	Tools & Machinery list		Q N	,	
7.	Method statements for all work		W.Y		
8.	Risk Assessment Plan	1			
9.	Baseline Risk Assessments				
10.	Safe work Procedures	•			
11.	Medical certificates \				
12.	All Health & Safety related policies				
13.	Section 37.2 agreement				
14.	Induction Information				
15.	Emergency plan & Numbers				
16.	Fall Protection plan				
17.	Health & Safety Plan				
18.	Incident / Accident management Control				

NO	Document	YES	NO	N/A	COMMENTS
19.	Traffic Management Plan			20 Page 22 22 23	
20.	Sample of all registers				
21.	Occupational Health and safety Consultant CV and Company profile				
22.	Construction building plans				
23.	Occupational Health & safety Act				
24.	Construction Regulations 2014				41/1/2
25.	Toolbox talks topics				2 4 76.79
26.	Client Health & Safety specs				4 4 0
27.	Sub-Contractor Control				400
28.	Environmental management				· ·
29.	Hazardous chemical substance list & MSDS's		ď		
30.	Example of OHS report			\	
31.	Organogram	N. A.			
NO	Appointment	YES	NO	N/A	COMMENTS
32.1	16.2	Simulativi	LOCAL SE LINE		
32.2	Delegation of duties	P .			
32.3	Construction manager CR 8(1)				
32.4	Ass Construction Manager CR 8(2)				
32.5	Construction supervisor CR 8(7)				
32.5	Ass Construction Supervisor CR8(8)				
32.6	Health & Safety officer CR 8(5)				
32.7	Risk Assessor CR 9(1)				
32.8	Incident / Accident Investigator GAR 9(2)				

NO	Appointment	YES	NO	N/A	COMMENTS
32.9	Contractor (sub) CR 7(2)(c)(v)				
32.10	Excavation Inspector CR 13(2)(h)				
32.11	Excavation Supervisor CR 13(1)(a)				
32.12	Fall Protection Plan Developer CR 10(1)				1 1
32.13	Fire Equipment Inspector CR 29(h)				
32.14	Scaffold Erector CR 16(1)				
32.15	Scaffold Inspector CR 16(1)				
32.16	Scaffold Supervisor CR 16(1)				
32.17	Stacking & storage supervisor CR 28(a)		6		
32.18	Crane Supervisor CR 22(a)	Ų		Sen!	
32.19	SHE Rep OHSACT 17(1)		View.		
32.20	First Aider GSR 3				
32.21	Crane Operator CR 22				
32.22	Crane Supervisor CR				
32.23	Construction Vehicle operator CR 23				
32.24	Construction Vehicle Supervisor CR 23				
32.25	Lifting Equipment inspector Reg 18(5)				
32.26	Electrical Installation Supervisor CR 24				

NO	COVID Documents	YES	NO	COMMENTS
33.	COVID 19 Risk Assessment			
34.	COVID 19 SWP			
35.	COVID 19 Policy			
36	COVID 19 Intergraded into all plans and policies			

### OCCUPATIONAL HEALTH & SAFETY – HEALTH & SAFETY COSTS TO BE INCLUDED IN THE PRINCIPAL CONTRACTOR'S / CONTRACTORS' PRICE

Project:

### ANNEXURE B

In terms of the Construction Regulations (2014), it is Department of Public works & infrastructure 's duty to ensure that the cost for health & safety has been provided for by the Principal Contractor, before appointment.

Acting on behalf of our Client, we require the following health & safety costs to be included by the Principal Contractor. It must be made very clear that these are just some of the health & safety costs to be included in your tender price. It is the duty of the Principal Contractor and Contractors to ensure that all aspects of the Occupational Health & safety Act 85/1993 and Construction Regulations are catered for.

Pricing for Occupational Health and Safety measures should include the following if applicable:

ITEM	DESCRIPTION
1	Supply of all items of Personal Protective Clothing/Equipment & ensure use
	thereof for full compliance
1.1	Steel toe capped safety boots
1.2	Overalls
1.3	Reflective vests(high visibility)
1.4	Hard hats
1.5	Dust masks
1.6	Hearing protection
1.7	Hand gloves
1.8	Any other :Principal Contractor to specify
2	Supply and provision of Equipment for working at Heights & ensure use thereof for full compliance
2.1	Fall protection equipment (Safety Harness)
2.2	Double lanyard harness
2.3	Fall protection plan
2.4	Scaffolding access ladders/toe boards/hand rails
2.5	Portable Ladders
2.6	Wind Meter
2.7	Any other: Principal Contractor to specify:
3	Barricading: Supply & install, including removal upon completion to ensure full compliance to legislation
3.1	Rigid type barricading
3.2	Temporary fence barricading along perimeter of excavated area
3.3	Safety netting
3.4	Any other: Principal Contractor to specify:
1	Related Training
1.1	First Aid Training
1.2	Health and Safety Representative training
1.3	Emergency Rescue training(Height)
1.4	Hazard Identification Training
1.5	Training of Personnel working at heights

Coherent Health & Safety Specification for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants© RisCon Consultants (All copyrights reserved)

4.7 Legal Liability(OHSACT) Training 4.8 COID ACT Training 4.9 Scaffold Erector and Inspector Training 4.10 Induction stickers for employees to place on hard hats 4.11 Any other: Contractor to specify: Working at elevated 5 Occupational Health and Safety Administration	4.6	Construction Plant Training
4.8 COID ACT Training 4.9 Scaffold Erector and Inspector Training 4.10 Induction stickers for employees to place on hard hats 4.11 Any other: Contractor to specify: Working at elevated 5 Occupational Health and Safety Administration 5.1 Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessme by Competent person. 5.2 Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer. 5.3 Competent Occupational Health and Safety Officer/Consultant. 6 Medical Surveillance 6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner. 6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project. 7 Facilities and Equipment 7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	4.7	
4.9 Scaffold Erector and Inspector Training 4.10 Induction stickers for employees to place on hard hats 4.11 Any other: Contractor to specify: Working at elevated 5 Occupational Health and Safety Administration 5.1 Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessme by Competent person. 5.2 Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer. 5.3 Competent Occupational Health and Safety Officer/Consultant. 6 Medical Surveillance 6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner. 6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project. 7 Facilities and Equipment 7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	4.8	
4.10 Induction stickers for employees to place on hard hats 4.11 Any other: Contractor to specify: Working at elevated 5 Occupational Health and Safety Administration 5.1 Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessme by Competent person. 5.2 Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer. 5.3 Competent Occupational Health and Safety Officer/Consultant. 6 Medical Surveillance 6.1 Medical Surveillance 6.2 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner. 6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project. 7 Facilities and Equipment 7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
4.11 Any other: Contractor to specify: Working at elevated  5 Occupational Health and Safety Administration  5.1 Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessme by Competent person.  5.2 Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer.  5.3 Competent Occupational Health and Safety Officer/Consultant.  6 Medical Surveillance  6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner.  6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project.  7 Facilities and Equipment  7.1 Sanitary facility for each sex and for every 30 workers.  7.2 Changing facilities for each sex.  7.3 Sheltered eating areas  7.4 First aid boxes  7.5 Fire extinguishers  7.6 Waste bins  8 Safety Signage  8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins	4.10	
5.1 Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessme by Competent person.  5.2 Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer.  5.3 Competent Occupational Health and Safety Officer/Consultant.  6 Medical Surveillance  6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner.  6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project.  7 Facilities and Equipment  7.1 Sanitary facility for each sex and for every 30 workers.  7.2 Changing facilities for each sex.  7.3 Sheltered eating areas  7.4 First aid boxes  7.5 Fire extinguishers  7.6 Waste bins  8 Safety Signage  8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins	4.11	
by Competent person.  Develop of Fall Protection and Rescue Plan by a Competent Fall Protection Plan Developer.  Competent Occupational Health and Safety Officer/Consultant.  Medical Surveillance Medical Certificates of fitness for all Employees by an Occupational Health Practitioner.  Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project.  Facilities and Equipment  Sanitary facility for each sex and for every 30 workers.  Changing facilities for each sex.  Sheltered eating areas  Fire axtinguishers  Waste bins  Safety Signage  Safety Signage  Sufficient and adequate safety signage on constructions site and at all flammable stores.  COVID 19  Signages  COVID 19  Signages  Sanitizer  Sanitizer  Masks / Face shields  Isolation Room  Maste bins	5	
Developer.  5.3 Competent Occupational Health and Safety Officer/Consultant.  6 Medical Surveillance  6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner.  6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project.  7 Facilities and Equipment  5.3 Sanitary facility for each sex and for every 30 workers.  7.2 Changing facilities for each sex.  7.3 Sheltered eating areas  7.4 First aid boxes  7.5 Fire extinguishers  7.6 Waste bins  8 Safety Signage  8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins	5.1	Develop of a Site Specific Health and Safety Plan and Hazard and Risk Assessment by Competent person.
6. Medical Surveillance 6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner. 6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project. 7 Facilities and Equipment 7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	5.2	
6.1 Medical Certificates of fitness for all Employees by an Occupational Health Practitioner. 6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project. 7 Facilities and Equipment 7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	5.3	Competent Occupational Health and Safety Officer/Consultant.
Practitioner.  6.2 Medical Certificates of fitness for all EPWP Employees by an Occupational Practitioner during the duration of the Construction Project.  7 Facilities and Equipment  7.1 Sanitary facility for each sex and for every 30 workers.  7.2 Changing facilities for each sex.  7.3 Sheltered eating areas  7.4 First aid boxes  7.5 Fire extinguishers  7.6 Waste bins  8 Safety Signage  8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins	6	Medical Surveillance
Practitioner during the duration of the Construction Project.  Facilities and Equipment  Sanitary facility for each sex and for every 30 workers.  Changing facilities for each sex.  Sheltered eating areas  First aid boxes  Fire extinguishers  Waste bins  Safety Signage  Sufficient and adequate safety signage on constructions site and at all flammable stores.  COVID 19  Signages  Sanitizer  Sanitizer  Masks / Face shields  Masks / Face shields  Isolation Room  Waste bins	6.1	
7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	6.2	Medical Certificates of fitness for all EPWP Employees by an Occupational
7.1 Sanitary facility for each sex and for every 30 workers. 7.2 Changing facilities for each sex. 7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		Practitioner during the duration of the Construction Project.
7.2 Changing facilities for each sex.  7.3 Sheltered eating areas  7.4 First aid boxes  7.5 Fire extinguishers  7.6 Waste bins  8 Safety Signage  8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins	7	
7.3 Sheltered eating areas 7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
7.4 First aid boxes 7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
7.5 Fire extinguishers 7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
7.6 Waste bins 8 Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
Safety Signage 8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
8.1 Sufficient and adequate safety signage on constructions site and at all flammable stores.  9 COVID 19  9.1 Signages  9.2 Sanitizer  9.3 Disinfectant  9.4 Thermometers  9.5 Masks / Face shields  9.6 Isolation Room  9.7 Waste bins		
stores. 9 COVID 19 9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins		
9.1 Signages 9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	8.1	
9.2 Sanitizer 9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	9	COVID 19
9.3 Disinfectant 9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	9.1	Signages
9.4 Thermometers 9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	9.2	Sanitizer
9.5 Masks / Face shields 9.6 Isolation Room 9.7 Waste bins	9.3	Disinfectant
9.6 Isolation Room 9.7 Waste bins	9.4	Thermometers
9.7 Waste bins	9.5	Masks / Face shields
	9.6	Isolation Room
9.8 Safety transport for COVID 19	9.7	
	9.8	Safety transport for COVID 19

### ANNEXURE C

The Occupational health and Safety File must consist out of the following documentation: **INDEX** 

### File 1( Legal file)

- 1. Client Mandatory Agreement & PC Appointment
- 2. Dept. Labour & Employment Documentation (COID) / UIF
- 3. Client Specifications
- 4. Scope of Work
- 5. Tools & Machinery List
- 6. HIRA Guide & Procedure
- 7. Client Baseline Risk Assessment
- 8. Medical Certificates
- 9. Health and Safety Related Policy's
- 10. Sub-Contractor Management
- 11. Emergency Preparedness and Emergency Numbers
- 12. Fall protection & Rescue Plan
- 13. Health and Safety Plan
- 14. Reporting of Injuries and Incidents
- 15. Environmental management
- 16. Occupational Health and Safety Organogram
- 17. Occupational Health and Safety Appointments
- 18. Employee Id Copies
- 19. Employee Particulars
- 20. Certificates of all lifting equipment

### File 2 (Work File)

- 1. Toolbox Talks
  - 2. Registers & Checklists
  - 3. Induction Training
- 4. Safe Work Procedures (SWP'S)
- 5. Issue based Risk Assessments
- 6. Method statements
- 7. COVID 19 workplace management plan
- 8. COVID 19 Baseline Risk Assessment & SWP
- 9. Emergency Numbers
- 10. Material safety data sheets (MSDS's)
- 11. Baseline Risk Assessments
- 12. OHS Reports
- 13. SHE committee meeting minutes
- 14. Occupational health & safety Act
- 15. Construction regulations 2014

### ANNEXURE D

### OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (Regulation 4 of the Construction Regulations. 2014)

### NOTIFICATION OF CONSTRUCTION WORK

1. (a)	Name and postal address of principal contractor:
(b)	Name and tel. No of principal contractor's contact person:
2.	Principal contractor's compensation registration number:
3. (a)	Name and postal address of client:
(b)	Name and tel. No of client's contact person or agent:
4. (a)	Name and postal address of designer(s) for the project:
(b)	Name and tel. No of designer(s) contact person:
్త. appoir	Name and telephone number of principal contractor's construction supervisor on site attention terms of regulation 8(1).
6. regula	Name/s of principal contractor's sub-ordinate supervisors on site appointed in terms of tion 8(2).
7.	Exact physical address of the construction site or site office:
8.	Nature of the construction work:

Expected commencement date:	
Expected completion date:	
Estimated maximum number of persons	on the construction site.
Total: Male:	Female:
Planned number of contractors on the co	onstruction site accountable to principal
Contractor:	
Name(s) of contractors already selected.	
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
pal Contractor	Date
s Agent (where applicable)	Date
	Expected completion date:  Estimated maximum number of persons  Total:  Planned number of contractors on the contractor:  Contractor:  Name(s) of contractors already selected.

THIS DOCUMENT IS TO BE FORWARDED TO THE OFFICE OF THE DEPARTMENT OF LABOUR PRIOR TO COMMENCEMENT OF WORK ON SITE. 

### Copies:

- Original to **Department of Labour** Copy on Health and Safety File 1.
- 2.

### ANNEXURE E

### Wind record register

Wind speed	Location on site	Date	Time	Signature
				alle.
			, i	See Sheep
				W
		4.		
		4		
	.460	II A III		
*	- C			
	4 T			
	Name of the last			
N. Carlotte				
	7			
Va. 10				
ALLOY (S)				
		Wand Speed site	wand speed site Date	Wild Speed Site Date Hime

### ANNEXUREF

### **Medical fitness Register (TYPED ONLY)**

Name	Surname	Date of medical done	Date that medical expires	Signature
Example : John	Botha	11/11/2019	11/11/2020	2019s.
				Sar Vin
				The The
			A PA	1.10
			A Sec. 41	100
			4 A A	
			1	
	li di			
	- 100	Name of the last		
	1,11,2			
	THE WAR			
w. 63				
11 4	1			
		(C		

### ANNEXURE G

### Project Closeout documents that need to be scanned

The H&S files for the Principal Contractors and all Contractors require closure and handover to the Client at the completion of the project. The following list is an example of what should be included, but is not exhaustive. The OHS Agent or the Client may require further information at the time of completion and the Principal Contractor is to ensure that all instructions are met. Documentation would include all records from the start of the project. Daily or monthly plant inspection records are not required unless they are related to an accident. All records to be in electronic format (scanned) and submitted to the OHS agent for approval in adequately formatted lists and folders.

### Health and Safety close out file requirements include:

- a) Client H&S Specification
- b) Principal Contractor's OHS Plan
- c) Organograms
- d) Legal Appointments
- e) Notification to Department of Labour of commencement of work
- f) Letters of Good Standing for the Project
- g) Incident Records
- h) Non-Conformance records
- i) Agent's Audits
- i) Method Statements
- k) Risk assessments
- I) Safe work procedures
- m) Medical surveillance certificates of fitness. Medical records are to be kept according to the OH&S Act as amended.
- n) All drawings for temporary structures (suspended beams/scaffolds etc)
- o) Copies of test results, policies and procedures for environmental monitoring (silica, noise, dusts etc.)

### **Defect and Liability Period**

The H&S files are to be kept 'live' for the defect and liability period by the Principal Contractor. Any work required during the defect and liability period will require an assessment of the H&S file by the OH&S Agent prior to any work commencing.





PO Box 3158

Polokwane

0200

E-Mail: riscon09@gmail.com

# BASELINE HAZARD IDENTIFICATION AND RISK ASSESSMENT

· ·

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

### 2. Methodology

BASE	BASELINE RISK MATRIX		HAZ	HAZARD EFFECT / CONSEQUENCE	EQUENCE	The second second
Loss Type		Insignificant	2 Minor	3 Moderate	4 Maior	Satisfronhic
Timeline		No impact on overall project timeline	May result in overall project timeline overrun of less than 5%	May result in overall project timeline overrun of between 5% and less than 20%	May result in overall project timeline overrun of between 20% and less than 50%	May result in overall project timeline overrun of 50% or more
Budget		No impact on the budget of the project	May result in overall project budget overrun of less than 5%	May result in overall project. budget overrun of between 5% and less than 20%	May result in overall project budget overrun of between 20% and less than 50%	May result in overall project budget overrun of 50% or more
Investment R	Investment Return – NPV loss	Less than R5m	R5m to less than R5om	R5oM to less than R5oom	Rsoom to Rsb	Rsb or more
Quality		No impact on quality	Minimal quality issues that can be addressed in a short timeframe with minimal interactions	Some quality issues that require immediate management action	Significant quality issues that require senior project management interaction	Significant quality issues that require sponsorship intervention with significant resource and cost implications for rework
Safety / Health	<del>-</del>	First aid case / Exposure to minor health risk	Medical treatment case / Exposure to major health risk	Lost time injury / Reversible impact on health	Single fatality or loss of quality of life / Irreversible impact on health	Multiple fatalities / Impact on health ultimately fatal
Environment		Minimal environmental harm – L1 incident	Material environmental harm – L2 incident remediable short term	Serious environmental harm – Lz incident remediable within LOM	Major environmental harm – L2 incident remediable post LOM	Extreme environmental harm – L3 incident irreversible
Legal & Regulatory	latory	No legal impact	Minor legal concerns with minor impact	Some legal concerns with manageable level of impact	Serious legal concerns and significant impact on operations	Legal non-compliance with risk of shutdown of operations with significant
Reputation / !	Reputation / Social / Community	Slight impact - public awareness may exist but no public concern	Limited impact - local public concern	Considerable impact - regional public concern	National impact - national public concern	International impact - international public attention
· · · · · · · · · · · · · · · · · · ·	LIKELIHOOD			RISKRATING		
5 Almost Certain	The unwanted event has occurred frequently; has a go% and higher probability of reoccurring	11 Medium	16 Significant	20 Significant	23 High	25 High
4 Likely	The unwanted event has a probability of between 60% and less than 90% of occurring	7 Medium	12 Medium	17 Significant	21 High	24 High
3 Possible	The unwanted event has a probability of between 30% and less than 60% of occurring	4 Low	8 Medium	13 Significant	18 Significant	22 High
2 Unlikely	The unwanted event has a probability of between 1% and less than 30% of occurring	z Low	5 Low	9 Medium	14 Significant	19 Significant
1 Rare	The unwanted event has never occurred, has a probability of less than 1% of occurring	1 Low	3 Low	6 Medium	10 Medium	as Significant

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

## 3. Hazard Identification, Risk Assessment and determining controls.

The organization shall establish, implement and maintain a procedure(s) for the on-going hazard identification, risk assessment, and determination of necessary controls.

The procedure(s) for hazard identification and risk assessment shall consider:

- routine and non-routine activities;
- activities of all persons having access to the workplace (including contractors and visitors); 9
  - human behaviour, capabilities and other human factors;
- identified hazards originating outside the workplace capable of adversely affecting the health and safety of persons under the control of the organization within the workplace; ਹ ਦੇ
  - hazards created in the vicinity of the workplace by work-related activities under the control of the organization; £ (g) € (g)
    - infrastructure, equipment and materials at the workplace, whether provided by the organization or others;
      - changes or proposed changes in the organization, its activities, or materials;
- modifications to the OH&S management system, including temporary changes, and their impacts on operations, processes, and
- any applicable legal obligations relating to risk assessment and implementation of necessary controls;
- the design of work areas, processes, installations, machinery/equipment, operating procedures and work organization, including their adaptation to human capabilities;

The organization's methodology for hazard identification and risk assessment shall:

- be defined with respect to its scope, nature and timing to ensure it is proactive rather than reactive; and  $\widehat{\mathbf{D}}$
- appropriate. Provide for the identification, prioritization and documentation of risks, and the application of controls, as

For the management of change, the organization shall identify the OH&S hazards and OH&S risks associated with changes in the organization, the OH&S management system, or its activities, prior to the introduction of such changes.

When determining controls, or considering changes to existing controls, consideration shall be given to reducing the risks according to the following hierarchy:

## 4. Hazard Identification, Risk Assessment and Controls

Before construction start, the Baseline Risk Assessment is a theoretical assessment before the construction start in order to highlight the foreseen hazards, but this is not intended to be seen as an absolute 100% of hazards that may occur. The Principal Contractor of their appointed Contractor should take this and whatever hazards that may be presented, due to the unique process which get used to execute the specific construction activity.

### **BASELINE RISK ASSESSMENT**

This Baseline Risk Assessment provides recommendations regarding the control measures, it is however the Principal Contractors duties to ensure that detailed control measures are addressed in the applicable unique Risk Assessment by the Principal Contractor or their appointed Contractors. The risk rating is deliberately rated high because there are no controls in this and without the required controls the possibility of the potential risk is extremely high, as indicated.

i i	Before Principal Contractor establish site ctor
4 1 1	<ul> <li>Client</li> <li>Project Manager</li> <li>Appointed OHS</li> <li>Consultant</li> <li>Principal Contractor</li> </ul>
H CONSEQUENCES RR BE DEALT PRE-CONSTRUCTION  LE APPROVAL AND ADMINISTRATIVE REQUIREMENTS  • Construction delays • Contravention notice from DOL notice from DOL Safety Specification Safety Specification • Baseline Risk Assessment • Site conditions evaluation.	Recommendation  No work  commencement  until approval has been signed off.  Client Health and Safety Specification  Baseline Risk  Assessment
CONSEQUENCES RR HOW  PRE-CONSTRUCTION  PRE-CONSTRUCTION  Construction  Construction  PRE-CONSTRUCTION  Riscol  Recor  Penalties  Contravention  notice from DOL  Dee  Construction  Construction  Linitian  Construction  Construc	delays  • Penalties  • Contravention  notice from DOL
red wing being being had being gistration (e.g lies, load tes lier, refient Spertand stand	appointed not in possession of required or valid competencies as per Client Spec and the OHS Act and Regulations
HAZARD/ITEM No file approval as per OHS requirements and Client specifications	and competency

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Before Principal Contractor establish site	Before Principal Contractor establish site
	- Client Project Manager - Appointed OHS Consultant - Principal Contractor	<ul> <li>Client</li> <li>Project Manager</li> <li>Appointed OHS</li> <li>Consultant</li> <li>Principal Contractor</li> <li>Competent risk</li> <li>assessor</li> </ul>
		Riscon Recommendation No work commencement until approval has been signed off. Client Health and Safety Specification Baseline Risk Assessment Method statement of tasks Site conditions evaluation
	21	7
	Construction     delays     Penalties     Contravention     notice from DOL	<ul> <li>Construction delays</li> <li>Penalties</li> <li>Contravention notice from DOL</li> </ul>
<ul> <li>Appointment not as per legal requirements</li> <li>Lack of experience for appointed positions</li> </ul>	Documentation does not site specific.     Policies and procedure not in place and approved.     Employees not trained in policies and legal requirements	Method of works not site specific.     Risk identification not in place or conducted.     Risk identification does not site specific.     Risk controls not sufficient     Risk assessor not competent
- •	documentation as per OHS Act and Regulations	KISK Identification

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	•	Continuous risk					
		evaluation not					
		conducted				Y	
Induction and	•	Employees entering	<ul> <li>Construction</li> </ul>	21	Riscon	- Client	Before Principal
medical certificate		the site not being	delays		Recommendation	- Project Manager	Contractor
of fitness		inducted.	<ul><li>Penalties</li></ul>		<ul> <li>Site induction can</li> </ul>	- Appointed OHS	establish site
	•	Visitors entering site	<ul> <li>Contravention</li> </ul>		only be done with	Consultant	
		not being inducted /	notice from DOL		an employee if the	- Principal Contractor	
		signing visitors'			required up to date	/	
		induction form.			medical is presented	7	
	•	Induction being			at the induction.	Ŀ	
		conducted on			<ul> <li>Medical fitness</li> </ul>		
		employees without			certificates must be		
eli		them being in			validated by the		
		possession of a valid			principal contractor		
	_	medical certificate of			to ensure adherence		
		fitness in form of		A STATE OF THE PARTY OF THE PAR	to minimum		
Colors Colors	_	annexure 3. The			requirements and		
3000		medical must be			validity of the		
	_	conducted by a			document.		
	_	register Occupational			<ul> <li>Each person's ID or</li> </ul>		
		Health Practitioner			valid work permit		
\$100.	•	Construction vehicles			must be inspected		
		and mobile plant			before induction can		
		operators entering			be allowed on site		
5510		the site without		410	for the individual.		
		being inducted.					
	•	Driver or delivery					
		vehicles not made					
		aware of the specific					
		site conditions.					
	•	<b>Employees being</b>					
		inducted without					
		valid work permits /					
	_	certified ID copies.					

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

Before Principal Contractor establish site	Before Principal Contractor establish site	Before Principal Contractor establish site
- Client - Project Manager - Appointed OHS Consultant - Principal Contractor	<ul> <li>Client</li> <li>Project Manager</li> <li>Appointed OHS</li> <li>Consultant</li> <li>Principal Contractor</li> </ul>	<ul> <li>Client</li> <li>Project Manager</li> <li>Appointed OHS</li> <li>Consultant</li> <li>Appointed Designer.</li> </ul>
Riscon Recommendation Recommendation Record all employees working on site on the employee list. Record all contractors on site on an updated contractor list. Enter new employées and contractors on the list as soon as they have received the site induction.	Riscon- Recommendation The Client cannot allow any work to commence without a valid (stamp) notification of construction work in place.	Riscon Recommendation Client to follow legal requirements as stipulated in the regulations before and during the construction process. Designers on the project to sign
		<b>z</b> .
Construction delays Penalties Contravention notice from DOL	<ul> <li>Construction delays</li> <li>Penalties</li> <li>Contravention notice from DOL</li> </ul>	<ul> <li>Construction delays</li> <li>Penalties</li> <li>Contravention notice from DOL</li> </ul>
Number of employees on site not listed on employee lists. Number of contractors on site not listed on contractor list. Employee and contractor list not being updated as required.	<ul> <li>Construction work         commencing without         an approved         notification.</li> <li>Notification         application not         submitted to DOL         within the prescribed         timeframe</li> </ul>	<ul> <li>Client not following requirements as stipulated in the regulations.</li> <li>Designers not appointed in writing and not made aware of their duties.</li> <li>Designers not following their legal</li> </ul>
•	<u>.</u>	<u> </u>
List of employees and contractors	Notification of construction work- DOL	Client and Designer duties

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	ion During the erection of lanager fence or Safety	tion Duration of construction lanager phase
gement ties on ties on ties on spections the ation as in the	ation — Construction Manager num of 1.8 — Project Manager num of 1.8 — Contractor Safety Officer.  Officer.  is being is being imust not nat ¾ of nt alone	ation Manager Dai - Project Manager must Il time rrsonnel the
agreement in acknowledgement of their duties on the project.  • Designers to conduct the required inspections and review the required documentation as. stipulated in the regulations	<u> </u>	Recommendation The principal contractor must appoint full time security personnel to control the access onto the site.
	Hand and back injuries     Physical injuries     Incorrect manual handling     Lost time injuries     Medical treatment cases     Interruption of, services	<ul> <li>Unauthorized entry to site</li> <li>Injuries to unauthorized people on site</li> <li>Theft of materials and equipment</li> </ul>
duties throughout the project	The erector must follow the specific position as required.     When digging for fence poles, services can be damage.     When post get knocked in it can damage services.     Ergonomics	No security in place at entrances to construction site
	Fencing construction site	Security

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Duration of construction phase		Before construction commences
	Construction Manager Project Manager	<ul> <li>Construction</li> <li>Manager</li> <li>Project Manager</li> <li>Contractor Safety</li> <li>Officer</li> </ul>	<ul><li>Construction</li><li>Manager</li><li>CLO</li><li>OHS Officer</li></ul>
<ul> <li>Dedicated access control sign books to be available for visitors sign ins.</li> </ul>	Riscon Recommendation Only clean water may be used for human consumption and must be marked as safe to be used. Contaminated water areas to be indicated as unsafe for used.	Recommendation  Electrical installations can only be utilized once COC is issued. Electrical installations must be inspected weakly. Electrical installations must be inspected only be done by appointed electrical contractor	<ul> <li>Signed copies of labour contracts are kept on file in the site office.</li> </ul>
	<b>m</b>	13	13
	<ul> <li>Hygiene related diseases</li> </ul>	<ul> <li>Loss of production time</li> <li>Fatality due to electrical</li> <li>Damage of equipment</li> <li>Fire</li> </ul>	<ul><li>Legal disputes and strikes.</li><li>Persons remaining on</li></ul>
	No proper water supplies available on site	No COC available for temporary electrical connection used on site.     Temporary DB not installed in accordance with legal requirements	<ul> <li>Ensure a proper labour contract is signed with all temporary labourers.</li> </ul>
	Temporary water supply	Temporary power supply	Labour control

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Before construction commences
	- Contractor Safety Officer Manager Manager
	Recommendation  The principal contractor must ensure that site is established at the correct location as identified by the Client.  Principal contractor's OHS file must be approved prior to site establishment begins – aligned to New Construction Regulation 2014  All workers on site must be declared medically fit by an Occupational Health Practitioner.  (Annexure 3)  Site –induction must be given to all employees to make them aware of the specific hazards.
¢	<u> </u>
	• nand and back injuries • Dropping of equipment • Physical injuries • Incorrect manual handling • Potentially fatal accidents • Loss of limbs • Lost time injuries • Medical treatment cases • Financial claims
<ul> <li>Sub-standard time keeping and attendance records.</li> <li>All staff employed on site must have a medical fitness certificate</li> </ul>	loading  Damage to property and or vehicles  Cuts and burns.  Rushed activities.  Incorrect supervision  Management team not identifying existing services.  Trip and fall.  Cuts  Cuts  Cuts  Incorrect manual handling – back injuries
Incompetent	Uncontrolled site establishment activities Incorrect stacking procedures

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

(				·		£																		E											
Proof of this should	be placed on the	OHS File.	Before the	commencement of	this phase a site-	specific risk	assessment must be	conducted by a.	competent risk	assessor.	All the employees	involved must be	inducted on the	risks; proof of this	would be signing off	on these risks.	Site specific safe	work procedures	must be followed	during these	activities.	<ul> <li>Relevant toolbox</li> </ul>	talks must also be	held with	200000	H H	Ine contractor must	ensure that the	correct serviceable	tools are available	during this phase.	Employees must be	issued with correct	PPE before works	begin.
																					r														
																										11								4.	
	230							1040				-20						4															7		

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

and fatalities Standing time Lost time injuries 1st Aid medical treatment cases Financial implications	Cilicanii Bilcavy	<ul> <li>Detective mobile crane</li> </ul>	Serious injury	13	Riscon	- Construction	Distinct
• Damage lifting tackle. • Cust time injuries area could cause accidents. • Damage to property implications  • Damage to property  • Tinancial implications • Damage to property • Tinancial implications	anipment and	יייים מיייים מפיי		991			Daimig site
Unsecure offloading     Unsecure offloading     unsecure offloading     area could cause     area could cause     accidents.     Damage to property     implications		can cause accidents.	and ratalities		Kecommendation	Supervisor	establishment
Unsecure offloading     Is Aid medical accidents.     Damage to property     Implications		<ul> <li>Damage lifting tackle.</li> </ul>	<ul> <li>Standing time</li> </ul>		<ul> <li>All lifting equipment</li> </ul>	- Lifting tackle	
• 1st Aid medical treatment cases • Financial implications		<ul> <li>Unsecure offloading</li> </ul>	<ul> <li>Lost time injuries</li> </ul>		including the mobile	Inspector	
• Financial implications		area could cause	<ul> <li>1<sup>st</sup> Aid medical</li> </ul>		crane must be	- Construction OHS	
• Financial implications		accidents.	treatment cases		checked before	officer	
implications		<ul> <li>Damage to property</li> </ul>			allowed on site.		
			implications				
to be used for the offloading proce  Safe Working Lo must be clearly displayed on the crane.  Load test certific will be submitted to the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to operators will be allowed to operators will be allowed to operator.  Daily checks as proceeding the provider be used these documentations must be approve by the principal contractor's OH					correct mobile crane	**aw	
offloading proces  • Safe Working Low  must be clearly displayed on the crane.  • Load test certific  will be submittet  the client.  • Only competent operators will be allowed to oper the mobile crane • Daily checks as p checklist by operator.  • Should a service provider be usee these documentations must be approve by the principal contractor's OH			i pe		to he used for the		
Safe Working Lomust be clearly displayed on the crane.  Load test certific will be submitted the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to operator.  Daily checks as g checklist by operator.  Should a service provider be used these documentations must be approve by the principal contractor's OH					offloading process	4	
must be clearly displayed on the crane.  Load test certific will be submitted the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to oper the mobile cran.  Daily checks as $\rho$ checklist by operator.  Should a service provider be used these documentations must be approve by the principal contractor's OH							
must be clearly displayed on the crane.  Load test certific will be submitted the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to operators will be allowed to operators will be checklist by operator.  Should a service provider be used these documentations must be approved by the principal contractor's OH				va Va Va Va Va			
displayed on the crane.  Load test certific will be submitten the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to operators will be allowed to operators will be allowed to operator.  Daily checks as proved these documentations must be approve by the principal contractor's OH					must be clearly		
<ul> <li>Crane.</li> <li>Load fest certific will be submitted the client.</li> <li>Rope and or slin certificates must submitted to the client.</li> <li>Only competent operators will be allowed to operators will be allowed to operators.</li> <li>Daily checks as provider by operator.</li> <li>Should a service provider be used these documentations must be approve by the principal contractor's OH</li> </ul>					displayed on the		
<ul> <li>Load test certific will be submitted the client.</li> <li>Rope and or slin, certificates must submitted to the client.</li> <li>Only competent operators will be allowed to operators will be allowed to operator.</li> <li>Daily checks as perfectlist by operator.</li> <li>Should a service provider be used these documentations must be approve by the principal contractor's OH</li> </ul>					crane.		
will be submittee the client.  Rope and or slin certificates must submitted to the client.  Only competent operators will be allowed to operators will be allowed to operator.  Daily checks as perfectlist by operator.  Should a service provider be used these documentations must be approve by the principal contractor's OH					10 to		
will be submitted the client.  • Rope and or slin, certificates must submitted to the client.  • Only competent operators will be allowed to operators will be allowed to operator operator.  • Daily checks as percent operator.  • Should a service provider be used these documentations must be approve by the principal contractor's OH.					road test certificate		
<ul> <li>Rope and or sling certificates must submitted to the client.</li> <li>Only competent operators will be allowed to operators will be allowed to operator so the mobile crange operator.</li> <li>Daily checks as provider be used these documentations must be approved by the principal contractor's OH.</li> </ul>			`		will be submitted to		
Rope and or sling certificates must submitted to the client.      Only competent operators will be allowed to operators will be allowed to operator will be allowed to operator.      Daily checks as perhecklist by operator.      Should a service provider be used these documentations must be approve by the principal contractor's OH.					the client.		
certificates must submitted to the client.  Only competent operators will be allowed to operators will be allowed to operators of the mobile cran.  Daily checks as perfectlist by operator.  Should a service provider be used these documentations must be approve by the principal contractor's OH.			~		<ul> <li>Rope and or sling</li> </ul>		
					certificates must be		
					submitted to the		
					client.		
				100	<ul> <li>Only competent</li> </ul>		
			آ)		on erators will be		
					allowed to operate		
					the mobile crane.		
					<ul> <li>Daily checks as per</li> </ul>		
					checklist by		
					operator.		
provider be used these documentations must be approving by the principal contractor's OH.							
these documentations must be approve by the principal contractor's OH:					provider be used		
documentations must be approve by the principal contractor's OH:					these		
must be approve by the principal contractor's OH:		ę.			documentations		
by the principal contractor's OH:					must be approved		
contractor's OH'					by the principal		
					contractor's OHS		
Officer.					Officer.		

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	BY WHEN	
	BY WHOM	- Construction Supervisor Construction OHS Officer - Construction Supervisor - Construction OHS Officer Qualified operators.
<ul> <li>Proper storing facilities for tool and equipment.</li> <li>Adequate waste bins available.</li> <li>Regular cleaning of these bins</li> <li>Waste recycling is encouraged.</li> <li>A COC certificate for temporary electrical installations by a register competent electrician.</li> </ul>	RKS HOW IS HAZARD TO BE DEALT	Method statement     Issue base risk     assessments     Offloading     procedures     Qualified operators     Check operator's     medicals     Pre- start checklist     Supervision     Correct PPE     Method Statements     Issue base risk     assessments     Induction all     employees     Medicals of     Operators
	2. CIVILS WORKS CONSEQUENCES RR	• Serious injury • Fatality • Lost time injury First aid treatment cases cases • Fatalities • Lost time injuries • Serious injuries • Serious injuries • First aid treatment cases Production time lost
	RISK ASSOCIATED WITH HAZARD	Offloading machinery could lead to damage to property and equipment     Falling machinery from lowbed Workers hit by machinery machinery      Employees hit with machinery     Breakdowns     Oil spillage     Poor workmanship     Poor visibility due to dust
	NO HAZARD/ITEM	ESTABLISH TEMPORARY PARKING AREA USING MOTOR GRADER; TLB; EXCAVATOR; WATER TRUCK; ROLLER COMPACTOR; TIPPER TRUCS

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Construction Supervisor Construction OHS Officer  Qualified operators.	Construction Supervisor Supervisor Construction OHS Officer
<ul> <li>Qualified operators</li> <li>Pre- start checklist</li> <li>of machinery</li> <li>Identify lay-down area</li> <li>Supervision</li> <li>Plant seats need to be maintained</li> </ul>	Method statements     Issue base risk     assessments     Employees must be visible always     Direct supervision.	<ul> <li>Method statements</li> <li>Issue base risk assessments</li> <li>Employees must be visible always</li> <li>Direct supervision.</li> <li>Well trained operators</li> <li>Level on survey profiles clearly indicated</li> <li>Proper communication between supervisor and operators</li> <li>Induct employees on safe working procedures</li> </ul>
	19	13
	Fatalities     Serious injuries     Lost times     injuries     Standing time due to poor     workmanship and work to repeat.	<ul> <li>Fatalities</li> <li>Serious injuries</li> <li>Lost times injuries</li> <li>Accidents due to defective machines</li> <li>Damaging services</li> <li>Over excavation</li> <li>Dust</li> <li>Electrocution when damaging electrical services</li> <li>Damage to services</li> <li>Damage to services</li> <li>Employees not visible to</li> </ul>
• Ergonomics	<ul> <li>Trip and fall into excavations</li> <li>Falling concrete pipes while offloading</li> <li>Poor quality workmanship</li> <li>Employees buried in trenches</li> </ul>	<ul> <li>Excavate with excavator to the specific level</li> <li>Trip and fall</li> <li>Collapsing soil</li> <li>Machine struck employees</li> <li>Hand injuries by excavation by hand</li> <li>Incorrect manual handling</li> <li>Ergonomics</li> </ul>
	STORM WATER DRAINAGE	AND TRENCHES

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	BY WHEN	
	BYWHOM	- Construction supervisor - Construction OHS Officer
All excavations must be inspected daily     Provide ladders ever 6 m for access in and out of excavations deeper than 1.5 m     Excavated material to be placed away from side of excavation to be shored (if necessary) and barricaded immediately     Excavations should be backfilled as soon as possible after excavation     Keep area barricaded with hard barricaded with hard barricaded with hard barricading until backfill is done until backfill is done     Employees must not work in bended (unnatural posture) for prolong times	JCTION RR HOW IS HAZARD TO BE DEALT	Quailed steel fixers     Induct workers on MSDS for concrete dust
machine operator  • Material falling in excavations while employees are working in excavations • Inadequate access and exit points Employees may strain muscles to get into or out of excavations	3. CONSTRUCTION CONSEQUENCES RR	Cuts; bruises;     hand injuries due     to steel work     activities
	RISK ASSOCIATED WITH HAZARD	<ul> <li>Filling material</li> <li>Concrete dust</li> <li>inhalation</li> </ul>
	NO HAZARD/ITEM	REINFORCING. CONCREATE

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Skin irritation	<ul> <li>Medical</li> </ul>		<ul> <li>Correct PPE for task</li> </ul>	- Excavation Supervisor	
	(dermatitis)	treatment cases		<ul> <li>Correct gloves for</li> </ul>	- Hazardous Chemical	
	<ul> <li>Unsecure retaining</li> </ul>	<ul> <li>Serious injuries</li> </ul>		steel fixing	Supervisor	
	wail	to back due to		<ul> <li>Toolbox talks</li> </ul>		
_	<ul> <li>Sharp edges</li> </ul>	inadequate		<ul> <li>Direct supervision</li> </ul>		
_	<ul> <li>Ergonomics</li> </ul>	manual handling		<ul> <li>Correct tools for the</li> </ul>	6.	
		procedures		task.		
		Lost time injuries		<ul> <li>Employees shall as</li> </ul>		
		First aid		far as possible fix		
		treatment cases.		steel in a lifted	1	
				position to limit the		
				bending over to		
	Concrete in contact	Dermatitis	6	Method statements	- Health and Safety	
	with skin	Lost time injuries		• Issue base risk	representative	
	<ul> <li>Sharp edges could cut</li> </ul>			assessments	- Construction	
	body parts		e r	<ul> <li>Toll box talks</li> </ul>	Supervisor	
	<ul> <li>Heavy rebar could</li> </ul>			<ul> <li>Proper induction in</li> </ul>	- Construction OHS	
	have potential back			task task	officer	
	injuries	× ×		<ul> <li>Supervision</li> </ul>		
	•					
	<ul> <li>Speed of delivery</li> </ul>	Damage to	18	<ul> <li>Proper supervision</li> </ul>	- Construction	During all
	vehicles	equipment and		when deliveries take	Manager	deliveries.
	<ul> <li>Dumping at the wrong</li> </ul>	or property		place.	- Health and Safety	
	place	<ul> <li>Production loss</li> </ul>		<ul> <li>Ensure that</li> </ul>	Officer	
	<ul> <li>No pointer/banks man</li> </ul>	<ul> <li>Injuries and</li> </ul>	30 k	assistance is given		
	to assist when vehicle	possible fatal		to driver when		
	is reversing	incidents to		reversing and or		
	3	employees.		dumping materials.		
	<ul> <li>Falling Materials</li> </ul>	• LTI	18	<ul> <li>Demolition current</li> </ul>	Demolition	During
	<ul> <li>Premature collapse of</li> </ul>	<ul> <li>Medical Cases /</li> </ul>	1000	method statement	Supervisor	Demolition work
	Structure	1st Aid Cases		<ul> <li>Ensure all</li> </ul>	- Construction	
		<ul> <li>May result in</li> </ul>		emergency	Manager	
	*	overall project		procedures are in		
		overrun.		place and all details		
				are displayed.		

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Before and During task	Before and During task
	- Construction supervisor - Construction OHS Officer - Excavation Supervisor - Civil Engineer - Hazardous Chemical Supervisor	<ul><li>Site Supervisor</li><li>Safety Rep</li><li>Team</li><li>Competent</li><li>Plumber</li></ul>
Ensure that structure demolition has been approved by designer and Construction Manager.      All personnel must have the necessary competencies:     Ensure at all times there is a safe means of access and egress.      Barricades are, no unauthorised entry.      All employees must wear the relevant PPE	Method statements     Issue base risk     assessments     Inspections by     excavation     supervisor     Proper train     operators     Location of services	<ul> <li>Ensure         measurements are         correct.</li> <li>Supervisor to         supervise.</li> <li>Proof of all workers         medically fit</li> </ul>
	(A)	<u>ه</u>
<ul> <li>Trip slip and falls.</li> <li>Serious injuries or possible fatalities</li> </ul>	Manual handling injuries     Lost time injuries.     First aid treatments	Medical Cases / 1st Aid Cases     May result in     overall project     overrun.     Trip slip and falls
	<ul> <li>Hard rock material</li> <li>Risk of collapsing excavations</li> <li>Seepage of subterranean water</li> <li>Employees inhaling dangerous fumes.</li> <li>Skin contacts with hazardous substances</li> </ul>	<ul> <li>Falling of objects</li> <li>Hand Injuries</li> <li>Back Injuries</li> <li>Strains</li> <li>Damage to property / Equipment</li> </ul>
	Excavation filling Trenches Plumbing works	

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Before and During task	Before and During task.
e e	Construction     Supervisor     Health and Safety     Officer.	Construction Supervisor Flagmen: Qualified Traffic control officer 1st Aider Emergency Coordinator
<ul> <li>Ensure all workers         are trained on the         specific task to         prevent damage.</li> <li>Toolbox talks to be         held on job specific</li> </ul>	<ul> <li>Employees must be provided with the PPE as determined in task risk, assessment.</li> <li>Must be done under constant supervision.</li> <li>Must be done in line with task risk assessment to ensure the safety of employees</li> </ul>	Installation of road traffic signs & regulating according to installation inventory.      Trained flagmen     Flagmen working in shifts.     Insure good visibility at all times.     Radio communication between flagmen     Implement:     Advance warning
	o	
	Uth Aid Cases / 1st Aid Cases / 1st Aid Cases May result in overall project overrun. Trip slip and falls	<ul> <li>Poor visibility could lead to vehicles ignoring traffic signs.</li> <li>Poor lay-out of signs could lead to traffic accidents (major) or fatalities.</li> <li>Standing time</li> <li>Flagmen ran over by speeding</li> </ul>
	<ul> <li>Tiling not done according to the drawing / design</li> <li>Tiling in public areas not completed creating a tripping hazard where there is a difference in floor level.</li> <li>Employee using tile cutter sustaining injuries due to not wearing correct PPE.</li> <li>Employees sustaining hand injuries while hand ling tiles</li> </ul>	<ul> <li>Serious injuries/ fatalities</li> <li>Heat exposure to workers</li> <li>Hit &amp; run accidents.</li> <li>Flying objects form loose stones.</li> <li>Damage to construction vehicles</li> <li>Damage to traffic signage</li> </ul>
	g:	Regulating traffic – flagmen operations:

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

												During the task	)									
												Construction	Supervisor	<ul><li>Health and safety</li></ul>	officer							
are, transition area; buffer zone; work zone termination area	Correct high     visibility vests & PPE.	signage. Continued of compliance for	flagmen  Correct appointments	Traffic Control     Officer	Direct supervision	Planned Job	Observations      Daily start-up	procedures &	closure	<ul> <li>Replacement of</li> </ul>	broken traffic signs & traffic cones	Placement of kerbs	close as possible to	needed area.	<ul> <li>Proper pvc gloves</li> </ul>	<ul> <li>Steel toe – capped</li> </ul>	safety shoes	<ul> <li>Proper induction</li> </ul>	on lifting methods	<ul> <li>Dust mask to be</li> </ul>	wear when any	dust is visible.
ead								A	·			18		dry	100		ot		Aling			
traffic could lead to fatality							Ų					Damage to	vehicles	Inhalation of dry	cement and	silica dust	Hand and foot	injuries	Manual handling	injuries		
												<ul> <li>Offloading of kerbs</li> </ul>	Obstruction in road	reserve / side walks	Wrong placement of	kerbs						
												Laying of Kerbs										

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

During task	Ongoing
<ul> <li>Construction         Supervisor         Health and Safety         Officer     </li> </ul>	- Construction Supervisor - Foreman - Fire Fighting Team - First Aider - Fire prevention supervisor
Wear correct PPE.     Deviations & correct prominent signage	Riscon  Recommendation  • Adequate fire equipment to be provided and placed at suitable location.  • Monthly checklist of all fire equipment's  • Provide training and have fire drills periodically.  • Store material in demarcated areas  • Cigarettes to be extinguished properly and thrown into rubbish bins.  • Ashtrays and waste bins to be emptied daily.  • Fire escape routes and assembly points to be determined and clearly marked.  • All workers must use appropriate PPE,  • Close supervision • Discuss risk assessment with workers.
20	<b>108</b>
<ul> <li>Occupational illness – respiratory system &amp; skin</li> <li>Injuries</li> <li>Obstruct &amp;/or Collision</li> </ul>	Medical Cases / 1st Aid Cases     May result in overall project overrun.     Trip slip and falls.     Serious injuries or possible fatalities when fire gets out of control.     Damage to property     Medical treatment     Bruises, cuts, broken limb     1st aid case treatment     Loss of life
<ul> <li>Cement powder</li> <li>Working in vicinity of plant</li> <li>Public transport</li> </ul>	<ul> <li>Inadequate and wrongly placed fire equipment can cause delay in dealing with fire should it occur.</li> <li>Poor housekeeping</li> <li>Falling objects</li> <li>Hand Injuries</li> <li>Strains</li> <li>Non-availability of fire equipment's</li> <li>Untrained personnel using wrong type of equipment to extinguish the fire equipment to extinguish the fire delays in searching for fire alarm not</li> <li>Fire alarm not functional or inaudible</li> <li>Access blocked and people trapped inside, firefighting team not able to obtain access.</li> <li>Shortage or nonoperation of firefighting equipment</li> <li>Overcrowding an exit point during fire</li> </ul>
Stabilization with cement	Fire Protection  wrongly placed fire equipment can caus delay in dealing with fire should it occur.  Poor housekeeping Falling objects Falling objects Hand Injuries Back Injuries Strains Non-availability of fequipment's Untrained personne using wrong type of equipment to equipment to equipment to extinguish the fire delays in searching fire extinguisher.  Fire alarm not functional or inaudil Access blocked and people trapped insifirefighting team no able to obtain acces. Shortage or nonoperation of firefighting equipment operation of firefighting equipment operation of firefighting equipment of point during fire

seline Kisk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

ning	• Construction			lan Scaffold Inspector	1				ection	drawn	petent		É		+ 1	าแลสห	re the	on plan.	ection	ď)	all le	vorking		Se	eights		leights		ssary	7	hecklist	lace			Sea
<ul><li>Induction training</li><li>Toolbox talks training</li></ul>	21 • A site and task	587	llei Jillads	protection plan	including rescue	nlan miist he in	2	place.	This fall protection	plan must be drawn	up by a competent	approinted Fall	Protection Plan	Developer	The Clients Agent		must approve the	fall protection plan.	<ul> <li>The fall protection</li> </ul>	plan must be	inducted to all	employees working	at heights.	Ail employees	working at heights	should have	working at heights	training.	<ul> <li>All the necessary</li> </ul>	registers and	inspection checklist	must be in place	and checked	regularly.	All employees
	Serious iniuries		20 IIII III III	from one level to	another level.	Equipment and		material could	be damage when	dropped from a	height.	Public and	plinos seavolame	be affected	should they	אווסמומ נוובא	enter the drop	zone.	Non-adherence	to FPP could lead	to major and	serious injuries.	<ul> <li>Employees not</li> </ul>	trained to work	at heights.										
	<ul> <li>Fatalities</li> </ul>	• Serious injuries		<ul> <li>Damage to equipment</li> </ul>	and material.	Production lost		<ul> <li>No barricading at</li> </ul>	drop zone	•																				ę					
	Working at heights	(general)																																	

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

£	Ongoing
	<ul> <li>Construction</li> <li>Manager</li> <li>Scaffold Inspector</li> <li>Health and safety</li> <li>Officer</li> </ul>
working at height medical in place.  • All employees working at height must wear the correct specific for task personal protective clothing.  • All hard hats of employees working at height must have chin straps.  • Proper procedures must be in place to gain access to tools and materials.  • No tools and materials.  • No tools and material may be dropped from any height.  • Adequate area identified for a drop zone.  This drop zone must be properly barricaded with all the necessary warning signs.	Must be designed and inspected by a competent appointed person as per specification requirements.     Must be inspected daily.
	Serious injuries when falling from one level to another level.     Equipment and material could be damage when dropped from a
	<ul> <li>Scaffolding not being erected in accordance with SANS 10085 standards.</li> <li>Employees working at heights not certified to work at heights in accordance with the SANA requirements.</li> </ul>
	Scaffolding

(

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

		: ,					, 4								311																				
Must be erected by	competent scaffold	erectors.	Must be signed off as	safe for use with	signage clearly	displayed before	employees may	commence with	scaffold work	,																	T SW					VI SE			
Public and	employees could	be affected	should they	enter the drop	zone.	•															·														
for working at heights	training.	<ul> <li>Employees allowed to</li> </ul>	work at heights who is	not medical fit and	not in possession of a	valid medical	certificate of fitness.	No rescue plan in	place for employees	working at heights.	Scaffold erected on	uneven ground level.	No sole boards	installed underneath	scaffold base jacks	when erected on soil	surface.	Scaffolding not	inspected daily by	competent, appointed	scaffold inspector.	No sign on scaffolding	indicating safe /	unsafe for use.	No design available	for special scaffolding	Area below	scaffolding not	barricaded off when	being dismantled.	Materials not being	lowered to ground	level correctly while	scaffolding are being	dismantled.

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Ongoing	Ongoing
	Site supervisor     OHS Officer     Health and Safety     Reps.	Site Supervisor     OHS Officer     Competent     Electrician
	<ul> <li>Proper planning</li> <li>Ensure sufficient rest periods.</li> <li>Only used skilled employees.</li> <li>Ensure tools and equipment is inspected before shift commence.</li> <li>Inspection registers must be completed and kept up to date.</li> </ul>	<ul> <li>Ensure power is off and isolate.</li> <li>All workers must wear PPE to prevent injuries.</li> <li>Trained and qualified electrician to complete task</li> <li>Proper supervision from Supervisor</li> <li>Toolbox Talks to be conducted on electrical tasks.</li> <li>Always have a Fire extinguisher at job task</li> <li>All tools and equipment must be inspected.</li> </ul>
	13	13
	<ul> <li>Cuts to hands leading to minor to serious injuries.</li> <li>Back injuries due to working in a bending position.</li> <li>Material waste due to unskilled workers.</li> </ul>	LTI     L <sup>st</sup> Aid Cases / Medical treatment     Serious injuries from falling.     Back injuries from falling.     Possibility of budget overrun on project.     May result in project time overrun
<ul> <li>Scaffold not sufficiently tied into existing building / structure when required.</li> </ul>	<ul> <li>Working in bending positions</li> <li>Ergonomic hazards to employees</li> <li>Use of sharp hand tools.</li> <li>Cut related injuries.</li> <li>Unskilled workers</li> </ul>	Falling from ladder, back injuries     Hand injuries     Electrical burns     Electrocution     Fire from incompetent electrical when misconnecting cables, etc
	Carpentry	Electrical

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Ongoing
	- Construction Supervisor - Construction OHS Officer - All employees - First aider
<ul> <li>Fire extinguishers must be available and serviced.</li> <li>Proper supervision must be applied from Supervisor.</li> <li>Correct tools and equipment must be used.</li> <li>All workers must wear correct and sufficient PPE as required.</li> <li>Toolboxes talk on Power tools.</li> <li>Ensure Electricity is isolated and locked out / switched off</li> </ul>	Riscon Recommendation Employees trained to recognise MSD symptoms. Encourage early reporting of MSD symptoms. Re-evaluate work procedures. Ensure regular resting periods. Employees need proper training in lifting practises. Job task observations Mechanical lifting
	100
	Lost time injury     Medical     treatment     incidents     Body injuries     Heat exhaustion
	<ul> <li>Repetition movements resulting in MSD'S.</li> <li>Grip force with hands, wrist, arms resulting in muscle fatigue and inflammation of the muscles and tendons.</li> <li>Liff /lower force activities that could result in lower back injuries.</li> <li>Working in awkward positions</li> <li>Extreme temperatures</li> <li>Activities that result in hand arm vibration that could result in</li> </ul>
	Ergonomic

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

	Ongoing afety ss
	- COVID – 19 Compliance officers - Construction Manager - Health and Safety Officer - All Employees
Redesigned tasks Trained first aider. Sufficient fresh water hourly (600 ml) Sunscreen should also be available. Equipment with lowest vibration be used. Proper maintenance schedules must be in place. Proper medical surveillance program in place program in place with place. Vibrating reducing hand gloves must be used.	COVID-19     Management plan     COVID-19 policy in place     All the new works areas must be disinfected and recorded.     MSDS must be available of the disinfection chemicals used.     All employees must be issued with 2 cloth face masks.     All employees must be issued with 2 cloth face masks.
	<b>2</b>
Manie de la constante de la co	Fever     Tiredness     Dry Cough     Runny nose     Sore Throat     Aches and Panes     Business     interruption     Financial loss
MSD and white finger syndrome.	Public/Professional Team and employees expose to COVID – 19 Virus
	COVID-19

and the second

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

4				k																				
Inducted in terms of COVID-19.  • Sufficient posters	and information displayed at the	Adequate hand     wash stations with	soap and water and	paper towels:     In areas where hand:	wash stations are	not possible, hand sanitation stations	should be available.	Sanitation chemicals     Should have an	alcohol content of	MSDS must be	available of these	sanitation chemicals.	All employees must	be screened (body	temperature) before	and after each shift.  This must be	recorded.	Hands must be	sanitised when	arriving at work.	All visitors to the site	must also be	screened and sanitised.	<ul> <li>This must also be</li> </ul>
				2.00														50				100		

Client Baseline Risk Assessment for SAPS Mankweng - Rev 1.1 Feb 2024 - Riscon consultants © RisCon Consultants (All copyrights reserved)

-		€.	200	٠, ۲																
The Principal	Contractor must	have a dedicated	isolation room/area	when needed.	The principal of no	mask, no entry must	always apply.	Social distancing of	at least 1.5m must	always be applied	where possible.	<ul> <li>Eating facilities must</li> </ul>	also arrange in such	manner that 1.5m	can be applied.	A sufficient daily	cleaning schedule	should be	implemented and	maintained
					-										=					
638							5.5				表 第							N. Y.		



### **DEPARTMENT OF PUBLIC WORKS**

# HIV/AIDS SPECIFICATION

**OCTOBER 2004** 

### **SECTION**

### **HIV/AIDS SPECIFICATION**

### **HIV/AIDS REQUIREMENTS**

### 1 SCOPE

This specification contains all requirements applicable to the Contractor for creating HIV/AIDS awareness amongst all of the Workers involved in this project for the duration of the construction period, through the following strategies:

- Raising awareness about HIV/AIDS through education and information on the nature of the
  disease, how it is transmitted, safe sexual behaviour, attitudes towards people affected and people
  living with HIV/AIDS, how to live a healthy lifestyle with HIV/AIDS, the importance of voluntary
  testing and counselling, the diagnosis and treatment of Sexually Transmitted Infections and the
  closest health Service Providers;
- · Informing Workers of their rights with regard to HIV/AIDS in the workplace;
- Providing Workers with access to condoms and other awareness material that will enable them to make informed decisions about sexual practices.

### 2 DEFINITIONS AND ABBREVIATIONS

### 2.1 Definitions

Service Provider: The natural or juristic person recognised and approved by the Department of Public Works as a specialist in conducting HIV/AIDS awareness programmes.

Service Provider Workshop Plan: A plan outlining the content, process and schedule of the training and education workshops, presented by a Service Provider which has been approved by the Representative/Agent.

Worker: Person in the employ of the Contractor or under the direction or supervision of the Contractor or any of his Sub-contractors, who is on site for a minimum period of 30 days in all.

### 2.2 Abbreviations

HIV: Human Immunodeficiency Virus.

AIDS : Acquired Immune Deficiency Syndrome.

STI : Sexually Transmitted Infection.

### 3 BASIC METHOD REQUIREMENT

3.1 The Contractor shall, through a Service Provider, conduct onsite workshops with the Workers.

The Service Provider shall develop and compile a Service Provider Workshop Plan to be presented at the workshops and which will be best suited for this project to achieve the specified objectives with regard to HIV/AIDS awareness.

The Service Provider Workshop Plan shall be based on the following information provided by the Contractor:

- Number of Workers and Sub-contractors on site;
- When new Workers or Sub-contractors will join the construction project:
- Duration of Workers and Sub-contractors on site;
- How the maximum number of Workers can be targeted with workshops;
- How the Contractor prefers workshops to be scheduled, e.g. three hourly sessions per Worker, or one 2.5 hour workshop per Worker;
- Profile of Workers, including educational level, age and gender (if available);
- · Preferred time of day or month to conduct workshops;
- A Gantt chart reflecting the construction programme, for scheduling of workshops;
- Suitable venues for workshops.

The Contractor shall submit the Service Provider Workshop Plan for approval within 21 days after the tender acceptance date. After approval by the Representative/Agent, the Contractor shall make available a suitable venue that will be conducive to education and training.

- 3.2 The Service Provider Workshop Plan shall address, but will not be limited to the following:
- 3.2.1 The nature of the disease;
- 3.2.2 How it is transmitted:
- 3.2.3 Safe sexual behaviour:
- 3.2.4 Post exposure services such as voluntary counselling and testing (VCT) and nutritional plans for people living with HIV/AIDS:
- 3.2.5 Attitudes towards other people with HIV/AIDS:
- 3.2.6 Rights of the Worker in the workplace;
- 3.2.7 How the Awareness Champion will be equipped prior to commencement of the HIV/AIDS awareness programme with basic HIV/AIDS information and the necessary skills to handle questions regarding the HIV/AIDS awareness programme on site sensitively and confidentially;
- 3.2.8 How the Service Provider will support the Awareness Champion;
- 3.2.9 Location and contact numbers of the closest clinics, VCT facilities, counselling services and referral systems:
- 3.2.10 How the workshops will be presented, including frequency and duration;
- 3.2.11 How the workshops will fit in with the construction programme;
- 3.2.12 How the Service Provider will assess the knowledge and attitude levels of attendees to structure workshops accordingly;
- 3.2.13 How the video will be used;
- 3.2.14 How the Service Provider will elicit maximum participation from the Workers;
- 3.2.15 A questions and answers slot (interactive session).

The Service Provider Workshop Plan shall encompass the Specific Learning Outcomes (SLO) as stipulated.

### 4 HIV/ AIDS AWARENESS EDUCATION AND TRAINING

### 4.1 Workshops

The Contractor shall ensure that all Workers attend the workshops.

The workshops shall adequately deal with all the aspects contained in the Service Provider Workshop Plan. A video of HIV/AIDS in the construction industry, which can be obtained from all Regional Offices of the Department of Public Works, is to be screened to Workers at workshops. In order to enhance the

learning experience, groups of not exceeding 25 people shall attend the interactive sessions of the workshops.

### 4.2 Recommended practice

### 4.2.1 Workshop Schedule

Presenting information contained in the Service Provider Workshop Plan can be divided in as many workshop sessions as deemed practicable by the Contractor, provided that all Workers are exposed to all aspects of the workshops as outlined in the Service Provider Workshop Plan.

Breaking down the content of information to be presented to Workers into more than one workshop session however, has the added advantage that messages are reinforced over time while providing opportunity between workshop sessions for Workers to reflect and test information. Workers will also have an opportunity to ask questions at a following session.

### 4.2.2 Service Providers

A database of recommended Service Providers is available from all Regional Offices of the Department of Public Works.

### 4.2.3 HIV/AIDS Specific Learning Outcomes and Assessment Criteria

Workers shall be exposed to workshops for a minimum duration of two-and-a-half hours. In order to set a minimum standard requirement, the following specific learning outcomes and assessment criteria shall be met.

### 4.2.3.1 UNIT 1: The nature of HIV/AIDS

After studying and understanding this unit, the Worker will be able to differentiate between HIV and AIDS and comprehend whether or not it is curable. The Worker will also be able to explain how the HI virus operates once a person is infected and identify the symptoms associated with the progression of HIV/AIDS.

### Assessment Criteria:

- 1. Define and describe HIV and AIDS;
- 2. List and describe the progression of HIV/AIDS.

### 4.2.3.2 UNIT 2: Transmission of the HI virus

After studying and understanding this unit, the Worker will be able to identify bodily fluids that carry the HI virus. The Worker will be able to recognise how HIV/AIDS is transmitted and how it is not transmitted.

### Assessment Criteria:

- 1. Record in what bodily fluids the HI virus can be found;
- 2. Describe how HIV/AIDS can be transmitted;
- Demonstrate the ability to distinguish between how HIV/AIDS is transmitted and misconceptions around transmittance of HIV/AIDS.

### 4.2.3.3 UNIT 3: HIV/AIDS preventative measures

After studying and understanding this unit, the Worker will comprehend how to act in a way that would minimise the risk of HIV/AIDS infection and to use measures to prevent the HI virus from entering the bloodstream.

### Assessment Criteria:

- 1. Report on how to minimise the risk of HIV/AIDS infection;
- 2. Report on precautions that can be taken to prevent HIV/AIDS infection;
- 3. Explain or demonstrate how to use a male and female condom;
- List the factors that could jeopardize the safety of condoms provided against HIV/AIDS Transmission.

### 4.2.3.4 UNIT 4: Voluntary HIV/AIDS counselling and testing

After studying and understanding this unit, the Worker will be able to recognise methods of testing for HIV/AIDS infection. The Worker will be able to understand the purpose of voluntary HIV/AIDS testing and pre- and post-test counseling.

### Assessment Criteria:

- 1. Describe methods of testing for HIV/AIDS infection;
- 2. Report on why voluntary testing is important;
- 3. Report on why pre- and post-test counselling is important.

### 4.2.3.5 UNIT 5: Living with HIV/AIDS

After studying and understanding this unit, the Worker will be able to recognise the importance of caring for people living with HIV/AIDS and be able to manage HIV/AIDS.

### Assessment Criteria:

- 1. List and describe ways to manage HIV/AIDS;
- 2. Describe nutritional needs of people living with HIV/AIDS;
- 3. Describe ways to embrace a healthy lifestyle as a person living with HIV/AIDS;
- 4. Explain the need for counselling and support to people living with HIV/AIDS.

### 4.2.3.6 UNIT 6: Treatment options for people with HIV/AIDS

After studying and understanding this unit, the Worker will be familiar with the various treatments available to HIV/AIDS infected or potentially HIV/AIDS infected people.

### Assessment Criteria:

- 1. Discuss anti-retroviral therapy;
- 2. List methods of treatment to prevent HIV/AIDS transmission from mother-to-child:
- 3. Describe the need for treatment of opportunistic diseases for people living with HIV/AIDS;
- 4. Describe post exposure prophylactics.

### 4.2.3.7 UNIT 7: The rights and responsibilities of Workers in the workplace with regard to HIV/AIDS

After studying and understanding this unit, the Worker will be able to identify the rights and responsibilities of the Worker living with HIV/AIDS in the workplace. The Worker will recognise the importance of accepting colleagues living with HIV/AIDS and treating them in a non-discriminative way.

### Assessment Criteria:

- 1. Discuss the rights of a person living with HIV/AIDS in the workplace;
- 2. Discuss the responsibilities of a person living with HIV/AIDS in the workplace;
- Report on why acceptance and non-discrimination of colleagues living with HIV/AIDS is important.

### 4.3 Displaying of plastic laminated posters and distribution of information booklets

The Contractor shall obtain a set of four laminated posters conveying different key messages and information booklets. The contractor should include the costs of posters and information booklets in his/her tender price.

The above-mentioned posters and information booklets have been prepared to raise awareness and to share information about HIV/AIDS and STI's.

Posters or display stands shall be displayed on site as soon as possible, but not later than 14 days after the date of site handover.

Posters shall be displayed in areas highly trafficked by Workers, including toilets, rest areas, the site office and compounds.

The posters on display must always be intact, clear and readable.

Information booklets must be distributed to all Workers as soon as possible, but not later than 14 days after site handover, or as soon as the Worker joins the site.

### 5 PROVIDING WORKERS WITH ACCESS TO CONDOMS

The Contractor shall provide and maintain condom dispensers and make both male and female condoms, complying with the requirements of SABS ISO 4074, available at all times to all Workers at readily accessible points on site, for the duration of the contract. The Contractor may obtain condom dispensers from the Department of Health and condoms may be obtained from the Local Clinic or the Department of Health.

At least one male and one female condom dispenser and a sufficient supply of condoms, all to the approval of the Representative/Agent, shall be made available on site within 14 days of site hand over. Contractors should note that arrangements to obtain condoms from the Department of Health Clinics prior to site hand over may be necessary, to ensure that condoms are available within 14 days of site handover.

Condoms shall be made available in areas highly trafficked by Workers, including toilets, the site office and compounds.

## 6 ENSURING ACCESS TO HIV/AIDS TESTING AND COUNSELLING FACILITIES AND TREATMENT OF SEXUALLY TRANSMITTED INFECTIONS (STI)

The Contractor shall provide Workers with the names of the closest Service Providers that provide HIV/AIDS testing and counselling and Clinics providing Sexually Transmitted Infection (STI) diagnosis and treatment. Information on these Service Providers and Clinics must be displayed on a poster of a size not smaller than A1 in an area highly trafficked by Workers.

### 7 APPOINTMENT OF AN HIV/AIDS AWARENESS CHAMPION

7.1 Within 14 days of site handover the Contractor shall appoint an Awareness Champion from amongst the Workers, who speaks, reads and writes English, who speaks and understands all the local languages spoken by the Workers and who shall be on site during all stages of the construction period. The Contractor shall ensure that the Awareness Champion has been trained by the Service Provider on basic HIV/AIDS information, the support services available and the necessary skills to handle questions regarding the HIV/AIDS programme in a sensitive and confidential manner.

- 7.2 The Awareness Champion shall be responsible for:
- 7.2.1 Liasing with the Service Provider on organising awareness workshops;
- 7.2.2 Filling condom dispensers and monitoring condom distribution;
- 7.2.3 Handing out information booklets;
- 7.2.4 Placing and maintaining posters.

### 8 MONITORING

The Contractor shall grant to the Representative/Agent reasonable access to the construction site, in order to establish that the Contractor complies with his obligations regarding HIV/AIDS awareness under this contract.

The Contractor must report problems experienced in implementing the HIV/AIDS requirements to the Representative/Agent.

The attached SITE CHECKLIST (SCHEDULE A) shall be completed and submitted at every construction progress inspection to the Representative/Agent.

The attached SERVICE PROVIDER REPORT (SCHEDULE B) shall be completed and submitted on a monthly basis to the Department's Project Manager, through the Representative/Agent.

The attached CONTRACTOR HIV/AIDS PROGRAMME REPORT (SCHEDULE C), a close out programme report, shall be completed by the Contractor at the end of the contract.

When did construction commence:  Name of Departmental Project Manager:
--

Please refer to HIV/AIDS Programme activities during the reporting period

Tick the block if Contractor satisfactorily complied with specifications	ly complied with	h specifications					
DATE	П	٦	<u>a</u> .	Ы	<u>a</u> .	ā	ā
מאור	M Q Q	M M Q Q	M O	M M Q	M M O O	M M Q Q	M M Q Q
Programme implemented within 14 days of site handover						-	
Awareness champion on site							
HIV/AIDS awareness service							
provider report							
Male condom dispenser							
Sufficient male condoms available							
Male condom dispenser in a highly trafficked area							
Female condom dispenser							
Sufficient female condoms available							
Female condom dispenser in a							
highly trafficked area							
All four types of posters displayed							
Posters in a good condition							
Posters in a highly trafficked area							
Posters displayed on local support							
services: clinic & VCT centre							
Support service poster/s in highly trafficked area							
Support service poster/s in a good condition							

SCHEDULE A

Page 1 of 3

Please indicate the applicable number for the repo	for the reporting period	
Workers on payroll (at PI)		
Sub-Contractors who will be on site		
for longer than 30 days (at PI)		
Workshop attendees		
Number of workshops held		
Scheduled workshops according to		
approved workshop plan		
Booklets distributed		
Male condoms distributed		
Female condoms distributed		
Representative/Agent	Date	
Contractor	Date	

Date of progress inspection: (ccyy/mm/dd)	
Reporting period: (ccyy/mm/dd)	to (ccyy/mm/dd)
Deviations from HIV/AIDS awareness programme plan:	
Corrective actions:	
Representative/Agent	Departmental Project Manager
Date	Date

SCHEDULE A

### **SCHEDULE B**

### HIV/AIDS AWARENESS PROGRAMME: SERVICE PROVIDER REPORT

Reporting period: (ccyy/mm/dd) to	(ccyy/mm/dd)
Number of workshops conducted in reporting period:	
Number of scheduled workshops according to approved wo	rkshop plan:
Deviations from workshop plan:	
State reasons for deviating from workshop plan:	
Corrective actions:	
Service Provider	
Date Da	ate

SCHEDULE B

Page 1 of 3

# HIV/AIDS AWARENESS PROGRAMME: WORKSHOP CONTENT ADDRESSED

DATE	S/M	W/S	W/S	W/S	N/S	M/S	S/M
	M M O O	M Q Q	M M O O	M O	⊢	+	M
Content of workshop:							
(Mark the content included)							
SLO1							
SL02							
SLO3							
SLO4							
SLO5							
SLO6							
SLO7							
HIV/AIDS in							
construction video							
Indicate the duration of the							
workshop in hours							
Total number of Workers							
Indicate workshop venue							

HIV/AIDS AWARENESS PROGRAMME: ATTENDANCE REGISTER

	לכמו וומוויב מווח ווומוסמים מיובווים	יים אוויטיוו לע סטו	ם מאאו חאוומום חם	250				
DAT	DATE W/S W/S W	S/M	W/S	/S	W/S	W/S	M/S	W/S
1		M O	M M O	M M Q	M M	D D M M	M M O	D D M M
2	NAMES							

Page 3 of 3

### **SCHEDULE C**

### **CONTRACTOR HIV/AIDS PROGRAMME REPORT**

Project name:	
Project Location:	
Contract value of project: R	
Department of Public Works Project Manager:	
HIV/AIDS Programme duration: (ccyy/mm/dd)	to (ccyy/mm/dd)
AWARENESS MATERIAL	
Describe location of posters displayed during the programme:	
Comments on posters:	
Indicate total number of booklets distributed:	
Comments on booklets:	
CONDOMS	
Indicate total number of male condoms distributed:	
Indicate total number of female condoms distributed:	
Describe where male condom dispenser was placed:	
Describe where female condom dispenser was placed:	
HIV/AIDS WORKSHOPS	
Indicate the total number of HIV/AIDS workshops conducted:	
Indicate the duration of workshops:	
Indicate the total number of Workers that participated in the HIV/A	IDS workshops:
Indicate the total number of Workers that were exposed to the vide Industry:	eo on HIV/AIDS in the Construction
Comments on HIV/AIDS workshops on site:	

SCHEDULE C

	tions or needs with regard to the HIV/	AIDS awa	reness pro	ogrammes o
Please indicate if your compa focussing on HIV/AIDS aware of HIV/AIDS Workers:	ny has a formal HIV/AIDS policy ness raising and care and support	Yes	No	Currently developing one
	nowledge, you have lost any worker One or more of the following might in Coughing or chest pain Pain when swallowing Persistent fever Diarrhoea		HIV/AIDS Vo Me Me	
humban af HIV//AIDO malata di a	deaths:			
Number of HIV/AIDS-related of				