

# ADDENDUM 1

Item	Description	Unit	Qty	Material		Labour	
				Rate	Amount	Rate	Amount
	<b>BROUGHT FORWARD</b>						
4.8	<b><u>Existing MV Network</u></b> Disconnect & Remove existing 11kV Switchgear & arrange for storage at the warehouse or the Department of Public Works.						
4.9	<b><u>Cessna Substation</u></b> 6 x Panel 11kV Switchboard	No.	1				
4.10	<b><u>Kafee Substation</u></b> 3 x Panel 11kV	No.	1				
4.11	<b><u>Substation - 1</u></b> 4 x Panel 11kV Switchboard	No.	1				
4.12	<b><u>Substation - 2</u></b> 3 x Panel 11kV Switchboard	No.	1				
4.13	<b><u>Steel Work</u></b>  Requires a pedestal in order to be lifted for connection of cables – steel structure to be provided for raising of PREMSET switches in the substations.  100 x 50mm U-channel	No.	4				
	<b>CARRIED FORWARD TO NEXT PAGE</b>						