



COMPLAINT: ID 3281013

DEPARTMENT OF PUBLIC WORKS AND INFRASTRUCTURE: 230 RIGEL STREET

Repair/Replace faulty security installation (CCTV monitoring, intercom, gate motor/rail and electric fencing).

SCOPE OF WORK:

1. Repair CCTV camera monitoring system IP installation and commissioning
2. Repair intercom system to good working condition
3. Replace, network cables, connectors, cameras, UPS power supply, monitors and switches to a good working condition.
4. Check/repair /commission/update firmware version function on the system.
5. Check power specification and power cable properly installed.
6. Check storage media back-up and inspect resolution of the system.
7. Replace faulty gate motor and repair gate track to a good working condition.
8. Repair power supply from the electrical distribution board to the gate isolator.
9. Check that monitor is showing a clear picture and that the brightness and contrast settings are correctly adjusted for day and night viewing.
10. Repair electric fencing as per electrical regulation compliance and provide certificate of compliance.
11. Gate must be painted to a good working condition.
12. Damages due to workmanship and repair work, shall be made good to match the existing.
13. Allow cleaning on-site inspection.
14. Test the system.
15. Job card must be signed on site for job completion.

NB: please note that Guarantee of all replaced materials and operational of the system must be submitted with the invoice.

NB: note that all above pricing must be market related

1. The above installation to be done/replaced/procured as per the existing on site and manufacturer specifications.

1. Guarantee must be attached for Labours (minimum period of 6 months) and equipment/manufacturer (minimum period of 12 Months)

SUMMARY

RESPONSIVENESS CRITERIA:

<input checked="" type="checkbox"/>	Only those tenderers who satisfy the eligibility criteria stated in the Tender Data may submit tenders.
<input checked="" type="checkbox"/>	Tender offer must be properly received on the tender closing date and time specified on the invitation, fully completed and signed in ink (All as per Standard Conditions of Tender).
<input checked="" type="checkbox"/>	1EP or 1EB or higher
<input checked="" type="checkbox"/>	It is estimated that potentially emerging enterprises should have PSIRA registered and experience in working with security installation equipment (CCTV).
<input checked="" type="checkbox"/>	<i>A valid tax clearance certificate for 2026</i>
<input type="checkbox"/>	<i>Wireman's Licence for electrical installation</i>
<input type="checkbox"/>	<i>wireman's Licence for electric fencing installation</i>

The total tender price for this service must include all labour, material and transport required for the proper execution of the work and shall be carried over to the quotation form which must be returned together with this document.

NAME OF COMPANY.....

TENDERER'S SIGNATURE:

ADDRESS

TEL / FAX DATE:

.....

NO		UNIT	QUANTITY	RATE	TOTAL
1	THE FOLLOWING OR THE BELOW WORK HAS TO BE DONE AT 230 RIGEL STREET IN WATERKLOOF (IID-3281013)				
1.1	REPAIR/REPLACE FAULY SECURITY INSTALLATION(CCTV MONITORING,INTERCOM, GATE MOTOR/RAIL AND ELECTRIC FENCING)				
1.2	THE BELOW AND ALL NECESSARY PRECAUTIONS ARE TO BE FOLLOWED AND ADHERED TO AT ALL TIMES. NO WORK NOT INCLUDED IN THE ATTACHED BOQ WILL NOT EXECUTED UNTIL AND UNLESS WRITTEN APPROVAL IS RECEIVED FROM THE PROJECT MANAGER.				
1.3	IT IS THE RESPONSIBILITY OF THE SERVICE PROVIDER TO KEEP SITE SAFE, CLEAN FOR HIS EMPLOYEES AND CLIENTS AND CLEARING OF ALL RUBBLE FROM SITE.				
1.4	THE RESPONSIBLE SERVICE PROVIDER WILL SUBMIT THE FOLLOWING DOCUMENTS TO PROJECT MANAGER AFTER THE COMPLETION OF WORK OR HANDING OVER SITE: THE EXECUTION OF THE WORK KEYS OF THE PROPERTY. CERTIFICATE OF COMPLIANCE AND A CERTIFIED COPY OF WIREMANS LISENCE.				
1.5	THE RESPONSIBLE SERVICE PROVIDER WILL: COMPLY AND ADHERE TO ALL LOCAL AND NATIONAL BUILDING REGULATIONS COMPLY TO OCCUPATIONAL HEALTH AND SAFETY ACT SERVICE PROVIDERSS PERSONNEL ON SITE SHOULD BE IDENTIFYABLE DURING THE PROJECT PERIOD/ DURATION				
2	SECTION A				
2.1	MAINTENANCE OF CCTV CAMERAS AND MONITORING SYSTEM				
2.2.1	SUPPLY AND INSTALL THE FOLLOWING CCTV CAMERAS, COMPLETE WITH MOUNTING BRACKETS, LENSES, HOUSING, FANS, PAN, DRIVES, ETC.				
2.2.2	Replace Bullet cameras 4MP 30M IP Auto day night sensor, 2.8 mm lens	No	16		
2.2.3	Install 10 port switch POE network switch surveillance	No	2		
2.2.4	Replace Cable Cat6 network cable UTP Unshielded Twisted Inclusive connectors	No	1500M		
2.2.5	Replace PVC pipe 20MM solid conduit Inclusive connectors	No	800M		
2.2.6	Install 8 way high surge protector multiplug	No	1		
2.2.7	Sprague 10m x 20mm inclusive connectors	No	1		
2.2.8	Replace Monitor 40 inch for surveillance	No	1		
2.2.9	32 chanel NVR non-POE remote monitoring 200 Mbps	No	1		
2.2.10	UPS 3 kva for surveillance	No	1		
2.2.11	8TB harddrive 30 days video back-up for surveillance	No	1		
2.2.12	Enclosure 114x114x57	No	16		

NO		UNIT	QUANTITY	RATE	TOTAL
2.2.13	HDMI cable 5m	No	5m		
3	TESTING AND COMMISSIONING				
3.1	Test and commission the entire electrical and IP installation and issue the necessary Certificate of Compliance				
	provision of certificate of compliance for electric fencing	No	1		
3.2	CCTV software commissioning	No	1		
	TOTAL COMMISSIONING				
4	INTERCOM				
4.1	IP intercom 1-1 video kit (with sd card and 4 port switch)	No	1		
4.2	touch screen indoor intercom monitor	No	1		
5	Electric fencing				
5.1	Repair Electric fencing 250m inclusive energiser, lightning protection and gate contact	No	1		
5.2	Replace faulty gate motor with a D20 centurion motor kit, Inclusive track and rail assembly	No	1		
6	WARRANTY				
6.1	Make a provision of warranty certificate	No	1	n/a	n/a
7	LABOUR SCHEDULES				
7.1	ARTISAN				
		80 Hrs	1		
7.2	LABOUR				
		80 Hrs	3		
7.3	TRANSPORT/ TRAVELLING AT RS/ KM				
		30Kmx2	8		
7.4	TOTAL				
7.5	ADD 15% VAT				
7.6	GRAND TOTAL				